


Popular Woodworking

Issue 49 June/July 1989

\$3.75

Coloring Wood • Lathe Tool Rack • Yo-Yo • Pushcart • Audio Video Cabinet

Bryce Muir's Wooden Toys for Grownups



Loads of
Projects

Plus

PullOut™ Plans

Wall Cabinet
Colonial Footstool





IMPORTS, INC.

**OUR SUMMER SALE IS ALWAYS
A BIG HIT. AT THESE PRICES
IT'S NOT SURPRISING!**

SALE PRICES EXPIRE SEPT. 10TH, 1989.

6" x 47" JOINTER




1 H.P. motor. All cast-iron construction. Weighs 260 lbs.

MODEL G1182

Regularly \$335.00

ONLY \$310.00

8" x 65" JOINTER



1½ H.P. motor. All cast-iron construction. Weighs 460 lbs.

MODEL G1018

Regularly \$665.00

ONLY \$625.00

**6/9 COMBINATION
SANDER**



6"x48" belt, 9" disc. ¾ H.P. motor. Machine weighs 140 lbs.

MODEL G1014

Regularly \$195.00

ONLY \$175.00

**6/12 COMBINATION
SANDER**



6"x48" belt, 12" disc. Quick belt release lever. Weighs 155 lbs.

MODEL G1183

Regularly \$395.00

ONLY \$335.00

15" PLANER



New 2 speed model. 2 H.P. motor with magnetic switch. Weighs 500 lbs.

MODEL G1021

Regularly \$695.00-without stand

**NOW - ONLY \$695.00 AND
WE'LL THROW IN THE STAND**

20" PLANER



3 H.P., 2 speeds. Weighs 900 lbs.

MODEL G1033

Regularly \$1295.00

ONLY \$1175.00

20" DISC SANDER



2 H.P. pedestal model. Weighs 500 lbs.

MODEL G1548

Regularly \$975.00

ONLY \$895.00

¾ H.P. SHAPER



½" spindle, precision cast-iron table, reversing switch. Weighs 155 lbs.

MODEL G1024

Regularly \$245.00

ONLY \$225.00

**10" HEAVY DUTY
TABLE SAW**




Precision ground cast-iron table and wings. 1½ H.P. motor. Weighs 255 lbs.

MODEL G1022

Regularly \$345.00

ONLY \$325.00

**10" SUPER H. D.
TABLE SAW**




Precision ground cast-iron table and wings. 3 H.P. motor. Weighs 500 lbs.

MODEL G1023

Regularly \$850.00

ONLY \$825.00

18" BANDSAW



1½" re-sawing blade capacity. 2 H.P. motor. Shipping weight is 380 lbs.

MODEL G1012

Regularly \$625.00

ONLY \$575.00

3 H.P. SHAPER



2 spindle speeds plus reversing switch. Comes with ½", ¾" and 1" spindles. Weighs 450 lbs.

MODEL G1026

Regularly \$850.00

ONLY \$825.00

**All above prices are F.O.B. our Bellingham, WA or Williamsport, PA Warehouse.
OUR 1989 FULL COLOR CATALOG IS LOADED WITH GOODIES AND IT'S FREE!
CALL US & EXPERIENCE EXCELLENCE**

CALL TOLL FREE (FOR ORDERS AND CATALOG REQUESTS ONLY)

EAST OF THE MISSISSIPPI: 1-800-523-GRRR
(717) 326-3806

← (For Orders & Catalogs Only) →
← (For Inquiries & Customer Service) →

WEST OF THE MISSISSIPPI 1-800-541-5537
(206) 647-0801

Popular Woodworking

Issue #49 June/July 1989

Volume 9, Number 1

Coloring Wood *by Thomas Wisshack* 30

Toys for Grownups *by Ken Textor* 34

A Popular Woodworking Project
Colonial Footstool *by John A. Nelson* 53

Project for the Shop
Lathe Tool Rack *by Jerry Ernce* 54

Swedish Savers *by Shirley Stebbins* 56

Computer-Assisted Furniture Design
Part 1: Drawing in 3-D *by Alan Marks* 58

A Popular Woodworking Project
Wall Cabinet *by Devore O. Burch* 63

A Popular Woodworking Project
The Audio/Video Cabinet *by Hugh Foster* 66

A Popular Woodworking Project
Pushcarts *by Kingsley Hammett* 69

A Popular Woodworking Project
A Wine Rack/End Table *by Ray Day* 72

Focus on Carving
Carving Carousel Animals
Part 2 *by William H. McMaster* 77

The Turner's Page
Yo-Yo *by John A. Nelson* 83




Mike Godsil

30



Jerry Ernce

54



Alan Marks

58

Columns

- 4 Clear Cuts
- 8 Book Reviews
- 14 Videoscene
- 16 The Business End
- 20 Tried and True
- 86 Out of the Woodwork

Departments

- 5 Tricks of the Trade
- 25 Tests & Comments
- 75 Calendar
- 84 Classified Market
- 85 Index to Advertisers

On the Cover

Bryce Muir makes complicated wooden toys using many different wood species for the colors in each piece. This King of Beasts sitting at the King of Instruments is one piece from a symphony orchestra that Muir is building for a client. The lion is made of redwood and his piano is rosewood. To see more of these marvelous "Toys for Grownups," turn to the story on page 34.



Ken Textor

I'll admit it, I haven't had much experience with wood finishing. I choose between either a certain brand of lacquer or a certain brand of Danish oil for my finishing needs and don't stray far from these basics. I think I've stuck with these two products that seem to "do the job" because I'm afraid to try anything else. I hear about other finishes and procedures and often feel like I'd need to be a chemist to work with them. Everybody's got his own secret formula—arrived at after years of experimentation with different materials.

But then it occurred to me that these guys aren't scientists; they're just woodworkers like me. They must have a reason for using other products, trying other concoctions. The reason is that there really are differing results from these experiments, and the differing qualities of these results work in interesting ways with different woods.

When I realized that the science of finishing wood is just one ongoing experiment—that there really is no one "right" way—it opened my mind to trying other ways myself.

So I'm learning. I'm reading about it, talking to other guys, and finding writers to share their experiments in the pages of *PW*. We'll try to run at least one article on the subject in each issue from now on. They're not intended as the final words on finishing; each is just the telling of what worked in one shop. My Beloved is shouting, "Tell them the brand names! The people want to know what did the job," so we will. When you see a brand name, it's not because they bought ad space from us but because that's what was used. The two old standbys of mine that I mentioned are Deft and Watco. If I've learned anything though, it's that everybody has a favorite.

We begin our experiments with Tom Wisshack's article "Coloring Wood." He discusses stains and dyes and "mixing your own" to get the color you want. Of course, there is always the school of thought that prefers the natural color of wood, so we follow this up with a fellow who uses different wood species as his palette, creating colorful "Toys for Grownups."

This should be interesting....

David M. Camp

Popular Woodworking Staff

Editorial

David M. Camp *Editor*

Wien Chod *Managing Editor*

Jeffrey Burr *Associate Editor*

J.A. Newell *Editorial Assistant*

Contributing Editors

William H. McMaster

Hugh Foster

Alan Marks

James Barrett

Distribution

Gertrude Berkowitz

Circulation

Suzanne Eriksen

Customer Service

May Fayne

Advertising

Debra Nowak *Advertising Manager*

Tel. (415) 671-9852

Popular Woodworking (ISSN 0884-8823) is published bimonthly by EGW Publishing Co., 1300 Galaxy Way, Concord, CA 94520. Second-class postage paid at Concord, California and additional mailing offices. POSTMASTER send address changes to *Popular Woodworking*, 1300 Galaxy Way, Concord, California 94520.

SUBSCRIPTIONS:

A year's subscription (6 issues) is \$17.00; two years' worth (12 issues) is \$30.00; outside of U.S.A. add \$5.00/year. Send all subscriptions, advertising inquiries and correspondence to:

Popular Woodworking
1300 Galaxy Way
Concord, CA 94520

Please allow 6 to 8 weeks for delivery.

All rights reserved. Reproduction without prior permission is prohibited. Copyright ©1989 by EGW Publishing Co.

Unsolicited manuscripts, photographs, artwork and other materials are accepted, but *Popular Woodworking* cannot assume responsibility for these materials. Writers who submit articles do so with the understanding that the work is original and done by them. The author warrants that submissions and subsequent printing of any materials in *Popular Woodworking* magazine do not infringe upon the rights of any third party and agrees to be totally liable for such claims. Submissions must be accompanied by a self-addressed, stamped envelope for return.

The opinions expressed by the authors do not necessarily reflect the policy of *Popular Woodworking*. Editorial correspondence is encouraged, and may be edited for publication.

Advertisers and agencies assume complete liability for the copy in their advertisements and warrant that it does not infringe on the copyrights or trademarks of others. Advertisers and agencies agree to hold publisher harmless from any liabilities arising out of such infringement and to reimburse publisher for any and all expenses and costs incurred by publisher by reason of such infringement.

Corporate officers: Wayne Lin, President
Produced and printed in U.S.A.

Tricks of the Trade

"Tricks of the Trade" shares readers' tips for making woodworking tasks easier and safer. If you've come up with a trick that would help other woodworkers, send it to "Tricks of the Trade," c/o Popular Woodworking, 1300 Galaxy Way, Concord, CA 94520. Include any photos or sketches that help illustrate your idea (we'll redraw them). We pay \$25 for each trick we publish.


Glue Brush Correction

In the last issue of *PW* we published a tip from John E. Leeds of Ojai, CA about his method for making glue brushes from wooden scrub brushes. In describing how to cut apart the tufts, we wrongly suggested that this be done on a table saw. Such a practice would be unsafe and difficult at best. Mr. Leeds uses a band saw, presenting the back of the brush to the blade and holding it at the appropriate angle to cut between the tufts. The thinner blade of the band saw makes it easier to avoid the metal staples, and holding on to the small pieces is not such a risky proposition. We regret the error.

Editor

Band Saw Wheels

I needed to be able to move my band saw easily around my shop but have it remain stationary when I was using it, so I came up with this way of attaching wheels to it. I made a wooden axle that extends about 1/2" beyond the spread of the legs and attached




some 8" wheels (cut from a scrap sink cutout) to it with lag screws. I bolted this assembly to the left side of the stand with the wheels about 1/4" off the ground. To move the machine, I tip it onto the wheels like a hand truck. Big wheels make it easier to go up a few stairs, if necessary.

W. K. Walthers
Rio Rancho, NM

Using the Band Saw with the Lathe

Here's a great way to make duplicate parts on the lathe. Lay out the pattern on two perpendicular sides of each piece. Carefully band saw to the pattern lines on one side and then tape the sawn pieces back onto the stock with masking tape, so you can cut out the pattern on the other side. Discard the waste, and



mount the stock on the lathe. When the wood is spinning, the outline of the pattern will show up as a kind of "ghost" line against the squareness of the stock. Carefully turn down the pattern. This technique works best on thicker spindles, but it can be used on any diameter.

Don Kinaman
Phoenix, AZ

Ferrules for Tool Handles

The brass ends of the large, cartridge-type electrical fuses make great ferrules for tool handles. These large fuses are discarded by electricians, contractors, industrial plants, apartment buildings and many other establishments when they burn out. To make the ferrule, bore a 1/2" hole in the end before you cut it off. Size your tool handle to fit, and secure the ferrule with a punch mark or a small screw.

Devore O. Burch
Fort Worth, TX

ORDER YOUR BACK ISSUES OF *POPULAR WOODWORKING* TODAY!

Check out our exciting woodshop plans and techniques.
You're not just ordering a magazine,
you're ordering 4-6 sets of plans you can use!

- | | | |
|---|--|---|
| #1 ☐ May 1981 \$1.00
<i>Sound and Its Effects</i>
<i>Goodwill's Contract Shop</i> | #28 ☐ Dec/Jan 1986 \$2.95
<i>Cedar Hope Chest</i>
<i>The Shamisen Process</i>
<i>Blind-Wedged Peg Joint</i> | #38 ☐ Aug/Sep 1987 \$2.95
<i>Dovetail Joinery</i>
<i>Connecticut River Valley</i>
<i>Desk on Frame</i> |
| #2 ☐ July 1981 \$1.50
<i>Assembly Furniture</i>
<i>Solar-Heated Wood Dryer</i> | #29 ☐ Feb/March 1986 \$2.95
<i>Making a Piano Bench</i>
<i>Signaling Sailor Whirligig</i>
<i>Carving the Human Head</i> | #39 ☐ Oct/Nov 1987 \$2.95
<i>Relief Carving</i>
<i>Make Your Own Handscrew</i>
<i>Clamps</i> |
| #6 ☐ April/May 1982 \$1.50
<i>Making Wooden Boxes</i>
<i>Abrasive Belt Cleaner Test Report</i>
<i>Table Saw Hints</i> | #30 ☐ April/May 1986 \$2.95
<i>Mortise and Tenon Joinery</i>
<i>Teak Serving Cart</i>
<i>Trestle Table and Stool</i> | #40 ☐ Dec/Jan 1988 \$2.95
<i>Making Box Joints on the</i>
<i>Table Saw</i>
<i>Biplane Walker</i> |
| #7 ☐ June/July 1982 \$1.50
<i>Interview with Sam Maloof</i>
<i>Make a Maloof Table Pedestal</i>
<i>Create a Maloof Finish</i> | #31 ☐ June/July 1986 \$2.95
<i>Make Your Own Solar Kiln</i>
<i>Making a Watch Clock</i>
<i>Penultimate Patio Chair</i> | #41 ☐ Feb/March 1988 \$2.95
<i>Making a Jewelry Chest</i>
<i>Wooden Buckets</i>
<i>Dry Sink TV Cabinet</i> |
| #8 ☐ Aug/Sept 1982 \$1.50
<i>Starting a Woodworking Business</i>
<i>Table Saw Maintenance</i>
<i>Rockwell Speed Block Sander</i> | #32 ☐ Aug/Sep 1986 \$2.95
<i>Martha Thompson's</i>
<i>Magical Mirrors</i>
<i>Power Carver's Tool Cabinet</i>
<i>Building a Wine Rack</i> | #42 ☐ April/May 1988 \$2.95
<i>Designing for</i>
<i>Dimensional Change</i>
<i>Garden Cart</i>
<i>Diamond Hones Review</i> |
| #9 ☐ Oct/Nov 1982 \$1.50
<i>Staining Wood</i>
<i>Quest for the Thinnest Blade</i>
<i>Marketing</i> | #33 ☐ Oct/Nov 1986 \$2.95
<i>How to Make a Serving Bowl</i>
<i>Home Entertainment Center</i>
<i>Art of Sandblasting Wooden Signs</i> | #44 ☐ Aug/Sep 1988 \$2.95
<i>Baby Dresser</i>
<i>Peeled Branch Settee</i>
<i>Marionette</i> |
| #10 ☐ Dec/Jan 1983 \$1.50
<i>Selecting a Portable Sander</i>
<i>Sealacell Wood Finish</i>
<i>Test Report</i>
<i>Evolution of an All-Wood</i>
<i>Box Design</i> | #34 ☐ Dec/Jan 1987 \$2.95
<i>Universal Table Saw</i>
<i>Veneered Vertical Tambours</i>
<i>Build-It-Yourself</i>
<i>Backgammon Board</i> | #45 ☐ Oct/Nov 1988 \$2.95
<i>Corner Pewter Hutch</i>
<i>Country Sconce</i>
<i>Massachusetts Lowboy</i> |
| #11 ☐ Feb/March 1983 \$1.95
<i>Model Making with Laser</i>
<i>Technology</i>
<i>Estimating and Bidding</i>
<i>Wood Finishes</i> | #35 ☐ Feb/March 1987 \$2.95
<i>Building a Butcher Block</i>
<i>Work Center</i>
<i>Ladder-Back Rocker</i> | #46 ☐ Dec/Jan 1989 \$3.75
<i>Walnut Dining Table</i>
<i>Child's Cupboard</i>
<i>Japanese Handsaws</i> |
| #25 ☐ June/July 1985 \$2.25
<i>Octagonal Pedestal Table</i>
<i>In-The-Round Carving</i>
<i>Building the Strip Canoe</i> | #36 ☐ April/May 1987 \$2.95
<i>Folding Picnic Table</i>
<i>Carving an Arabian</i>
<i>Stallion-Part I</i> | #47 ☐ Feb/March 1989 \$3.75
<i>Bending Wood</i>
<i>Duck Basket</i>
<i>A Tilting Mirror</i> |
| #27 ☐ Oct/Nov 1985 \$2.95
<i>The Computer Desk</i>
<i>Alternate Bowl-Turning Techniques</i>
<i>Cradle Table with Magazine Bin</i> | #37 ☐ June/July 1987 \$2.95
<i>Interview with James Krenov</i>
<i>Plate Joiner Test Report</i>
<i>Koa Dinner Table</i> | #48 ☐ April/May 1989 \$3.75
<i>Victorian Table</i>
<i>Decorative File Cabinet</i>
<i>Carving Carousel Animals</i> |

**All available back issues for
only \$70.00.**

This price includes postage and handling.
(Add \$8.00 postage for foreign countries.)

Add \$2.00 postage and handling for up to ten copies.
If ordering more than ten copies, add \$2.00 per lot of ten.

Please send my back issues to:

Name _____

Address _____

City _____ State _____ Zip _____

☐ Personal Check

☐ Visa/Mastercard


Card# _____ Exp. Date _____

Send your order and payment to:

Popular Woodworking Back Issues, 1300 Galaxy Way Suite #8, Concord, CA 94520.

Octagon Picnic Table

Plans \$16.75 (MI res. add 4% tax)



Easy-to-follow plans, instruction sheet and step-by-step pictorial. Features include, walk-through seating, ability to seat eight people in a sociable circle, the strength of a bolted construction.

Specialty Furniture Designs of Michigan

797 West Remus Road, Dept. PW-5
Mt. Pleasant, MI 48858

VISA/MC accepted

ROUTER BITS TUNGSTEN CARBIDE

CORNER ROUNDING

	1/4"	\$14.50
	3/8"	\$15.50
	1/2"	\$17.00

COVE BITS

	1/4"	\$12.50
	3/8"	\$13.75
	1/2"	\$14.50

ROMAN OGEE BITS

	5/32"	\$18.25
	1/4"	\$20.00

- Quantities Limited •
- Satisfaction Guaranteed
- Order Now •

Skycroft Tools, Inc.

Box 418P1

Myersville, MD 21773

1-800-767-4747, 24 hrs/day, 7 days/wk



West Coast Veneer Store

P.O. Box 06243
Portland, Oregon
97206-0015
Phone: (503) 777-1848

RETAIL VENEER Clipping & Jointing


\$2.50 sample kit available
(refunded with first order)

Send for free price list.

Clayton Oscillating Spindle Sanders.

For large or small shops. Ideal for contour sanding. Quick change drums. 1/2" to 4". Satisfaction guaranteed. Covered by 1 yr. warranty. 4 models to choose from. For more information write:

Clayton Enterprises
2505 W. Dewey Rd.
Owosso, MI 48867



Made In U.S.A.

Catch The ROADRUNNER... The Fastest Blade Running!

Designed for today's wood-working professionals, contractors and serious D-I-Y'ers, the **ROADRUNNER** is the ultimate performance blade.

SPEED: An aggressive hook angle combined with the "thinnest" kerf and plate make **ROADRUNNER** the fastest cutting blade of its kind sold in America. (For both soft and hard woods.)

FEED: The ultra-thin kerf and special body expansion grooves allow the **ROADRUNNER** to make straight, accurate cuts in all directions of the wood grain.

SMOOTH: The large number of teeth provide smooth, splinter-free cuts even in the most difficult materials.

So catch the **ROADRUNNER** and our **Money-Back Guarantee** if you're not fully satisfied.

Call or write for a free catalog and the name of your local dealer.

OLDHAM-UNITED STATES SAW

P.O. Box 1, Burt, NY 14028
1-800-828-9000 (Nationwide)
1-716-778-8588 (New York State)
716-778-8625 (Fax)

100%
CUSTOMER
SATISFACTION
GUARANTEE.

ROADRUNNER
"THE PROFESSIONAL'S CHOICE."

SPEED

The Extremely Thin Kerf and Aggressive Hook Angle Make for a VERY FAST

Manufactured by
Oldham Saw
Burt, NY

SMOOTHNESS

The Large Number of Teeth Provide Smooth Splinter-Free Cuts.

* SANDPAPER *

NO GIMMICKS — GREAT PRICES

BELTS: GRITS ASSORTED

SHEETS: (9 x 11) PRICE

UNLESS OTHERWISE SPECIFIED

CABINET PAPER

1 x 30	\$.69 ea	3 x 24	\$.80 ea	50 / pk	100 / pk
1 x 42	.69 ea	3 x 27	.83 ea	40-D	\$16 / pk \$30 / pk
1 x 44	.69 ea	4 x 21 1/4	.91 ea	50-D	15 / pk 27 / pk
2 1/2 x 16	.73 ea	4 x 24	.94 ea	60-D	14 / pk 25 / pk
3 x 18	.74 ea	4 x 36	1.14 ea	80-D	13 / pk 23 / pk
3 x 21	.77 ea	6 x 48	2.98 ea	100 thru 150C	12 / pk 21 / pk
3 x 23 1/4	.80 ea	2 1/4 x 80	2.47 ea		

OTHER SIZES ON REQUEST

FINISHING PAPER

NO LOAD PAPER

	50 / pk	100 / pk
80-A	\$ 9 / pk	\$16 / pk
100 thru 280A	8 / pk	14 / pk
180-A thru 400-A	\$10 / pk	\$18 / pk

WET / DRY PAPER

PRESSURE SENSITIVE

ADHESIVE DISCS!

6"	\$1.06 ea	* OTHER ITEMS *
8"	1.99 ea	* WIDE BELTS
9"	2.46 ea	* ROLLS
10"	3.05 ea	* FLAP WHEELS
12"	4.45 ea	* PUMP SLEEVES
15"	6.95 ea	

* JUMBO CLEANING STICK *
\$8.80

SEND MAIL ORDERS TO:
ECON-ABRASIVES
P.O. BOX P865021
PLANO, TX 75086

NATIONAL 1-800-367-4101

IN TEXAS (214) 377-9779

*TEXAS RES. ADD 7% SALES TAX

*SHIPPING CHARGES ADD \$4.75

Book Reviews

by Hugh Foster

John Scheeler: Bird Carver by Roger Schroeder, ©1988 (Stackpole Books, Cameron and Kelker Streets, Harrisburg, PA 17105) 288 pp., hardcover, \$49.95

This is a large, colorful, attractive book. Not a "how-to" book of the type most interesting to woodworkers, this will appeal more to lovers of "bird art" and art lovers in general. Great artists deserve homage of some sort, and the many color plates in this book indicate that John Scheeler is as worthy of homage as any sculptor who lived in America.

The book was to have been a

Hugh Foster is an English-teaching woodworker in Manitowoc, Wisconsin.

co-written study of the advanced techniques of bird carving as practiced by Scheeler, but Scheeler died when the book was just under half finished. Author Schroeder knew that the material he had was good, so he shifted focus. Now the first two-thirds of the book are devoted to the history of bird carving and people's remembrances of John Scheeler and his work. The history of bird carving in America is interesting, and this book illuminates the interdependencies between many of the major carvers as well as their dependence upon the patronage of wealthy collectors and museums. Scheeler's memory is well served by this book. Anyone who isn't awed by his bird carvings just isn't paying

attention. A few years ago I reluctantly attended an exhibit of bird art, and I remember being moved at how some of these sculptures seemed to defy even the law of gravity. Schroeder and Scheeler reveal part of the "trick" to that here. If you are a good bird carver and aspire to greatness, this book will be must reading for you, not only for the techniques presented, but for the extensive bibliography and listing of collections. Woodcarvers won't be the only people who'll want to have this handsome volume gracing their coffee tables.

Classic Architectural Birdhouses and Feeders by Malcolm Wells, ©1988 (Malcolm Wells, P.O. Box 1149, Brewster, MA 02631) 96 pp., paperback, \$9.95 postpaid

I would normally have little interest in a book about birdhouses. The introduction to this one tells why as well as I could: most birdhouses are just six ill-fitting boards sort of nailed together. Knowing from his previous work that controversial architect Malcolm Wells has too much integrity to tell us to do that, I picked up a copy of his book. He's got lots of good plans here, but more interesting to me is his discussion about the attitude one needs when planning bird—or human—houses. He says we shouldn't be slave to fashion; too much of our architecture expresses our uncertainty. In a way, he says, anything goes. Or does it? How much artificiality should we try to foist upon ourselves and the creatures around us? The birdhouse should be our attempt to bridge the chasm between the human and the wild; Wells suggests that if we don't owe our best shot to the birds, then we owe it to the birds' Creator. He'd have us use natural materials. Never pay for more than the nails. Help keep the organic movement alive. He advises us to remember Thoreau's suggestion that "All work passes directly out of the hands of the architect into the hands of nature, to be perfected."

According to Wells, birdhouses and feeders must meet these criteria: they should be safe from attack, they should be well-ventilated and well-drained, they

The Best Blade Is No Secret...It's A WIZARD!

A sharp departure from conventional blade design, the WIZARD is the smoothest cutting carbide blade ever manufactured!

ELIMINATES TEAROUT OR SPLINTERING: Large bevel angles (30°) produce lower cutting pressures—virtually eliminating tearout.

SANDED-LIKE SIDES: Shallow side clearance angles enable the WIZARD to cut with the entire side of the carbide tip (not just the top), creating a planing action which leaves the wood with a smooth, sanded-like finish.

100% CUSTOMER SATISFACTION GUARANTEE: If the WIZARD isn't the smoothest cutting blade you've ever used, return it for a full refund.

Available in heavy duty plate for stationary equipment and mitre-thin plate for mitre boxes.

Call or write for a free catalog, sample cuts and the name of your local dealer.

OLDHAM-UNITED STATES SAW

P.O. Box 1, Burt, NY 14028
1-800-828-9000 (Nationwide)
1-716-778-8588 (New York State)
716-778-8625 (Fax)

100%
CUSTOMER
SATISFACTION
GUARANTEE.

WIZARD



should be easy to hang, and easy to open for inspection and cleaning. Combining all these might be more difficult for most of us than it first appears. Wells' last caveat about these projects is "Get out there and build something beautiful."

This book is hand-lettered, hand-illustrated, and hand-published. It's sold more or less only by the author. The book is as attractive—and as offbeat—as some of his birdhouses. I hope it sells well, for I trust that Wells will do interesting, organic things with his proceeds from it. Frankly, I hope he does some more books—having sampled and enjoyed his attitudes, I'd love to see a book of his home furnishings...items for standard rooms and for the home office. Whatever the topic, I look forward to sharing the next batch of ideas from one of the most profoundly individual designers of our age.

The Woodworking Shop by the Editors of *American Woodworker*, ©1989 (Rodale Press, 33 E. Minor St., Emmaus, PA 18049) 95 pp., paperback, \$9.95

Fine Woodworking has been publishing anthologies like this for years, and people like me who save the magazines instead of buying these books are probably making a mistake. In the ceaseless rush of bimonthly publication, errors creep into articles almost so regularly that cynical readers are, doubtless, convinced that we put them there on purpose. When it comes time to anthologize the articles, the errors have usually been repaired. This is particularly important when we're considering project plans without double checking the math and the logic. But often when we're reading the magazines (*American Woodworker* in this case), we can pretty easily overlook the articles about tools, or we can look at them very quickly, resolving to get back to them "another day" that never comes. The 27 articles collected here treat planes and scrapers (6 articles), power tools (10 articles), maintenance and setup of tools and equipment (3 articles), useful shop-made tools (6 articles), and single pieces about dust collection, finishing, and shop

safety. I found only the article about plate joiners to be superficial and out-of-date. A couple of the other articles didn't impress me when I initially read them in the magazine, but the power of the individual articles is magnified as they are brought together. The consistent attitude seems more obvious when like topics are brought together. Every magazine that's able should bring together an anthology like this one—just as often as possible.

Make Your Own Handcrafted Doors & Windows by John Birchard, ©1988 (Sterling Publishing Company, 2 Park Ave., New York, NY 10016) 288 pp., paperback, \$14.95

and

Contract Joinery by Ken Austin, ©1988 (Linden Publishing Company, 3845 North Blackstone, Fresno, CA 93726) 169 pp., paperback, \$15.95

Contract Joinery, first published in England in 1981, has become something of a classic in Great Britain. This text is designed to help student and apprentice craftspeople pass the exams required there. The book is about panelling, partitions, doors, windows, handrails, staircases, and even ecclesiastical projects. Each chapter includes a series of questions and answers which will aid craftspeople who are preparing to do "one-off" work. One can learn a great deal about the mathematics that underlies woodworking projects from this book; indeed, there is enough good material here that I wish I could recommend it more heartily. Unfortunately, it's written in the "castor oil" style of textbook presentation, as if to say "This is important stuff, dammit, so there's no reason to try to make it palatable." For me, this unattractive book just makes me consider Birchard's *Make Your Own Handcrafted Doors & Windows* more seriously.

Of course, all good doors and windows are made of wood, but many of us have never thought much about making these things. Just looking at the cover of Birchard's book should be enough to make us reconsider our doors and windows. In our spare time, for our own homes, we should experiment with some of the beautiful doors and windows


that are explored in this handsome book. While Birchard doesn't give us as much math as does Austin, his book appears to do a better job of explaining what sorts of things have to happen around doors and windows if they are to be effective. His is the book to buy, for he will inspire you to build better doors and windows for the place where you live, even if Austin's probably gets the facts more nearly right. Since I regard woodworking as an inspired craft, I'm convinced that inspiration will do most builders more good than a bunch of very practical math. Once inspired, we'll know enough to go get the math.

The Complete Illustrated Guide to Everything Sold in Hardware Stores by Tom Philbin & Steve Ettlinger ©1988 (MacMillan Publishing Company, 866 Third Ave., New York, NY 10022) 432 pp., hardcover, \$24.95

Steve Ettlinger got fed up with the guessing games he had to play every time he went into a hardware store asking for items he was unfamiliar with; it seemed the clerks were also unfamiliar. One day he was told by a carpenter to get a tool he had never heard of before, a "cat's paw." Sold the wrong tool by a sarcastic clerk, it took him a week to do a job that should have taken only a couple of hours with the right tool. When he failed to find a "cat's paw" listed in any of the how-to books in his extensive collection, he decided to do his own. Even with his background as a book producer and magazine editor, it took two years and a whole crew of able people to prepare this book. One old-time hardware manufacturer admitted that he'd "been in the business for over forty years and still hadn't figured it out." Every real hardware store should have a copy of this book somewhere near the service desk; clerks should be made to study it during lulls in the store's activity, and it should always be ready for the customers who are shopping for "whatchamacallits" or "thingamajigs."

The book is laid out the same way a hardware store or home center is. While there is a section about hand tools, specialized tools for particular products or projects (such as masonry tools) are

1/2" SHANK CARBIDE-TIPPED ROUTER BITS MOULDING PLANE PROFILES




SPECIAL OFFER:

SET OF ALL FOUR BITS \$99.95


ORDER ITEM #166, SET OF FOUR
QUICKLY PRODUCE CLASSIC TRADITIONAL MOULDINGS
BITS ARE SHOWN FULL SIZE - 2 FLUTE CARBIDE TIPPED.

MULTI FORM*




Unlimited Moulding
Patterns


FINGER JOINT*



RAISED PANEL*




LOCK MITRE*



*shown smaller than actual size.

To order by Master Charge or Visa Toll Free
7 Day - 24 Hour Order Service, Call
1-800-533-9298 or send check to:
MLCS Ltd., P. O. Box 4053P-A, Rydal, PA 19046

CONTROL THE SPEED OF YOUR ROUTER



**ROUT AT THE SPEED
THAT GIVES THE BEST
RESULTS WITH THE
WOOD AND BIT YOU
ARE USING!**

- LESS TEAR OUT
- STOPS BURNING
- FEED AT COMFORTABLE RATE
- BETTER, SAFER RESULTS
WITH LARGE DIAMETER
PANEL-RAISING BITS
- LESS WEAR ON BITS
- LESS NOISE AND SOFTER STARTS
AT LOWER SPEEDS

INTRODUCTORY PRICE \$39.95
Order Item #200 POSTAGE PAID
VALUE OVER \$100.00

FEATURES:

- SPEED ADJUSTABLE FROM FULL SPEED TO 0 RPM
- 3 POSITION TOGGLE SWITCH: VARIABLE - OFF - FULL SPEED
- FULL HORSEPOWER AND TORQUE AT ALL SPEEDS
- GO BACK AND FORTH FROM ANY PRE-SET SPEED TO FULL
SPEED AT THE FLIP OF A SWITCH
- WORKS WITH ALL ROUTERS 3 HP OR LESS
- 120V 15 AMP
- GIVES YOUR ROUTER A FEATURE ONLY AVAILABLE ON
ROUTERS THAT COST OVER \$500.00

EASY TO USE — SIMPLY PLUG IN SPEED CONTROL AND PLUG YOUR
ROUTER INTO THE SPEED CONTROL — TURN DIAL FOR BEST RESULTS.
(SPEED CONTROL HAS A CLIP THAT CAN BE WORN ON YOUR BELT OR
HUNG ON WALL OR LEFT LOOSE.)

- REDUCES SPEED ELECTRONICALLY WITHOUT REDUCING TORQUE;
ELECTRONIC FEED-BACK MAINTAINS SPEED BY INCREASING VOLTAGE
TO MOTOR AS LOAD INCREASES.


MAKE BEAUTIFUL RAISED PANEL DOORS . . . WITH YOUR 1/4" ROUTER!

SET ALSO AVAILABLE IN 1/2" SHANK — \$79.95 — Item #154
Professional production quality bit makes it quick and easy to
produce matching rails and stiles — the panel raising bit with
ball bearing guide makes the raised panel
perfect every time.

Regular value Over \$150.00

ORDER ITEM #054 for 1/4" Shank Set
(Includes all bits shown)


SALE PRICE \$69.95 FOR COMPLETE SET



RAISED PANEL BIT SUPPLIED WITH BALL BEARING


2" Large Diameter

CARBIDE TIPPED
1/4" Shank



REVERSIBLE COMBINATION RAIL AND STILE BIT

(For making matching rails and stiles in
raised panel doors, etc.)
Works with stock from
1 1/16" to 7/8" thick



CARBIDE TIPPED — TWO FLUTE
1/4" SHANK
supplied with Ball Bearing

To order by MasterCharge or Visa Toll Free
7 Day - 24 Hour Order Service, Call
1-800-533-9298 or send check to:

MLCS Ltd., P. O. Box 4053P-C, Rydal, PA 19046

BRIDGEWOOD®

WOODWORKING MACHINERY

ACT NOW — SPECIAL PRICES VALID WHILE QUANTITIES LAST

◆ DUST COLLECTORS AND ACCESSORIES

REDUCERS (STEEL)

R-43	... \$9.50
R-54	... 9.50
R-65	... 10.50
R-64	... 10.50

ELBOWS (STEEL)

EL-3	... \$4.00
EL-4	... 4.50
EL-5	... 5.00
EL-6	... 5.50

STRAIGHT METAL DUCT

IN 2 FOOT SECTIONS	
MD-3	... \$3.60
MD-4	... 4.00
MD-5	... 4.60
MD-6	... 5.60

SMOOTH FLOW TEE (STEEL)

T-443	... \$15.50
T-544	... 16.00
T-555	... 16.00
T-654	... 17.50

CAST ALUM. GATES

	PRICE EA.	PRICE EA. 4 OR MORE
GA-3	\$14.00	\$11.50
GA-4	15.00	12.50
GA-5	19.50	15.50
GA-6	24.00	19.50

HOSE CLAMPS

HC-3	... \$1.90
HC-4	... 2.40
HC-5	... 3.00
HC-6	... 3.15

Y-FITTINGS (STEEL)

Y-433	... \$16.00
Y-444	... 16.00
Y-555	... 16.50
Y-544	... 16.00

H.D. FLEX HOSE - PVC

	PRICE PER FOOT 10 FT. MIN.
BWFH-3	... \$1.90
BWFH-4	... 2.50
BWFH-5	... 3.55
BWFH-6	... 4.45

PLANERS

BW-15P
\$795


3 H.P.
2 SPEED
15" PLANER
WITH STAND
AND
DUST HOOD
AND MOTOR

- BW-12P — 12" x 6" portable . \$ 349
 - BW-15P — 15" x 6" econ. 795
 - BW-20P — 20" x 8" econ. 1295
 - ★ BW-16PV — 16" x 7" H.D. 2495
 - ★ BW-20PV — 20" x 7" H.D. 3195
 - ★ BW-508 — 20" x 9" INDUST. . 3895
 - ★ BW-612PV — 24" x 9" INDUST. 6195
- ★ — WITH USA MOTORS

◆ JOINTERS

- BW-6J - 6"x42" 1 HP, w/STD . \$ 299
- BW-8J - 8"x66" less motor 699
- BWJ-872 - 8"x72" H.D., 2 HP,
U.S. motor 1695
- BW-12J - 12"x80" H.D., 3 HP,
U.S. motor 2495
- CE-40N - 16"x100" INDUST., 7½ HP
U.S. MOTOR 4395

15" SCROLL SAW



- 2" Thick cutting capacity
- 15" Throat depth

\$119



BW-6J
\$299

6" x 42"
table
1 H.P. MOTOR
WITH STAND

◆ BANDSAWS

BW-14BS
14" x 6" cap., ¾ HP
\$299

BW-18BS
18" x 12" cap., 2 HP
\$795


PBS-500
20" x 12" cap., 2 HP
w/Carter guides
\$1595

SHAPERS

BW-1S
½" spindle . . \$269
BW-2S
½", ¾" spindle
2 HP \$795
BW-3S
½", ¾", 1" spindle
3 HP \$1295

BW-511TS
sliding table, tilt spindle
3 HP \$2695
BW-512TS
sliding table, tilt spindle
5 HP \$3495
TC-50
sliding table, industrial
7½ HP \$4695

EXTRA LARGE
20" x 24"
TABLE SIZE
2 H.P.
MOTOR



BW-2S
\$795

ALL PRICES
QUOTED F.O.B.
YORK, PA

WILKE

MACHINERY COMPANY

WE ARE A FULL LINE MACHINERY COMPANY — FAMILY OWNED AND OPERATED — BUY WITH CONFIDENCE
3230 SUSQUEHANNA TRAIL • YORK, PENNSYLVANIA 17402 • TELEPHONE 717-764-5000 • FAX 717-764-3778

CALL OR SEND \$1.00 FOR COMPLETE 52-PAGE CATALOG

Energy Saving Dryer Vent Closure



Dietrich's

Box 777 • Valley City, ND 58072
TOLL FREE 1-800-437-4780
 Qty. _____ at \$19.95 plus
 \$3.50 shipping & handling
 VISA & MASTERCARD WELCOME

Name _____
 Address _____
 City _____
 State _____ Zip _____
 Daytime Phone _____

- ★ Saves up to 10% on energy bills during cold weather.
- ★ New patented closure design incorporates a floating shuttle that rises when dryer is running and drops back down to seal opening when not running.
- ★ When open allows moist air and lint to escape without plugging.
- ★ When closed keeps out cold air, dust, rodents, bugs, birds, etc.
- ★ Satisfaction guaranteed or you may return for a full refund.
- ★ Installs in minutes.
- ★ May paint to match your home.
- ★ Made in the U.S.A.
- ★ High impact material withstands extreme temperatures.
- ★ Adaptable to most bathroom and range vents.

FREE!

Orders will receive a
 bonus gift of the
 pocket utility knife.



Book Reviews

continued from page 9

found in their own section. The more common items in each section are placed nearer the front of the section. The book leaves out heavy construction materials, esoteric cabinetmaking tools, housewares, electronics, gardening items, and hobby materials, among other things; there's also precious little "how-to" advice. The tips here echo the advice you might get from a "good" hardware clerk. The book also points out the amount of thinking that must precede every hardware purchase, for "there's no such thing as 'just a paintbrush.'"

The book opens with the commonest hand tool of all, the hammer—in a multitude of varieties—and closes with fire extinguishers. Between the two are nearly everything you'll need from the hardware store and, no doubt, a few things you didn't even know they had. If you think you already know the names and everything else about most of the goodies in the hardware store, you may be amazed at just how much you learn from this book. **PW**

FREE!




78 full-color pages of exclusive, innovative tools and accessories for the woodworker, do-it-yourselfer and hobbyist, all guaranteed! Mail in the coupon today...or call toll-free

800-654-7817 (Ext. 107).

() Please rush my FREE catalog!

Name _____
 Address _____
 City _____
 State _____ Zip _____
 Mail to: Leichtung Workshops, Dept. 107
 4944 Commerce Pky. • Cleveland, OH 44128

The workbench companion



WATCO DANISH OIL FINISH

Watco Danish Oil Finish can be your ideal workbench companion for all those wood finishing projects around the house. Easy to use with beautiful results... Watco Danish Oil gives wood that natural hand-rubbed look and feel with long-lasting durability.

Watco is IN the wood not on it like surface coatings. And because Watco is deep within the wood, it's spot-repairable and simple to maintain.

Ideal for furniture, paneling, cabinets, doors, antiques and trimwork. Watco is also safe to use on butcher blocks, cutting boards and children's furniture and toys.




Choose from 10 beautiful finishes: Natural, and Light, Medium, Dark and Black Walnuts, Iced Iced Oak, Cherry, Golden Oak, Fruitwood and English Oak. For more information on Watco Finishing Products...call or write

Watco-Dennis Corporation
 19610 Rancho Way
 Rancho Dominguez, CA 90220
 (213) 635-2778

CARBIDE TIPPED ROUTER BITS

PROFESSIONAL PRODUCTION QUALITY

1000's SOLD TO READERS OF FINE WOODWORKING

BEST CUT BEST PRICE	ITEM NO.	DESCRIPTION	RADIUS	LARGE DIAM.	CUTTING LENGTH	PRICE
	#01	COVE 1/4" R	1/4"	1"	1/2"	\$13.00
	#02	3/8" R	3/8"	1-1/4"	9/16"	14.00
	#03	1/2" R	1/2"	1-1/2"	5/8"	15.00
	#04	ROUND OVER 1/4" R	1/4"	1"	1/2"	\$15.00
	#05	3/8" R	3/8"	1-1/4"	5/8"	16.00
	#06	1/2" R	1/2"	1-1/2"	3/4"	19.00
	#07	ROMAN OGEE 5/32" R	5/32"	1-1/4"	15/32"	\$18.00
	#08	1/4" R	1/4"	1-1/2"	3/4"	20.00
	#11	3/8" RABBETING	Deep 3/8"	1-1/4"	1/2"	\$14.00
	#09	1/8" (KERF) SLOT CUTTER		1-1/4"	1/8"	14.00
	#10	1/4" (KERF) SLOT CUTTER		1-1/4"	1/4"	14.00
	#12	45° Chamfer	45° Angle	1-1/2"	5/8"	\$15.00
	#15	Raised Panel	20° Angle	1-5/8"	1/2"	\$25.00
	#35	1/4" V Groove 90°	1/4"	1/4"		\$ 8.00
	#36	3/8" V Groove 90°	3/8"	3/8"		9.00
	#37	1/2" V Groove 90°	1/2"	1/2"		11.00
	#16	3/8" Dovetail 9°	3/8"	3/8"		\$ 7.50
	#80	1/2" Dovetail 8° (For Leigh Jigs)	1/2"	13/16"		12.00
	#17	1/2" Dovetail 14°	1/2"	1/2"		8.50
	#18	3/4" Dovetail 14°	3/4"	7/8"		10.50
	#19	CORE BOX (ROUND NOSE) 3/8" Core Box	3/16"	3/8"	3/8"	\$11.00
	#20	1/2" Core Box	1/4"	1/2"	11/32"	14.00
	#21	3/4" Core Box	3/8"	3/4"	5/8"	18.00
	#056	Tongue & Groove (FOR WOOD THICKNESS FROM 1/2" to 1")		1-5/8"	1"	\$30.00
						
	#24	1/4" Straight Bit	1/4"	3/4"		\$ 7.00
	#25	5/16" Straight Bit	5/16"	1"		7.00
	#26	3/8" Straight Bit	3/8"	1"		7.00
	#27	1/2" Straight Bit	1/2"	1"		7.00
	#28	3/4" Straight Bit	3/4"	1"		10.50
	#13	1/2" FLUSH TRIM	1/2"	1"		\$ 8.50
	#14	3/8" KEY HOLE (This Bit Only HSS)	CUTS 3/8" KEY HOLE FOR FLUSH MOUNTING PICTURE FRAMES, ETC.			\$ 8.50

WHEN ORDERING ANY THREE OR MORE DEDUCT \$1.00 EACH
ALL PRICES POSTAGE PAID

Professional Production Quality • 1/2" Ball Bearing Pilot
• 1/4" Diameter Shanks x 1-1/4" Long • One Piece Construction
• Two Flute Thick High Quality Tungsten Carbide Tips

To order by MasterCard or Visa Toll Free

7 Day—24 Hour Order Service Call

1-800-533-9298

or send check to:

MLCS Ltd., P. O. Box 4053P, Rydal, PA 19046

NEW! UNIQUE! AND TRULY PERSNIPPITY™

PERSNIPPITY WOOD

OIL FINISH

DRY POWDER CONCENTRATE
(PAT. PEND.)

"THE SECRET IS IN THE T.L.C."

● MIXES WITH ANY COOKING OIL!
(VEGETABLE, PEANUT, OLIVE, GRAPE SEED,
SUNFLOWER, SAFFLOWER, YOU NAME IT!)

- NON-TOXIC, CHILD SAFE!
- NO OBNOXIOUS, LINGER-
ING ODORS!
- UNLIMITED SHELF AND
STORAGE LIFE!
- ECONOMICAL! NO WASTE:
MIX AS MUCH OR AS LITTLE
AS YOU NEED PER JOB!
- IDEAL FOR HOBBIES, AN-
TIQUES, TOUCH-UPS AND
CRAFTS!
- QUICK AND EASY SOAP AND
WATER WASH-UP!
- DOUBLE YOUR MONEY BACK GUARANTEE! IF FOR ANY REASON
YOU ARE DISSATISFIED WITH "PERSNIPPITY" WOOD OIL FINISH PERFOR-
MANCE, WE'LL HAPPILY REFUND WITH DOUBLE YOUR MONEY BACK!


● 3 BEAUTIFUL COLORS!
LIGHT WALNUT, DARK WALNUT,
AND MAHOGANY.

ONE
GALLON \$9.95
EQUIVALENT,
DRY POWDER
CONCENTRATE
PER
PKG.

ADD \$1.50 POSTAGE AND HANDLING.
CAL. RESIDENTS PLEASE ADD 7% SALES
TAX.

TO ORDER CALL COLLECT: 619-433-3652
OR WRITE:

"TRULY PERSNIPPITY"
607 NORTH HORNE, OCEANSIDE, CA. 92054



CLAMP 'N
TOOL GUIDE

ALL-IN-ONE...

- Bar Clamp
- Straight Edge
- Fence
- Power Tool Guide

As a FENCE or GUIDE, it attaches ten times faster than 'C' clamping and won't surface mar wood. As a BAR CLAMP, the unique low profile jaws enable you to clamp butt-jointed corners (down to 1/2" material) and also allow edge clamping. These clamps always lay flat for easy assembly set-ups. World's fastest, most versatile bar clamp!

TWO SIZES AVAILABLE:

24" Grip.....\$22.95
50" Grip (panel size).....\$32.95


ORDER TOLL-FREE!

1 800 428-3809 (Inside California)


1 800 228-1806 (Outside California)

Master Card, Visa, Check or Money Order. In California, add 6% sales tax.


WE PAY FREIGHT within Continental U.S.A.




CROSS CUTTING
GUIDE (no "C" clamps)



ASSEMBLY CLAMPING



INSTANT FENCE
(fully adjustable)



SHORT JAWS ALLOW
EDGE CLAMPING

Rodman
RODMAN & COMPANY, INC.

965 W. VENICE BLVD.
LOS ANGELES, CA 90015

Videoscene

by Alan Marks

The Stanley Armoire with Bruce Marchard and Terri-Lee Hysell, ©1988 by The Stanley Works, Advertising Services, Box 1800 Armoire, New Britain, CT 06053, 35 minutes, \$14.95

The claim of this tape is that it, along with the Stanley brochure that goes with it and a parcel of Stanley hand tools and hardware, will enable you to nail and glue together an armoire. Three types to choose from—and you don't even need a single major power tool! Not even a table saw, honest. Your friendly neighborhood lumber yard will rip your hard-to-handle

Alan Marks is a cabinetmaker in Carmel Valley, California, and a contributing editor to PW.

Popular,
Pocket-size
MINI-LIGNO
\$110
Only

Come see us
at Booth #2538
Woodworking
Machinery Fair
in Anaheim, CA

Incl. Case,
Batteries
and Pins
for 3/16" and 7/16"
Measuring Depth.

Also available as:
Mini-E: Range 6-36%
Mini-C with external probe.



Everybody Knows

that the moisture content of wood is crucial. Moisture related defects such as surface checks, warpage, cracks, loose joints, foggy finishes, etc., can ruin the best piece ever built.

Everybody Knows

moisture defects are irreversible. Therefore don't waste money and time on wet wood. Use a moisture meter to be sure you work only with dry wood.

Ask for free brochure on moisture meters (range 4-30%, 4-60%) and accessories to monitor air or kiln drying.


Wood Moisture Meter
from Lignomat USA

P.O. Box 30145
Portland, OR 97230
Tel: 800-227-2105 503-257-8957

Best Japanese Scroll Saw Available

COMPARE FEATURES AND PRICE WITH ANY OTHER MAKE

- Arm pivots up 25° so you can start cutting anywhere in the workpiece
- Blade Changing: Very Quick and Easy due to Arm Pivot
- 4.4 Amp, Condenser Type, Ball Bearing Motor (110V, 60 Hz) Gives Plenty of Power for Toughest Jobs
- Special Guide Rollers Prevent Blade Buckling
- Air Nozzle Blower Clears Chips and Dust from Work
- 10" x 10" Cast Aluminum Table Tilts 20° Right
- 20" Throat Depth handles 1 meter workpiece
- Cuts up to 2" in hard wood, 3/8" in metal. 10 6", Plain End Blades Included. 7 Styles Available.
- 1050 Strokes per Minute
- Machine weighs 66 lbs.
- Low Noise Level; Non-Vibrating; Easy-to-Maintain
- Made by IIDA KOGYO, one of Japan's leading producers of production woodworking machinery



ONLY
\$399.00
Delivered by UPS
to your door.

CALL TOLL FREE: 800-447-7770 • VISA / MC / AMEX

Dollar Trading Corp. (Est. 1953) • Dept. PW06A
P.O. BOX 8433 • GRAND RAPIDS, MI 49518
MI and CT Buyers, Please Add Sales Tax
90 Day, Hassle-Free, Money Back Guarantee

plywood sheets into manageable panels for a nominal fee, and your Stanley hand tools will do the rest. Imagine the challenge of cross cutting large plywood panels with a hand saw! Takes a good eye and a steady hand, but you can do it! Provided you don't care too much about tight-fitting joints and such.

As I hope you can tell, I have a few reservations. Furthermore, it is my opinion that anyone who assumes that a framing square (even a Stanley) will draw an accurate 90° line deserves whatever pickle he gets himself into as a result.

Clearly the emphasis of this tape is not on producing a quality piece of furniture, but on selling Stanley tools and hardware. This is all done very slickly. This is the first video on woodworking I have seen that had a script and a commercial actress. Not that I'm complaining. Terri-Lee Hysell is a nice-looking lady. (Could hers possibly be a stage name with a concealed innuendo? High-sell? Hmmm...) She adds an element of feminine charm to the do-it-yourself world, something it has lacked until now.

One fortuitous thing for this video was the choice of an armoire as a sales vehicle because it is a piece with so many applications, for clothing, storage of household items, or as an entertainment center, to name a few. I am surprised nobody thought to present an armoire project before this and I hope someone does it again, next time with more integrity and minus the sales hype.

Refinishing Furniture with Bob Flexner, ©1988 by The Taunton Press, Box 355, Newtown, CT 06470, 60 minutes, \$29.95 (Rental: \$14.95)

This excellent video comes with a companion booklet that adds significantly to the viewer's knowledge of the subject, instead of merely paraphrasing the lessons on the tape.

In tried and true pedagogical fashion, Bob Flexner stimulates the viewer's curiosity for knowledge by raising questions which are then answered as instruction proceeds. He tells us at the start that he has run across many curious notions about what refinishing furniture entails. The subject has been grossly oversimplified, he says. One prevalent misconception is the idea that an entire piece has to be refinished because of a few surface blemishes. Another myth has it that important differences distinguish one commercial furniture polish from another.

He then piques the viewer's interest by showing many of the various ways in which furniture can be finished, including some less desirable treatments. He shows how to revive various finishes instead of stripping them, demonstrating the use of soap and water, and TSP (Trisodium Phosphate) and wax. I particularly appreciated his method of wrapping a glob of wax in a cloth for easy application.

In the section on stripping, Flexner strongly recommends using mineral spirits or lacquer thinner instead of water to rinse off the methyl ethyl ketone (MEK) stripper in order to protect the wood from damage. Of course, this can get expensive and it creates noxious vapors.

In his demonstration using MEK, Flexner did not clearly

explain why stripper should not be worked over once applied. He mentions stirring up wax, but the viewer gets the impression that it is the wax dissolved from the old finish that somehow produces a negative effect. If I am not mistaken, stripping compounds contain wax which floats to the surface and acts as a barrier for preventing the evaporation of solvent. It is this barrier of wax, I believe, which should not be broken or disturbed to enable the solvent to remain active. Otherwise, there was lots of good advice and information in this section!

In the next section of the video, we learn how to prepare a blemished surface for finishing, including how to remove surface defects, black rings and water stains. He demonstrates methods for bleaching and of course, the old standby, sanding. A useful tip from Bob Flexner: fold your strip of sandpaper in thirds accordion-like so its segments will not slip against one another. That one was worth the entire purchase price to me.

In the following section, when Flexner talks about staining, he presents the most detailed exposition I have run across in a video. He speaks of pigments and dye and oil stains, and demonstrates bleaching with potassium dichromate and with a two-part bleach for altering the color of new replacement parts in order to match the original wood.

The next unit, on sealing and filling, is also a honey; but my favorite contains information on glazing, wherein is revealed the secret of How to Produce the Fabled Patina of Age using Japan

Drier. For me, Japan Drier is the missing link. I wish I had been informed of its magical properties when I used to color/blend patches of new wood into old on repair jobs, rather than mixing and applying layers of concentrated watercolor pigments and clear acrylic lacquer from spray cans. The problem with this was that I could never de-gloss the lacquer properly to match existing gradients of sheen. And then there was the lengthy drying time of the pigments to contend with. As a result of seeing this video, I plan to collect various colors of Japan Drier to have on hand, and I'll stop using lacquer. I am convinced that tung-oil varnish will make it possible to match older finishes.

From time to time during this tape I found myself getting annoyed at the way Flexner rushed from topic to topic without even taking a breath, so to speak. I kept hoping the producer would interject an occasional musical interlude to slow him down, but such relief was all too rare. It was as if someone had allotted only a sixty-minute time limit for ninety minutes' worth of material.

There are good sections on oil, varnish, shellac, and lacquer, and an excellent one on adjusting and repairing finishes, with which the video concludes. I am familiar with French polishing, but French padding was a new process to me. This finish, which contains both nitrocellulose lacquer and shellac, is apparently both easier to put down and more water-resistant than French polish, which contains only shellac. **PW**

SAVE\$ SAVE\$ SAVE\$ SAVE\$ SAVE\$ SAVE\$ SAVE\$ SAVE\$

DANIELS DISCOUNT TOOLS

Free Shipping

SAVE TIME SAVE CASH

FAMOUS TOOLS FOR LESS

412-655-7541

CALL TOLL FREE

LARGE SELECTION

1-800-537-3274

Milwaukee Tools 					
0213-1	Heavy-Duty Cordless Driver/Drill			\$149.77	
5371-1	Heavy-Duty Magnum Hammer-Drill Kit			\$177.99	
6508	Heavy-Duty Sawzall			\$129.77	
Makita 					
6012HDW	Cordless Driver-Drill			\$108.99	
6093DW	Cordless Driver-Drill Kit			\$138.80	
5007NBA	7 1/4" Circular Saw			\$119.77	
8419B-2W	3/4" Hammer Drill			\$123.77	
Bostitch 					
N80C-1	Nailer Coil 4D-12D	Recon		\$299.77	
N70SB-1	Nailer Stick 6D-10D	Recon		\$229.77	
N12B-1	Nailer Coil Roofing 7/8" to 1 3/4"			\$368.77	
N60FN-2	Nailer - Finishing 1 1/4" - 2 1/2"			\$339.77	
Porter-Cable 					
9850	Cordless 3/8" Driver Drill Kit			\$139.77	
7556	1/2" 2 Speed Reversing Right Angle Drill Kit			\$169.77	
659	Reversing Drywall Driver			\$79.77	
690	1 1/2 HP Router			\$129.77	

Free Catalog

Hours 8-4 EST

Call Now 1-800-537-3274

SAVE\$ SAVE\$ SAVE\$ SAVE\$

Many other famous tools at LOW LOW prices.

Same Day Shipping

SAVE\$ SAVE\$ SAVE\$ SAVE\$

Service contracts are certainly nothing new in our society. In some commercial sectors, service contracts have been the backbone of the maintenance effort for many years. During recent times, service contracts, and their first cousin, extended warranties, have become common options when buying cars, mechanical equipment, electronic devices and numerous other items. One area in which I haven't seen them is woodworking, yet they are probably needed here as much or more than in many other fields.

The nature of wood is such that we can't predict exactly what it's going to do in the long run. Even when we make a piece of furniture out of high quality, well dried, carefully selected wood that looks beautiful, there is no guarantee that six months from now it won't shrink, crack, buckle, fade or do some other inconsiderate thing which proves very distressing to both the person who made it and the person who bought it. There is also a seemingly endless parade of other things that can go wrong involving finishes, glues, joinery, hardware, moulding, edge-banding and who-knows-what-else that may decide to act up somewhere down the line. When this happens, we get a call from the unhappy customer, and we are more or less expected to correct the irregularity, generally without charge. In this situation, somebody will come out on the short end. If a charge is made for the repair, adjustment or whatever, the customer loses. If no charge is made, you lose. I suggest that incidents such as this could be turned into a win-win situation through the use of a service contract or extended warranty.

Basically, both service contracts (sometimes called maintenance agreements) and extended warranties begin when the original warranty expires. These plans are sold as options and generally can be bought either at the time of original purchase or at any time up to the expiration of the warranty. These options vary in what they cover, but

generally a service contract provides routine scheduled maintenance such as cleaning, lubrication and adjustments. Also, all repairs which may be required are performed without additional charge for either materials or labor, regardless of the cause—with the exceptions of abuse, misuse or, in some cases, accidental damage. Extended warranties commonly do not provide any routine scheduled maintenance, but protect the purchaser against repair costs in the event of failure of certain specified parts, components or assemblies. Extended warranties usually cover a specific period of time and are not renewable. Service contracts, although they may cover a specific period of time, are commonly sold by the year, and are renewable, perhaps indefinitely. There are many variations of service contracts and extended warranties, but the intent is always the same: to provide the buyer with insurance against things going wrong, and to provide the seller with compensation to cover after-sale service.

Although I've never seen such contracts offered by woodworkers, I see no reason why they wouldn't work. From the standpoint of the woodworker, the benefits would be: 1) additional income from the sale of follow-up service insurance, 2) continued contact with the customer, enhancing the prospects of future sales, 3) ability to monitor the performance of the goods, 4) early detection of problems in the goods, resulting in lower repair costs, and 5) promotion of good will through continued attention to the customer's needs.

From the buyer's point of view, the main benefits are: 1) peace of mind and the assurance of continued service being performed on the goods without fear of additional charges, 2) the reduced likelihood of problems occurring in the product, and 3) the maintenance of the original appearance and level of performance of the product.

So, how would this actually work? First of all, you'll need to make, as accurately as possible, an assessment of the probable and possible things that could be required for the continued service and repair of whatever goods you are producing. Then decide which you're

willing to assume cost-free responsibility for and what you would need to charge as an annual service contract fee in order to cover your costs for the *probable* service items, plus an appropriate allowance to cover a portion (say one third) of the *possible* service or repair items. You need to understand that with any insurance policy (which this is, in effect), each side is gambling. The customer is gambling that repairs or maintenance will be needed and wants to avoid having to pay extra for them. You are gambling that the repairs won't be needed, which means that you will make an additional profit through the sale of the contract or extended warranty.

Let's look at an example of how this might work. Suppose you produce a dining table for someone. It would be reasonable for you to guarantee the table to be free of defects in material or workmanship for a period of 90 days, which is sufficient time for most problems to show up. Providing a longer guarantee would be inadvisable because you would be assuming continued responsibility for wood—an imperfect, natural material which, despite your knowledge, expectations and woodworking abilities, might do something weird and unpredictable that would make both you and your customer unhappy. The basic idea of standing behind your work has some merit, but let's not get ridiculous about it. Instead, you could offer, at any time up to the expiration of the 90-day guarantee, either a service contract or an extended warranty.

How do they differ? First of all, figure out what could go wrong with this table, or what might be needed to keep it in first-rate condition. Then, decide what would be appropriate to offer in the way of a protection plan. An extended warranty would typically protect against the malfunction or failure of specific named things for a certain non-extendable period of time. An extended warranty is non-extendable because the maintenance provided is corrective only, and allows the overall condition of the article to deteriorate over time, as all things do. If the warranty is renewed, you would become responsible for an increasing number of repairs

continued on page 18

As the owner of Grand Openings in Oakland, California, Peter Good manufactures doors. He also gives seminars at national woodworking shows on the business aspects of running a small shop.

TRANSPOWER

We are NOT NO. 1 in catalogue and advertising.


We are NO. 1 in QUALITY, PRICE & WARRANTY - You check! CALL 1-800-654-7702



SHAPER/ROUTER MACHINE

Extra Large Table


Only \$664



1", 3/4" & 1/2" spindles, 1/4" & 1/2" router chucks, 3HP motor, 25"x22" mirror table, dovetailed miter gauge, 8000/11000 reversible 2 speeds, 3" spindle travel, precision steel fence, 6" insert opening, side & top spring hold-down, dead collar for irregular surface, 34" height, 425 lbs. Optional roller extension.

12" AUTO PLANER


Sale \$328



2HP, 115V, 12"x6" capacity, 1/8" max cut, 0.2"6" range, 26.2 FPM rate, 8000 RPM, 16000 cuts, 2 feeders & extensions, all ball bearings, 65 lbs.

DUST COLLECTOR


Sale \$284



2HP, 3 intake holes (4"), 1250 CFM, 21"x37" base w/casters, 19"x36" bags, 78" height, 6.04 static pressure at 6", 210 lbs.

15" AUTO PLANER


2 speeds \$664



15"x6" capacity, 2 feeders, 3HP, 18 AM, motor, 3 blades, 1/8" FMP rates, 1/4" max. cut, 0.2"6" range, 5100 RPM/15300 cuts, 20"x16" table, 2 extensions, 520 lbs.

8" JOINTER

Sale \$625



2HP, 9"x68" extra long bed, 3 blades, 2 v-belt drive, 1/2"x8" cut, 36" fence, 4500 RPM, precision lead screw, built-in chip chute, 500 lbs.

20" AUTO PLANER


Sale \$1175



5HP, 20 AMP motor, 20"x8" capacity, 4 blades, 1/8" FMP rates, 1/4" max. cut, 0.25"8" range, 20000 cuts/min, 26"x20" table, 2 feeders & extensions, 980 lbs.

6"x12" SANDER

Sale \$362



1 1/2HP, 6"x48" vertical/horizontal belt, 12" sanding disc, tilting tables 7"x17", 3600 RPM, quick release belt, 180 lbs.

10" TABLE SAW

Sale \$840




W-Biesmeyer Fence \$990

3HP, top precision fence, double lock, micro adj, 3" max cut, 36"x27" mirror table, T-slot, cast iron construction, 4200 RPM, 1/8" arbor, 33.5" rip capacity, 500 lbs.

90" EDGE SANDER

Sale \$394



1 1/2HP, 6"x90" belt tilts 90°, 28"x10" cast iron table, T-slot miter gauge, quick belt release design, heavy duty stand, adjustable fence, 260 lbs.

TCM Industries, Inc. 322 Paseo Sonrisa, Walnut, CA 91789

Inquiries (714) 594-0780

WOODWORKER II best on TABLE SAW

With this ONE ALL PURPOSE blade 40 Teeth and 1/8" kerf. SMOOTH RIP & CROSSCUT 1" - 2" ROCKHARDS and SOFTWOODS with smooth-as-sanded surface. PLY-VENEERS oak/birch crosscut with NO BOTTOM SPLINTER.

- Mostly 1/8" kerf 15" ATB and 20" face hook (easyfeed).
- DOUBLE HARDER and 40% STRONGER CARBIDE.
- Ends blade changing (does rip, combo and crosscut).
- Ends scratchy saw cuts (for the rest of your life).
- Ends second step finishing (jointing and sanding).
- Ends cutting 1/16" oversize to allow for RESURFACE.

Buy and sharpen ONE blade instead of 3, 24T rip, 50T Combination, 80T Crosscut.
• Strongly recommend our .001 flat large stiffener - dampener against outside of blade for smoothest, quietest, cuts by this and any other blade.
• Use 30T if ripping mostly 2" - 3" hardwoods.
• Side wobble held .001 - others .004/.010 is common!
• RAISE for THICK woods, LOWER for THIN woods and perfect cut everything!

List	Sale	List	Sale
12" x 40T x 1"	\$183	8" x 40T 3/32"	\$136
12" x 30T x 1"	162	30T 3/32"	115
10" x 40T	156	7 1/4" x 30T 3/32"	112
30T	135	7" x 30T 3/32"	112
9" x 40T	146	5/8" holes, boring to 1 1/4"	49
30T	125	+ \$7.50 - SHIPPING \$3.50	

ALSO help your SEARS blade, FREUD, PIRANHA, JAPANESE THIN SAW, DML, LEITZ, etc.

FOR BETTER CUTS!

Use our large 1/8" DAMPENER STIFFENERS, against one side 6" - \$25 Parallel and flat to .001

- 5" - 24 Stops vibration, flutter, cutting noise and blade ring.
- 4" - 21 Tryable and RETURNABLE. Full cash refund.

FREE dampener or \$10.00 off with any 2nd blade.

5/8" holes bore to 1 1/4" \$7.50 extra. Others available. Add \$2.00 Shipping.

WE RECOMMEND OUR FACTORY SHARPENING 2-3 DAYS ON THESE AND ALL MAKES OF CARBIDE TIP SAWS. SHIP IN UPS (500 grit microscoped) 10 x 40T \$14.25, 60T \$16.83. Add return UPS \$3 or 2nd Day Air \$5.

NOW... ORDER the one blade that will outlast you! (10-20 sharpenings possible).

SAISFACTION GUARANTEED OR FULL CASH REFUND.

40 years of fine American saw making & sharpening.

FORREST MANUFACTURING COMPANY, INC.
250 Delawanna Ave., Clifton, NJ 07014

WOODWORKER I Best on RADIAL SAW

(table saw too) This ALL PURPOSE blade gives scratch free POLISHED cuts on all materials RIP or CROSSCUT up to 2".

- All 60T and 3/32" THIN kerf 20" ATB and 5" face hook.
- DOUBLE HARDER and 40% STRONGER carbide.
- THIN KERF:

Saves 1/3 wood loss on each cut, radial or table.
Feeds easy when used for moderate rip and crosscut on table saw.

Reduces "JUMP IN" greatly for better "PULL-CONTROL". Practically eliminates bottom splinter on RADIAL CROSSCUT.

- Totally stops ALL bottom and top splinter on ply veneers in push-cut mode on RADIAL.
- Our STIFFENER STRONGLY RECOMMENDED AGAINST outside of blade only for best cuts.

Made and serviced in USA for your benefit.

List	Sale
12" x 60T x 1" or 5/8"	\$198
10" x 60T x 5/8"	162
9" x 60T x 5/8"	156
8" x 60T x 5/8"	150
New 8 1/4" x 40T x 5/8"	136

RYOBI RA200 TS200 MAKITA 5008 NBA
HITACHI PSM6 PORTER CABLE 368-1

Lasercut DADO KING MULTITOOTH dado set cuts ALL 1/4" - 13/16" flat bottom grooves WITH or CROSSGRAIN all woods and VENEER PLYS. NO SPLINTERING due to unique 4T and 8T fillers and 24T outside saws. NOTHING LIKE IT IN THE USA!!



8" x 24T x 4T x 8T fillers	13/16" set \$299	5/8" set \$209
8" x 24T x 4T	3/4" set 249	1/2" set 179
10" x 24T x 4T x 8T fillers	13/16" set 362	

FOR MCP MELAMINE & LOW PRESSURE LAMINATES
8" Neg-shear 24T x 2T or 4T fillers \$259
10" Neg-shear 24T x 2T or 4T fillers 314
5/8" holes - boring extra - SHIPPING \$5.50

For TABLE and RADIAL SAW

(very good on chop saw too!) STOP SPLINTERING those SPLINTERY OAKS, HARDWOOD VENEERS and thin 2 SIDE LAMINATES ON PARTICLE BOARD. FOR FASTER FEED RATES AND MORE ABSOLUTE SPLINTER CONTROL.

DURALINE HI-AT

Note: Fine Woodworking Editorial Nov./Dec. 1988 No. 73 pg. 65 S.N. recommends high alternating top bevel (ATB) thin kerfs and large blade stiffeners for smoothest cuts on RADIAL SAWS, etc.



Jim Forrest, President and designer, microscoping cutting edge.



All 5/8" hole. Boring up to 1 1/4" \$7.50 extra - Larger holes - time basis. Shipping \$3.50.

HI-AT Price List

8" x 80T	\$202	14" x 80T	\$232
9" x 80T	207	100T	266
10" x 80T	207	16" x 80T	262
12" x 80T	212	100T	294
100T	253		

All CARBIDE is THE HARDEST OF THE C-4 grades and 40% STRONGER, NOT WEAKER!! For 50% to 300% longer life!

FREE dampener or \$10.00 off with any 2nd blade.

CHOPMASTER SERIES FOR MITER SAWS for tight, smooth, splinter-free miter-joints. NEW AVAILABLE SIZES.



List	Sale
Hitachi 8 1/2" DeWalt 8 1/2"	8 1/2" x 60T x 5/8" \$179 \$ 89
Delta	9" x 80T x 5/8" 204 99
Ryobi-Makita	10" x 80T x 5/8" 207 109
Ryobi-Makita	14" x 100T x 1" 266 160
Hitachi	15" x 100T x 1" 277 164

Use small stiffener where possible.

We honor Amex, Visa & MasterCard, Money Orders, Personal Checks and COD's To order BY MAIL clip ad, circle choices and enclose payment. Specify Dept. PW when ordering. PHONE TOLL FREE!

1-800-526-7852 (In NJ: 201-473-5236)

FORREST

because of the continuing deterioration process.

In contrast, a service contract provides preventive maintenance, a program which cares for and continuously restores the article to an approximation of the condition when new. An extended warranty might cover such things as failure of joinery, separation of veneers and loosening or malfunctioning of hardware for a period of five years. Such a plan would not cover any other things which might go wrong such as failure of the finish, checking, splitting, cracking, warping or color changes in the wood, or anything resulting from damage or misuse. An extended warranty such as this would automatically terminate at the end of the five-year period or upon sale or transfer of the table. If you felt pretty confident that no more than, say, two service calls would have to be made during the five-year period to correct named discrepancies—and that those problems could each be rectified within two hours

including travel time, without taking the table back to your shop—then a reasonable cost for the five-year extended warranty on the table might be 30% of the original price. If repairs other than those named in the extended warranty are needed, they should be charged for at your current rates.

Service contracts are usually sold for a period of one year and can be renewed year after year, at whatever your current price for such things is at the time of renewal. A service contract covers more than an extended warranty, and under it there would normally be a provision that you will correct everything that needs correcting and also provide cleaning, finish restoration and preventive maintenance at specific stated intervals, usually once a year. Also all labor and materials would be included in the price of the contract. The ever-present exception, of course, is any work to correct problems from damage or misuse, which is charged for separately. A reasonable price for a service contract of

this type would be 15% of the price of the table per year. Each year, however, the contract price is based on the current price of the table if you were to make it again, not the original price. Service contracts, in order to be renewable, must be continuously in effect from the expiration of the original 90-day guarantee and could not be purchased once a lapse in coverage occurs. Otherwise, because of neglect and non-maintenance, you could be in for much more work than you bargained for. Also, unexpired service contracts generally remain in effect when the product is sold or transferred.

The concept of service contracts and extended warranties would go a long way toward improving performance, appearance and useful life of products made by woodworkers, and would also provide fair compensation for follow-up service which otherwise might be awkward to charge for. In that respect, it would bring woodworkers one step further toward making a decent living through sensible business practices. **DW**

Special Limited Offer - Expires Oct. 31, 1989

FORSTNER BITS: WHAT THEY CAN DO FOR YOU WHY OURS ARE BEST AND LEAST EXPENSIVE

Forstners, the only wood bits that can:



- Bore any arc of a circle at any angle
- Make entry holes in veneer, end grain, and knots
- Leave glass smooth walls and a flat bottom hole

Pros use them:

- For starting rabbets or grooves
- To make pocket holes to attach rails to tops, and rods, spindles and stretchers to legs
- To make blind holes for plugs and
- Through holes for locks

Best Because:

- Machined from high-carbon alloy steel
- Precision ground cutting edges, lifters and brads
- Hardened to HRC 50
- Mirror polished head to maintain splinter free entry holes



Inexpensive Because:

- Manufactured in China where the US dollar is still king
- Imported directly by us
- Our sincere desire to bring back sensible prices for woodworking tools

SPECIAL INTRODUCTORY OFFERS

BUY A 7-PC FORSTNER BIT SET (1/4, 3/8, 1/2, 5/8, 3/4, 7/8, 1") and we will give you FREE a 7-PC Brad Point Drill Set, a \$12.00 value.

Shp./Hndl. \$4.50

ORDER #10-1426 only **\$34.99**

BUY A 16-PC FORSTNER BIT SET (1/4, 3/8, 1/2, 5/8, 3/4, 7/8, 1, 1-1/8, 1-1/4, 1-3/8, 1-1/2, 1-5/8, 1-3/4, 1-7/8, 2, 2-1/8") and we will give you FREE a 25-PC Brad Point Drill Set in Metal Index, a \$29.95 value. Shp./Hndl. \$9.50

ORDER #10-1441 only **\$124.99**




All Forstner Bits fit 3/8" chucks and are 3-5/8" overall. FOR A FREE PRICE LIST OF INDIVIDUAL SIZES, SEND NAME AND ADDRESS TO: P.O. BOX 964, RIDGEFIELD, CT 06877

CALL TOLL FREE: 800-447-7770 • VISA / MC / AMEX

Dollar Trading Corp. (Est. 1953) • Dept. PW06 • P.O. BOX 8433 • GRAND RAPIDS, MI 49518
MI and CT Buyers, Please Add Sales Tax • 90 Day, Hassle-Free, Money Back Guarantee


More New Items for '89



Dust Collector

- 1 hp, 110v
- 4" inlet
- Commercial quality
- Compact size


Reg. \$209.00
\$348.00
(Shp. & Hdig. \$30.00)



Industrial Dust Collector

- 2 hp, 110v
- Two 4" inlets
- 1185 CFM
- 125 lbs.


\$499.00
Value \$339.00
(ships freight collect)



MS-648 Sanding Machine

- Table tilts 2 ways for horizontal or vertical sanding
- ¾ hp
- 6" x 48" Band
- 17¾" Table


Reg. \$369.00
\$269.00
(ships freight collect)



TS 14-56 14" Bandsaw

- Blade size up to ¾" wide
- Cast iron construction
- 180 lbs.
- ¾-hp


\$259.00
(ships freight collect)



List \$1315
\$915

Call Toll Free ☎ **1-800-845-9356**


or in S.C. 288-4174



6" Long Bed Jointer

- ¾ hp, 110v
- Fence tilts 45° both ways.
- Fully adjustable
- 190 lbs.


Reg. \$499.00
\$299.00
(ships freight collect)



Wood Shaper

- ½" Spindle
- 1 hp
- Cast iron construction
- Precision fence
- 160 lbs.
- Ball bearings


Reg. \$499.00
\$239.00
(ships freight collect)



6" Belt Sander

- ¾ hp
- 6" x 48" belt
- Cast iron construction
- 152 lbs.
- 9" Sanding Disc Included
- Ball Bearings

\$199.00
(ships freight collect)



12" Thickness Planer

- Depth of cut ⅛"
- Feed rate 26 fpm
- 69 lbs.
- Safety Switch
- All ball bearing


\$395.00
(Shp. & Hdig. \$20.00)

15" and 20" Planers also available

FREE 24 PAGE CATALOG

Call Toll Free or Write for our newest catalog today **1-800-845-9356**

1 Hour Video Brochure



- ☐ YES! Please send me your free 24 page catalog.
- ☐ YES! Please send me your 1 hour video brochure. (Enclose \$10.00 refundable deposit - specify VHS or Beta)

Total Shop®

P. O. Box 25429, Dept. 11, Greenville, SC 29616

Name _____
Address _____
City _____
State/Zip _____
Phone _____

What I find at yard sales and the like never ceases to amaze me, especially when it comes to old tools. I'm referring to genuinely old tools—a hundred years old or more—many of which may have seen a great deal of use even if they have subsequently lain ignored and forgotten for the last fifty years or so. In this age of antique collectomania almost anything over fifty years old is collected avidly by some group or another and, consequently, almost anything dirty enough to look the least bit old is enthusiastically offered for sale at yard sales, garage sales, flea markets, and even in antique stores (where they ought to know better). As a result, between eagle-eyed collectors on the one hand and people eager to put up for sale almost anything that looks the least bit less than brand new on the other, it is a never-ending surprise to me that something really old (and of real value) does show up.

Of course, one reason for this is that despite the plethora of specialist books and price guides on everything from bottle caps to bass drums, some things slip through the net simply because they are not recognized for what they really are. The dado plane is a case in point. It looks a lot like a moulding plane—which fact alone often leads many overenthusiastic antique dealers to charge an arm and a leg for it. Usually, however, even in California where no moulding planes were ever commercially made, they may commonly be found for just a few dollars or so. In fact, the average price at flea markets and the less pretentious antique stores seems to be between ten to fifteen dollars.

Like many other things, once you start looking, there are more of them than you might otherwise think. There were, after all, hundreds of thousands of these planes made over the better part of two hundred years. Although commercial production to all intents and purposes ceased in the nineteen twenties (there are still a few models made and offered for sale today in specialist woodworking tool catalogs

such as *Woodcraft Supply Co.*), their production in the last century was truly staggering. Early examples from the middle or beginning of the eighteenth century are far less common and command commensurately higher prices when they enter the knowledgeable tool collectors' market.

Nevertheless, despite these older planes' greater rarity, since there is little difference (to the untrained eye) between one moulding plane and the next, it is by no means impossible to discover a plane that is well over two hundred years old. Even so, when I discovered an example of one of the very first *dado* planes ever made, I was truly amazed. But before going further with my latest discovery, let's examine *dado* planes as a group more closely.

What Is a Dado Plane?

First of all, a *dado* plane (see Figure 1) is not a moulding plane. It may look like one, but it does not and cannot make mouldings; and in any event, a *dado* is not a moulding. Like many other planes that get lumped together as moulding planes simply because they are all about 9-1/2" long, somewhat thin, and made of wood, the *dado* plane is a special-purpose plane whose function is not to **stick** mouldings (the correct term for the process of forming a moulding on solid wood with a moulding plane), but to **form** joints.

There are many varieties of this type of plane: plough planes, tongue-and-groove planes, rebate planes and gutter planes, to mention just a few. For the most part the names are self-descriptive, and a little thought will demonstrate that these do not have very much to do with mouldings. The *dado* plane is a little different. The very word *dado* has several different meanings, not all of which are properly understood anymore. Furthermore the plane has been known by other rather enigmatic names such as banding plane, cut-and-thrust plane, raglet, trenching plane, housing plane, and carcase grooving plane.

Without going into the etymology of the word, *dado* currently has two distinct meanings. To the general public it means an ornamental band of paper, plastic, or wood—running around the top of an interior wall. To the woodworker,

however, it means a specific kind of groove (see Figure 2), and it is with this latter meaning that we are concerned here. To be precise, the woodworker understands a *dado* to be a groove that runs across—rather than with—the grain, and is usually wider than it is deep. (Being deeper than it is wide is the primary characteristic of a groove, no matter which way it runs.) These terms, then, define the *dado* plane's true function: it is used to make a groove (or *dado*) across the grain.

In the days before drywall, rooms were often paneled with wood. This paneling was frequently let into a groove cut in the flooring by means of a tongue formed along the bottom edge of the paneling's frame. The receiving groove in the flooring was made with the *dado* plane. This is the reputed original use of this plane, and supposedly explains how the name came about. When you bear in mind that wainscoting was commonly capped by a so-called "*dado*" rail, it becomes clear how eventually the use of this word "*dado*" was transferred from the rail, to the paneling, to the plane used to cut the groove for housing it and, at last, to the very groove itself. At least, that's one story. But, true or not, the fact remains that today both the groove and the special-purpose plane used to make it are called *dadoes*.


I'm not totally convinced myself, and years of looking through old tool catalogs has tended to demonstrate that there never was much consensus regarding either nomenclature or use. Nevertheless, it is true that this plane is wonderfully well suited for forming what we now call *dadoes*—wherever they might be needed.

How the Dado Plane Works

Two things define and qualify the *dado* plane for its ability to make *dadoes*. First is the skewed iron that extends all the way across the sole, and second is the presence of a two-spurred iron placed in front of the main cutting iron (see Figure 3).

The skewed iron ensures a smooth, shearing cut when used across the grain, and is a feature shared in common with various rebate planes and fillisters, as well as many of the metal planes made by Stanley over the years. This feature alone,

Graham Blackburn is a furniture designer/maker in Soquel, California and the author of many books on woodworking and home maintenance including Floors, Walls and Ceilings.






however, would not be sufficient to create a clean dado were it not for the presence of the two little spurs that precede the main iron and score the fibers ahead of the shaving to be taken. By being exactly as far apart as the blade's width, the spurs ensure that the dado may be formed with perfectly clean sides. Without these spurs the bottom of the dado might be smooth enough, but it would undoubtedly suffer from much tearout at the edges.


Both irons—the cutting iron and the double spurred (or “knicker”) iron—are held in the stock by wedges, and these two wedges are what constitute the dado plane's most obvious distinguishing characteristic. Quite a few moulding planes and other special-purpose planes can be found with double wedges, but these wedges and irons are invariably located side by side. The dado plane's wedges are in line, like the masts of a sailing ship.

The second distinguishing characteristic of the dado plane is that it is the only other plane besides the rebate plane that has a tapered mouth, which discharges the shavings off the bench—that is, out of the left-hand side of the plane (assuming that the plane is being


Illustrations by the author



Top-adjustable
Depth Stop



Side-mounted
Depth stop



Simple Wooden
Depth Stop

Set screw




Fig. 5 Depth Stop Types

used by a worker standing at the bench and facing to the left). The reason for this is due to the fact that the iron is skewed with the trailing edge on the left-hand side of the plane, and that the dado plane is descended directly from the rebate plane itself. Furthermore, in use there is invariably a fence on the right-hand side of the plane which would impede the shavings' exit if they were to be discharged on this side.

All dado planes share these two features. The vast majority are 9-1/2" long—the standard length for all moulding planes and related planes since early in the nineteenth century. However, manufacturers commonly made dado planes in various widths—typically in sets increasing by 1/8" from 1/4" to 1". The other chief differences encountered among dado planes is the presence or absence of variously designed depth stops.

It is true that all dado planes possess a built-in depth stop by virtue of the fact that the width of the dado is less than the thickness of the plane's body, and the resulting step down in width at the sole results in a maximum depth that can be worked which is around 1/2" (see Figure 4). But since it is not always convenient to form a dado of this depth, some form of depth regulation becomes in order to work a groove of consistent depth.


Consequently, the majority of all dado planes may be found with one of three main kinds of depth stop (see Figure 5)—although there were some cheap models made with no stop at all. When it became necessary to form a dado to any depth other than that formed by the plane's own stepped sole on these depth stopless models, the usual solution was to tack an extra thickness of wood to the bottom of the plane. Planes with no built-in depth stop often bear traces of this having been done in the form of old holes, blackened soles, and the remnants of nails.

The earliest form of depth stop (which continued in use as the cheapest form) was the provision of a simple wooden stop, usually made of boxwood, which was morticed very snugly into the stock, so that friction alone sufficed to hold it in place. Adjustment up or down was accomplished by tapping it in or out with

Fig. 6

Guide Strip Fixed to Work

Score marks left by Plane's first backwards stroke



illustrations by the author

a mallet or hammer. Regardless of how well fitted this form of depth stop was initially, sooner or later, with use or shrinkage caused by dryness, it became loose. The obvious cure was to secure it in the required position by means of a screw inserted through the cheek of the plane. Consequently, it was not long before manufacturers were providing planes with depth stops that were fully securable by wooden or brass set screws through the sides of the plane.

The final solution, used in the best planes, was to adopt the kind of top-adjustable depth stop found in fillisters and many plough planes. This consisted of a steel shoe which emerged from and retracted into the sole of the plane, thereby stopping the action of the plane as soon as it made contact with the work. A curious feature of these top-mounted depth adjustment screws is that they operate with a reverse thread. To cause the depth stop to emerge from the sole of the plane it is necessary to turn the screw counter clockwise, something which almost everyone, at first, tries to do the reverse of!

The Dado Plane in Use

On all planes, of course, the irons must be sharp or very little will be possible. But on the dado plane it is equally important that the spur iron and the cutting iron be in perfect alignment. To make sure of this, the spurs must only be sharpened on their *inside* edges. To do otherwise would alter their effective width and destroy their

relationship to the width of the skewed iron. Since setting of the irons is achieved by tapping on the front of the stock to lower the blades and tapping on the back of the stock to raise the blades, it is usually best to start with the spur iron set much higher than is needed, adjust the cutting iron, and then gently lower the spur iron by tapping directly on the end of its tang. Be careful, for this end of the iron is very soft and can easily bend.


There is a lot more that could be said on the fine adjustment of wooden planes' irons; but with regard to dado planes the chief point is that both irons be in perfect alignment, not only with each other but with the sole through which they protrude as well. If this is observed, the only other vital precaution is to start work by drawing the plane backwards across the board that is to be dadoed so that the first marks made upon the wood are the parallel lines scored by the spur cutter.

Since the dado plane is intended to be used across the grain and to sink into the wood as it works, it cannot have a fence attached to it. Consequently, a guide taking the place of a fence must be provided by attaching a straight edge to the work, immediately to the right of the intended dado. In carpentry, this guide is usually a lath or other thin, straight strip nailed onto the work with small tacks or brads (see Figure 6); in finer work, a guide may be clamped on.

After the guide is in place and the depth stop set to the required depth, the

Fig. 7

Dado Plane
by William Madox
1748-1775



plane is drawn backwards across the work and then pushed forward. If the two irons are truly in alignment and the plane is held tightly against the guide, distinctively curled shavings will issue out of the plane's mouth, cutting a smooth-bottomed, straight-sided dado with very little effort. It is one of the simplest tools to use, eminently more pleasurable than a router, being quieter, safer, and producing an immaculately smooth, burn-free, "chipout-less" cut.

Obviously, the dado plane cannot compete with a router or a dado blade in a table saw when vast quantities of grooving are required, but in custom furnituremaking, or for small projects, the convenience of being able to reach for the right size dado plane and, with a few quick passes, quietly cut a perfect dado is unmatched.

My Amazing Discovery

Since I enjoy using these planes so much, I am always on the lookout for them, and indeed, as I explained at the beginning, they are not too hard to find. It has, in fact, gone past the point with me where I am still looking for a complete set; I now enjoy finding examples with better depth stops or other curious

features. But I never expected to find a plane made by the very man credited with having developed the dado plane over two hundred years ago—and more than five thousand miles away from where it first saw the light of day.

The gentleman in question was one William Madox, who is known to have operated a plane-making business in Peter Street, Westminster, near London, from 1748 to 1775. The first "proto-dado planes" made by Madox were little more than regular skewed rebate planes with a projecting sole formed by cheeks on either side of the iron, and were fitted with two depth stops and two separate spurs or knicker blades. His planes were typically longer than later nineteenth century planemakers' planes, being on average about 9-7/8" long, and a further idiosyncrasy was that his irons were set at 47° rather than the 50° common for later planes.

The dado plane that caught my eye at the yard sale I visited was keeping company with numerous other wooden moulding planes and various metal bench planes. Although it was a more developed version than Madox's original design, it still exhibited (see Figure 7) significant

differences from the later standardized types of the nineteenth century. Most noticeably, the wedge holding the spur iron was positioned facing backwards instead of forwards. Despite this glaring difference, there were other clues to this plane's age. Although covered with a venerable patina, it was apparent by the roughness of the surface at the back of the plane, and the truncated form of the chamfers that are typically carried along the top of the stock and down the back, that this plane had been sawn to a shorter length than originally made. This is a frequent occurrence with eighteenth century planes, due, no doubt, to later owners wanting to be able to fit these planes into the same size space as would contain the shorter, standardized lengths of nineteenth century tools.

Together with the 47° angle at which the main iron was bedded and the distinctive round shape of the wedge heads, I had no doubt that I had found an old plane; but when I saw Madox's name stamp with its distinctive eighteenth century zigzag border impressed in the plane's toe, I was truly amazed. There is no knowing what may turn up—anywhere. **PW**

Tests & Comments


by Hugh Foster

Some Framing Clamps

As you may have noticed, our craft frequently requires the assembling of four-sided objects. Whether we're making cabinet carcasses or picture frames, many of these assemblies require something more than the basic bar clamp to hold them together. If mitered corners are involved, you are almost sure to need a special device.

The obvious use for at least the first several of the clamps discussed here is picture framing, though they may indeed be used for other larger four-sided and mitered units. The last clamp mentioned is designed more with larger jobs in mind—carcase units and the like. Each of them, in its respective price range, represents a good value.

The model 9448 "Pony" Four Corner Framing Clamp from the Adjustable Clamp Co. consists of four corners, four connectors, four finger-nuts, and eight pieces of 1/4" X 24" threaded rod. The concept behind this clamp is an excellent idea, particularly if you have lots of work that is nearly the same size. In theory at least, the threaded rod is easier to work with than the




The threaded rods allow the Pony Four Corner Framing Clamp to maintain its shape for mass-producing frames that are all the same size.


wired, corded, or banded clamps; in practice, it can mean lots of fooling around. However, given a production run of frames, this will be the clamp that I'd want to use because its use of rods makes it hold its shape far better than do any of these that follow.

The 3417 Wolfcraft light-duty cord clamp features a two-meter long piece of spring-loaded cord (heavy string, really), four square corners, and a cam-action stopper. I really like the action of the cam clamp here; unfortunately, the string has so much "flex" in it that the clamp cannot be made to stay even "finger tight." Since miter joints are only as good as we cut them, regardless of how tight we clamp them, maybe this relatively loose fit isn't a problem. I found that I was able to tinker with the fore-and-aft fit of my miters in this clamp, unlike some of the others. After the day's framemaking was done, I was hard-pressed to tell which frames had been clamped in which clamp. In other words, the least expensive framing clamp you can find will do, and this Wolfcraft 3417 is the least expensive framing clamp I could find!

When he's not pursuing freelance writing or teaching English, Hugh Foster designs and builds custom furniture in Manitowoc, Wisconsin.




The Wolfcraft Cord Clamp (above and to the right) does not apply a lot of pressure, but this makes it possible to adjust for square and to rapidly slide the clamp off and onto another frame.



The more expensive 3416 Wolfcraft Belt Clamp does only what those already described do, but it does it more quickly and more tightly. This stronger clamp features two cam-tightened belt positions, and a tightening screw to be used only after the four-meters-long web is pulled as tight as possible and cam-locked in place. If it's important that your framing clamp be light and easy to use, as well as have a pretty powerful clamping action, this may be the clamp of choice. I know I'd like to have a couple more of these in my shop for occasional use.


This belt clamp is similar to my old Jiffy Clamp, a metal clamp with adapters for curved or molded surfaces that uses 3/16" wire instead of a belt. The wire is drawn tight with a standard turnbuckle. The only real drawbacks to the Jiffy Clamp are that I have scratched a couple of frames while tightening the

The Wolfcraft Belt Clamp is light and easy to use.




Tests & Comments

continued



The Jiffy Clamp's wire cable is drawn tight with a turnbuckle.

Finger Spring clamps pinch the corners of a frame together.




turnbuckle, and the wire tends to become somewhat distorted, especially after it has been excessively tightened a few times. On the other hand, it will span a 25' perimeter. The Jiffy Clamp has been the "old standby" framing clamp in my shop for the past decade or so, and I believe its strength matches or exceeds the Pony's and beats both the others handily if only because wire, like threaded rod, doesn't stretch.

The Spring Miter Clamp Set is made in Germany by Ulmia, a company that exemplifies German precision craftsmanship. If one made lots of frames, as in a professional framing shop, this set would be good to have, particularly if one used lots of large, heavy frame stock. These clamps grab the right size frame very tightly and hold it well. The small scars these clamps leave are not a problem, especially if you use brads in your mitered joints as many framers do. The six available sizes of clamps will handle frame stock that ranges from 3/8" to 3-1/2" wide. If I made more than half a dozen frames a year, you can be sure I'd want to add this fine clamping system to my arsenal.

While the spring miter clamp set is a fast, powerful, professional system, the Finger Spring Clamps might be just the

The Spring Miter Clamp Set comes with a spreader tool for applying the clamps.





ticket for holding typical homebuilt frames made of material that is up to 1" wide. These clamps work similarly to the spring miter clamps in that they have very sharp, pointed tips for grabbing the wood. The difference is that these have the springing mechanism built in, instead of requiring a separate spreader. I don't have an accurate way to measure the strength of these springs, but I cannot fully compress the larger one with just two fingers. I'd buy the larger size since it is nearly twice as big at its maximum opening as the small version and its spring action is much stronger. Having the smaller size wouldn't give you any advantage beyond the 20 cents difference in price.

Both types of these Ulmia spring clamps are faster and easier to use than any of the band, string, or wire clamps mentioned earlier, so they are worthy of your consideration.

Perhaps less worthy of your attention is the Pivoting Jaw Clamp. The jaw will open to 3", and the jaw pads each have ten small sharp teeth. A set of four would be required for most framing applications; \$26 (at \$6.50 each for three or more) would put this in the more expensive range of framing clamps. These jaws did more damage to my sample frames than did all

The Pivoting Jaw Clamp has ten small teeth to grip the work.






The Wolfcraft Miter Vise features quick-action jaws for rapid assembly of mitered joints.

of the other miter clamps combined. Perhaps a single use shouldn't be enough to generate this negative comment, but it was enough to convince me that I don't really want to use it again.

Next in this line-up is the 3415 "mobile clamp," as Wolfcraft's packaging calls it. These aluminum clamps are especially well made, featuring steel jaws (or the option of replacing them with softer liners if you prefer) and push-button screw releases for rapid gluing, assembly and nailing of many types of joints. I wish every clamp I owned with a screw in it had this quick-adjust feature; it alone differentiates this clamp from all those others that merely look like it. Some catalogs call it a "Rapid-Action Miter Vise." This might be a better name, for at \$38.50 (or more) each, four of these would be an awfully expensive way to join the four corners of a picture frame, especially when it won't really do it any better than any of the others. It will, however, do other things the others won't. A careful worker could even saw in it if he needed to adjust the fit of his miter.




Clamping flat assemblies is quick and easy with the Lamello Spanner Set.

At first glance, Bessey's WS-3 and its larger cousin, the WS-6, look as though they function very much like the Wolfcraft clamp just mentioned. Indeed they do, but without the quick-action vise. Otherwise equal in versatility, these clamps (like the Wolfcraft) are sufficiently expensive to warrant their use only as an assembly tool in carcass construction, rather than as a clamp for picture frames. I believe the Wolfcraft's quick-action clamps will save sufficient time to warrant the few dollars of extra expenditure.

The Lamello Spanner's price might prevent your interest, but this is a clamp that will permit you to do assembly jobs alone that you've never been able to do alone before.

I have had a spanner set for only a few months, but I can see that it presents certain advantages over other clamping methods. For carcass work, it is much handier than using pipe clamps; it is certainly lighter in weight if you want to move the case. To use it in carcass construction, simply set the "bottom" of your project in the extrusion with sufficient webbing to span the unit hanging out. Assemble the carcass. Set the remaining pair of



The pivoting jaw of the Bessey WS-3 permits clamping of pieces that are different thicknesses.

The Lamello Spanner Set includes aluminum extrusions that fit on the corners of a carcass.



Tests & Comments

continued

extrusions on the "top" joints and "set" the clamp lightly. After the final adjustments for square have been made, tighten the clamps. It can easily be done while working alone, and it helps ensure that your joints are all drawn tight. Nothing could be simpler; certainly, I'll hope to never have to be bar clamping in several different directions again.

At first the spanner set seems less handy for flat clamping. However, it really works well for that, too. A standard pipe or bar clamp can move the work slightly by torsioning it clockwise as it is tightened. The spanner set does a better job of maintaining the work flat and square.

Those things are positive. This next point is less positive. Glue squeeze-out isn't usually much of a problem with standard clamps; we expect them to get glue on them, and we let it dry and chip it off. In this respect, some gluing habits will have to change. The webbing of the Lamello spanner kit doesn't want glue all over it. If you are using the spanner with plate-jointed

assemblies, there need be little if any seepage. For other joints, learn to use less glue.

So, here is a clamping system that may replace eight or more pipe clamps in carcase construction. Suddenly it seems less expensive.

I bought the full kit, and I will be adding the 5" corner protectors, as I expect to be building quite a few storage units for compact disks over the next several months, and that will make their construction easier. While I can't present this to you as an economical tool, the full kit will save you the most in the long run. Certainly you could get along without it—as no doubt I could. But I don't want to, even if it won't fully replace most of the framing clamps mentioned earlier in the article.

The Bessey Poly-Angle Strap Clamp is the ultimate framing clamp for projects not much over twenty feet in circumference. For starters, it's better made than any of the other lightweight clamps. The manufacturer claims that the woven polyester fiber strap has 400 pounds of tensile strength. The polycarbonate body can be clamped into place for easier working. And the corner pieces are designed for assembling rectangular, hexagonal, and octagonal shapes. These corner pieces are easily assembled to the strap, but the strap can be used without the corners for clamping shapes with even more sides. There is a ratchet in the main body of the clamp which has three positions.

Table of Hopper Joints


by Don Kinnaman


Real works of art often have frames that are real works of art. Some craftsmen make a business out of picture framing, buying special profile cutters for their planers or cutting frames from commercially available moulding stock. There's more to it, though, than cutting accurate 45° miters. The more interesting frames are made with compound miters—also called "hopper" joints because the pieces are angled like the square funnel on a grain hopper.

Listed in the chart below are the arbor tilt and miter gauge settings required to cut compound miters that allow the frame members to flare out from the wall, but still come together with 90° corners. A magnetic base protractor can be very helpful in setting up to the accuracy required. **DW**


Slope	Arbor Tilt	Miter Gauge
5°	44 ³ / ₄ °	85°
10°	44 ¹ / ₄ °	80 ¹ / ₄ °
15°	43 ¹ / ₄ °	75 ¹ / ₂ °
20°	41 ³ / ₄ °	71 ¹ / ₄ °
25°	40°	67°
30°	37 ³ / ₄ °	63 ¹ / ₂ °
35°	35 ¹ / ₄ °	60 ¹ / ₄ °
40°	32 ¹ / ₂ °	57 ¹ / ₄ °
45°	30°	54 ³ / ₄ °
50°	27°	52 ¹ / ₂ °
55°	24°	50 ³ / ₄ °
*60°	21°	49°

* most popular slope for picture frames





The Bessey Poly-Angle Strap Clamp's corner pieces are shaped in such a way that, depending on how they are fitted on the strap, they will clamp four-, six- or eight-sided objects. The base itself can also be clamped to the work surface.



photos by the author

The upper position is for tightening the slack in the strap; the lower position applies final clamping pressure; and the middle position is for pulling out the strap. The ergonomic features of the clamp show that the designers have paid attention to what really goes on in a shop. While I was experimenting with this clamp, I cut a quick octagonal frame and used this to assemble it. Never before has assembly of such a project been so easy. Bessey's reducing the list price from \$72.95 to \$49.95 has made having it realistic for most shops. After an hour's experimentation with it, I knew I liked it well enough to reach for my checkbook. **[PW]**

Where to Get Them

The clamps mentioned in this article are listed below in the order in which they are discussed. Following each are letters which correspond to the legend below to indicate mail order distributors of the clamp or, in some cases, the manufacturers who can then put you in touch with a local distributor.

Pony #9448 Four Corner Framing Clamp: **A**
 Wolfcraft Cord Clamp #3417: **F**
 Wolfcraft Belt Clamp #3416: **E, F** and **G**
 Jiffy Clamp: **H**
 Spring Miter Clamp: **G**
 Finger Spring Clamps: **G**
 Pivoting Jaw Clamp: **G**
 Wolfcraft Mobile Clamp #3415: **D, F** and **G**
 Bessey #WS3: **B, D, E, H** and **I**
 Bessey #WS6: **B, D, E** and **I**
 Lamello Spanner: **C**
 Bessey Poly-Angle Strap Clamp: **B**

Legend

- | | |
|---|--|
| A Adjustable Clamp Co.
417 N. Ashland Ave.
Chicago, IL 60622
(312) 666-0640 | F Wolfcraft of America
1107 Lunt Ave. #6
Schaumburg, IL 60193
(312) 893-7266 |
| B American Clamping Corp.
P. O. Box 399
Batavia, NY 14020
(800) 828-1004 | G Woodcraft Supply Corp.
P. O. Box 4000
Woburn, MA 01888
(800) 225-1153 |
| C Colonial Saw Co.
P. O. Box A
Kingston, MA 02364
(617) 585-4364 | H The Woodworkers' Store
21801 Industrial Blvd.
Rogers, MN 55374-9514
(612) 428-2199 |
| D The Fine Tool Shops
P. O. Box 7091
Portsmouth, NH 03801
(800) 533-5305 | I W. S. Jenks & Son
1933 Montana Ave. NE
Washington D.C. 20002
(800) 638-6405 |
| E Lee Valley Tools
1080 Morrison Dr.
Ottawa, Ontario K2H 8K7
Canada | |

Coloring Wood

by Thomas Wisshack

There are a lot of good reasons to color wood, and just as many ways to do it. When restoring antiques, you often have to match the color of a replacement part to the rest of the piece. If you're refinishing the whole piece, a light stain can help it retain the look of an old surface, rather than one newly refinished. Newly made furniture can be enhanced by the use of color, too, whether you use commercial stains, dyes, or concoctions of your own.

Many of the customers that bring old furniture into my shop for refinishing cringe when they hear the word "stain" in connection with their pieces. They've probably seen some ghastly results, or have had a bad experience of their own using stain, so I've stopped using the word in front of people (even though nearly every piece that leaves my shop goes through a staining process). Instead, I now call it a "wash of color."

Whenever an old piece has been stripped and sanded down, it loses a lot of its character. By staining I can give the piece a rich patina, yet the customer is convinced he is looking at a natural finish. The same technique can be applied to newly made furniture by studying the colors that are already present in the wood and mixing up a solution that will enhance them. By making your own stains, you have a better chance of getting exactly the color you want.

The oak highboy at right was given a wash of color in order to bring out the golden tones of the wood. To create this look I

Thomas Wisshack is a furniture maker, restorer, and finisher in Galesburg, Vermont.

used pure mineral spirits, boiled linseed oil, artists' oil colors in tubes and Japan drier. Begin by mixing roughly four parts mineral spirits to one part linseed oil with a few drops of Japan drier (about 5% by volume). It would be safest to begin with a pint container because you will need to do some experimenting in order to get the color you want. Squeeze a small amount of cadmium yellow and about half as much burnt umber into the liquid and stir. Then add a very small amount of cadmium red (the mixture should take on a slightly orange hue). Deepen the tone by adding a little black. Try the mixture out on a piece of scrap wood to get an idea of its intensity. Apply it with a brush, let it soak in for up to fifteen minutes, and then gently wipe it off with a soft rag. Notice the effect the wash has had on the wood and make any adjustments you might need to get the color you're after. Small amounts of any of the raw colors can make a dramatic difference in the tone. If it appears too orange, try adding burnt umber until you are satisfied. If you accidentally put in too much red, don't panic; mix in some green in small amounts until a rich brown results. You can then add whatever colors are lacking to get the color you want. If the mixture seems watery and has little effect on the wood, you will have to add more pigment in similar proportions. If it is thick and opaque you will have to add more thinner. After your project has been sanded to perfection, apply a liberal coat of the mixture with a brush. Let it soak into the wood for up to twenty minutes (the wash will begin to haze and become dull in places). Gently distribute the stain with a soft cloth using a circular motion. By the time you're done, you should be ready to give your piece a final, gentle

Mixing Stains

by Sam Allen

Using these formulas as general guidelines, you can mix your own stains using tinting colors. Many shades can be achieved with the four basic colors as shown in the left chart. With additional colors, a wider range of effects can be achieved as shown in the chart on the right.

Stains Using the Four Basic Tinting Colors

Walnut 6 oz. burnt umber	Light Oak 1 oz. burnt umber 1 oz. yellow ochre	Natural Pine 4 oz. yellow ochre 2 oz. zinc white 1 oz. burnt umber
Brown Mahogany 6 oz. burnt umber 2 oz. burnt sienna	Antique Pine 3 oz. burnt umber 2 oz. yellow ochre 1 oz. burnt sienna	Pickled Pine 4 oz. zinc white 1 oz. yellow ochre 1/4 oz. burnt umber
Red Mahogany 6 oz. burnt sienna	Limed Oak 6 oz. zinc white 1 oz. yellow ochre 1/4 oz. burnt umber	Honey Maple 6 oz. yellow ochre 1 oz. burnt sienna 1/4 oz. burnt umber
Dark Oak 6 oz. burnt umber 1 oz. burnt sienna 1/2 oz. yellow ochre		

Stains Using Additional Colors

Light Cherry 3 oz. raw sienna 3 oz. burnt sienna 1/4 oz. rose pink	Honey Pine 4 oz. yellow ochre 1 oz. raw sienna	Mission Oak 3 oz. vandyke brown 1 oz. burnt umber 2 oz. lamp black
Dark Brown Mahogany 6 oz. vandyke brown 1 oz. raw umber 1 oz. raw pink	Weathered Silver Grey 2 oz. lamp black 3 oz. zinc white 1/4 oz. raw sienna	Ebony 8 oz. ivory black 1/4 oz. rose pink 1/8 oz. Prussian blue
Pumpkin Maple 5 oz. burnt sienna a touch of ultramarine blue	Medium Dark Walnut 5 oz. vandyke brown	Bright Red Mahogany 5 oz. burnt sienna 1 oz. raw umber 1/2 oz. vermillion red
Yellow Maple 3 oz. raw sienna 1 oz. raw umber	Dark Walnut 7 oz. vandyke brown	

Reprinted by permission of Sterling Publishing Inc., 387 Park Avenue South, New York, NY 10016 from *Wood Finishers Handbook* (\$12.95) by Sam Allen, copyright 1984 by Sterling Publishing Co. Inc.

wiping off with the grain, using a fresh cloth.

When making your own oil stains with artists' oil colors you will need to have some sense of color to get the effect you want, but you needn't be an artist. Trial and error will give you confidence and eventual mastery. Always remember to study the natural wood tones and base your stain on this. Look at a fine old piece of figured mahogany and you will very likely see reds, yellows, oranges, browns and even blacks. You will be using these very colors in mixing up a mahogany oil stain. I begin with a rich red, deepen it with a small amount of black, and charge it with small amounts of yellow or orange. If it appears too red, I add green to bring it back to a brown mahogany.

Sometimes because of the size of a job, or because you must have uniform results without any guesswork, commercial stains are the answer. Obviously they are much more convenient, but it pays to be aware of their limitations before using them. My main objection to these is that most companies who now make them have switched from organic to synthetic ingredients, and I believe a certain richness is lost in the process. Sometimes too, fillers are added which tend to give the wood a muddy appearance. Having said that, I must admit that there are some very fine stains on the market. One of my favorites is Minwax Wood Stain. The people who originated this product must have been aware of the dilemma that stains can present to the wood-finisher, because they have come up with a product that meets all the requirements for a superior stain: ease of application, richness, permanence and transparency. By intermixing Minwax stains it is possible to match nearly any shade of wood. This, I am sure, has made them very popular among people who restore antique furniture. The stains have a transparency that I have not seen before in a commercial product and with, for example, an old piece that has been stripped and sanded and lost some of its patina, you can again give the wood the richness that it might possess if the original finish had remained intact.

For newly made furniture these stains work equally well. Since my approach has always been to try to enhance rather than completely change the character of any wood surface, I suggest you use these stains very much as you would use the wash of color I just described. You needn't accept them just as they come out of the can; by experimenting you will get the best results. In some cases you may need to add a little thinner to your stain because some of the colors, such as their Red Mahogany and Jacobean stains, are very intense. Once you have stained a piece too dark, it can be very difficult to remove; these stains contain a certain amount of sealer and can penetrate quite deeply into the wood (more about this later). Always experiment on a scrap of the same wood from which you have made your project. The properties and working characteristics of these stains vary somewhat from color to color. Certain of the colors seem to have a slightly more cloudy appearance than others, possibly due to the addition of fillers or other ingredients. Others seem to have a remarkable transparency, and by intermixing you can usually get a very nice effect. Minwax *Golden Oak* will give you a very rich, transparent effect on new or old work, much like the color of the highboy at right. If you wish to darken the tone and move away from the "yellowish" look, you can add small amounts of *Jacobean* to it until you get the effect you want. By adding small amounts of the darker, more intense stain to the golden, transparent one, you can safely advance toward the exact color

photos by Mike Godsil



This Jacobean pine chest by the author was given a wash of color to bring out the natural tones in the wood.



The golden tones of this oak highboy were brought out with a homemade oil stain. (Highboy by the author)



An aniline dye was used to achieve the brilliant red color on the mahogany legs of this contemporary table. (Table by the author, top of African wenge)

you are after.

You can also spice commercial stains with artists' oil colors to get special effects or to match a specific color. Have a selection of the basic oil colors on hand and become familiar with how they effect each other. Experiment with smaller or slightly larger amounts of boiled linseed oil in the mixture, and add Japan drier accordingly to insure rapid drying, even when using a commercial stain. (Linseed oil brings out the golden tones which you may or may not want.)

Vary the amount of drying time when using oil stains. For the darkest effect, allow the stain to sit as long as you can without it becoming sticky, and wipe it off with a very gentle touch. For just a hint of color, wipe it off soon after you have applied it and give the wood a good rubbing down with your cloth.

You may have trouble when applying an oil finish over a piece that has been stained with oil colors. Sometimes the stain will dissolve into the finish with disappointing results. You can avoid the problem by first isolating the stained piece with a wash coat of shellac, which will usually not disturb the color. Shellac is available in spray cans, and a light coat misted onto your project and later smoothed lightly with steel wool allows you to apply an oil finish without worry. Most finishes will bond to the shellac, as long as it is applied thinly.

In some cases you may be leery of applying a stain directly to the wood because of blotchy or uneven results. Applying a sealer to the wood first and rubbing it down with fine steel wool when dry, will give you more control over the final color. You could use shellac or one of the penetrating finishes for this. Many craftsmen have trouble when working with pine, which is sometimes a difficult wood to stain. One way to get a soft, mellow, old look on pine is to first give it a wash coat of shellac.

photos by Mike Godsil

An aniline dye produces dramatic effects on wood; these water-soluble dyes will, however, raise the grain of the wood.



White shellac that has been spiced with a little orange shellac does a very nice job of it. You may want to use two coats, but be sure you have thinned it considerably with alcohol to avoid a gummy build-up. Afterwards you can apply your stain and leave as much or as little as you like on the wood. I have given new pine the look of 100-year-old-stock using variations of this method. Again, studying the tones already in the wood (which in the case of pine are oranges, yellows, reds and browns) will give the richest results.

I should mention that a number of commercial stains combine the pigment with sealers so that you are in essence sealing and staining the wood simultaneously. These are becoming increasingly popular, and there are some good ones on the market (including Minwax) which have ingredients in the correct proportions to give good results. But technically, the staining operation is best viewed as a separate step in the finishing process, one that should be allowed to dry completely before proceeding, so that the finish can cure properly. Many of the products I have seen, which claim to combine the two steps, give a greasy look to the wood and can emphasize the open pores in a wood like oak to the point where they look unnatural and bizarre.

So far I have been talking exclusively about oil stains, and for very good reasons: I think they are the easiest to use and give good results to even the amateur wood finisher. With oil, you know exactly what's in the mixture and you can mix up a very small amount, if the job calls for it. I would not want to be without them as a wood finisher. At the same time, I am aware that for some very special jobs, oil stains may not be the answer, so I want to talk a little about another approach to coloring wood.

Water-soluble aniline dyes are considered by many to be the finest wood stains available. The difference between a dye and an oil stain, in simple terms, is that with an oil stain, particles of finely ground pigment are suspended in a clear vehicle (mineral spirits and oil in the case of the stains/washes I described). At its very best, a mixture like this will give you a semi-transparent film of color. In its thickest form (roughly equal to an ordinary commercial stain), it will leave a semi-opaque film or color on your wood. An aniline dye, on the other hand, is made up of a very finely ground pigment, which when dissolved in water will give you a completely transparent, brilliant effect. There is another difference between the two: A water-based stain will raise the grain of the wood; an oil stain will not. For this reason, I use dye on very few of the pieces I make or restore. A piece of furniture with carving, or with a lot of moldings or hard-to-reach places, is probably not a good candidate for water-based dyes. For a piece of furniture with relatively flat, unbroken surfaces, however, it can give striking results. As an example, look at the small end table on the previous page. Here a mahogany frame and legs have been combined with an African wenge top. The table called for a special staining approach, because the mahogany appeared quite pale and lifeless at first. I wanted to play up the contrast between the two woods, which meant enhancing the color of the legs and frame. A red mahogany aniline dye provided the answer to this problem.

To create the same effect, first raise the grain of your wood by sponging it with hot water. After it's dry, sand it thoroughly to remove any roughness. Repeat this process a second time and sand your wood to perfection, finishing up with #400 or #600

wet or dry paper. The idea is to minimize the amount of grain-raising that will occur when you finally apply the stain. For maximum penetration of the dye, boil some water and place it in a glass container. Add the powdered red mahogany dye to this in small increments, testing it frequently on identical scrap wood until you have the desired shade. Flow a generous coat onto one area of your project at a time and immediately wipe the surplus off with a fresh, soft cloth. Continue this way until everything is covered, being careful not to overlap one area onto another. You can add a second coat, if you find it necessary, in about thirty minutes. Any roughness can now be removed with a worn piece of #400 wet or dry paper or fine steel wool, used with care. If you rub through a corner or an edge, it can be fairly easily touched up with a small amount of dye on an artist's brush or cloth.

You can create some very beautiful effects on wood by intermixing the dyes, and I believe they are as permanent and fade-resistant as any stains. Interestingly enough, the dye I used for this experiment was one commonly available in stores for dyeing fabrics. I see no reason why you shouldn't experiment with this kind of dye, since it is readily available and cheap, and as far as I know, the effect is permanent. Of course you should realize from the start that any dye or stain will, over the years, lose some of its brilliance unless it is completely hidden from light. But in most cases, the wood will have aged and developed a rich color of its own.

Finally, there is a very unique way of giving wood a beautiful color, but it is one that few of us can afford from the standpoint of time. Even so, every craftsman should know about what I call "shop aging" wood. This involves constructing a piece and sanding it to perfection, but allowing it to sit around the shop for weeks or months before attempting to do anything in the way of finishing it. If, for example, you are making a piece for yourself and do not have a specific deadline, I encourage you to experiment with this technique. The grain, texture and color of wood will "soften" and mellow in time (as anyone familiar with antique furniture knows) and by giving the wood a period of time to acclimate, many of the problems associated with staining and finishing are eliminated. In a sense you are letting the wood get a bit of a patina before you apply anything to it, and in every case, you will be rewarded by the extra time allowed.

Pine, a wood many craftsmen seem to have trouble with, indeed to misunderstand, will benefit greatly from being allowed to stand a few weeks in the shop. The tendency for it to appear blotchy or "anemic" when staining or finishing will be lessened considerably. Maple, in the same way, becomes "friendlier" after a period of shop aging, though it often takes longer to see results. But the most dramatic change of all takes place in cherry, which will begin to show darkening in just a few days. To see this for yourself, try this experiment: Freshly plane a piece of cherry and apply a piece of masking tape across the grain, near the middle of the board. Let it sit around for a week or so and then remove the tape. You'll see a very distinct pale stripe surrounded by a noticeably darker, brownish-green area. Apply a coat of finish to your board to see an even more dramatic effect. The aging process occurs very rapidly with cherry; even two weeks will give you a head start on a beautiful patina. It's interesting to note, as we look at the various ways of coloring wood, that if the wood is left alone, nature itself has one of the best solutions. **PW**



Toys for Grownups

Using Wood Species as a Palette

by Ken Textor

A project for Bryce Muir usually begins with a frantic phone call from an excited spouse saying, "At last I've found something that I know he doesn't have." "And what did you have in mind?" answers Bryce patiently. Psychology can be as much a part of his business as woodworking, as he tries to discern the true personality of a potential client. "I'm not sure, but he certainly loves skiing," the caller says, and then pauses for a moment. "And his dog. It's a black Lab."

With this, Bryce's wheels start turning, and he at once sees the project—a black Labrador on skis—and the woods to be used—ebony for the Lab, cocobolo for the skis, maybe birch dowels for poles. "Does he have a favorite piece of clothing?" he asks. "Oh, yes, he often

Ken Textor is a woodworker and writer in Arrowsic, Maine.


wears a checked vest," she says. Bryce now sees that the Lab will need to be dressed in a checked vest—a tricky proposition, but perhaps with some padauk and Osage orange glued together in a crisscross pattern... It will be tough, but Bryce's self-imposed rules against using any stains, painting, or veneers make it necessary.

Bryce may next try a shot in the dark: "He doesn't play a musical instrument by any chance, does he?" "He used to play the guitar in college, but not much anymore," comes the answer. That does it for Bryce. He suggests a vested black Lab on skis that strums a guitar when you move its tail. The customer is delighted, and Bryce has landed himself another week of work.

Bryce the Toymaker has his shop in Bowdoinham, Maine, in the front parlor of an old Victorian house. At 41, he now

works full-time making toys, and "a little more than full-time" when Christmas gets near. He works exclusively in hardwoods, both foreign and domestic, including such exotics as bocote, zebrawood, rosewood, and greenheart, as well as the old standbys: oak, maple, birch and cherry. "I find myself using a lot of wenge lately because it's very good for pinstripes," says Muir. His shop is a veritable squirrel's nest of odd pieces of wood tucked away here and there.

The tools Muir needs for making the toys are the same simple, basic tools which any woodworker uses. He usually starts on the bandsaw, roughing out body parts and other major components. He also uses a lathe and a drill press to make his dowels, wheels, and gears. The real heart of the operation, however, is a sanding/grinding wheel which Bryce handles like a virtuoso playing a violin.




This toy was made for an antique dealer who must "ferret out" pieces of folk art and memorabilia. When you move the ferret's tail, he "reads the fine print" of an antique catalog.



This was made for a hiking grandmother who never hits the trail without her walking staff, straw hat, and a fluttering ribbon in her hand.

When the tail of the dog on the right is turned, he cranks the organ and causes the other dog to "play" it with his feet and hands.





The newspaper publisher for whom this toy was commissioned likes to offer a toast now and then; when you turn the crank, he offers one while cranking the press.



After roughing out a piece, Muir will use the wheel to sand in subtleties such as facial expression, folds of clothing, and so on. For finer work, he uses a small grinding tool, and tiny files and chisels. He finishes the toys with a non-toxic oil, just in case some real kids get ahold of them and start gnawing away.

"I still make mistakes, and occasionally I have to throw a whole piece away," Muir admits. After 20 years

of toymaking, however, the mistakes are few, and Muir's finished pieces look remarkably like the person or animal they are intended to portray.

Muir glues the toy's pieces together with epoxy and pegs inserted at critical stress points. The moving parts are the most difficult to assemble. "Sometimes I have to spend quite a while working with a piece to get it to work the way I want it to," says Muir. "I never know how these

This piece was made for a Maine chiropractor who will even take on a giraffe with a stiff neck. When you turn the crank, the moose (a symbol of Maine) does the back-cracking procedures.





photos by the author


things will work after I think them up."



One of his most challenging pieces so far was for a bartender who had an affinity for racehorses. Bryce built a toy consisting of two horses, with caricature riders which, when a crank was turned, burst out of their gates and galloped through the air on strings. When the crank was turned the other way, they galloped backwards into the gates again. "It took me almost a month to perfect that," he says.


The moving parts for Muir's toys are based on either a cam, a spoked wheel, a carved gear, or a cog assembly. "Most everyone wants their toy to do something," says Muir, adding, "The more complex it gets, the more time consuming and expensive it is to produce." The cost of his toys ranges from \$500 to \$1,500. Considering the detail of many of the toys, many consider them a bargain. **PW**



Carefully open staples to remove plans, then bend them closed again.












Wine Rack/End Table Rail Patterns

Colonial Footstool Patterns







■ Popular Woodworking

BACK ISSUE LIBRARY

This page is blank because it contained a full-page advertisement—the content for which was not retained.

To maintain page numbering with the original table of contents, this page has been inserted.

Please continue reading
on the next page.





■ Popular Woodworking

BACK ISSUE LIBRARY

This page is blank because it contained a full-page advertisement—the content for which was not retained.

To maintain page numbering with the original table of contents, this page has been inserted.

Please continue reading
on the next page.





■ Popular Woodworking

BACK ISSUE LIBRARY

This page is blank because it contained a full-page advertisement—the content for which was not retained.

To maintain page numbering with the original table of contents, this page has been inserted.

Please continue reading
on the next page.





■ Popular Woodworking

BACK ISSUE LIBRARY

This page is blank because it contained a full-page advertisement—the content for which was not retained.

To maintain page numbering with the original table of contents, this page has been inserted.

Please continue reading
on the next page.





■ Popular Woodworking

BACK ISSUE LIBRARY

This page is blank because it contained a full-page advertisement—the content for which was not retained.

To maintain page numbering with the original table of contents, this page has been inserted.

Please continue reading
on the next page.





■ Popular Woodworking

BACK ISSUE LIBRARY

This page is blank because it contained a full-page advertisement—the content for which was not retained.

To maintain page numbering with the original table of contents, this page has been inserted.

Please continue reading
on the next page.





■ Popular Woodworking

BACK ISSUE LIBRARY

This page is blank because it contained a full-page advertisement—the content for which was not retained.

To maintain page numbering with the original table of contents, this page has been inserted.

Please continue reading
on the next page.





■ Popular Woodworking

BACK ISSUE LIBRARY

This page is blank because it contained a full-page advertisement—the content for which was not retained.

To maintain page numbering with the original table of contents, this page has been inserted.

Please continue reading
on the next page.





■ Popular Woodworking

BACK ISSUE LIBRARY

This page is blank because it contained a full-page advertisement—the content for which was not retained.

To maintain page numbering with the original table of contents, this page has been inserted.

Please continue reading
on the next page.





■ Popular Woodworking

BACK ISSUE LIBRARY

This page is blank because it contained a full-page advertisement—the content for which was not retained.

To maintain page numbering with the original table of contents, this page has been inserted.

Please continue reading
on the next page.





■ Popular Woodworking

BACK ISSUE LIBRARY

This page is blank because it contained a full-page advertisement—the content for which was not retained.

To maintain page numbering with the original table of contents, this page has been inserted.

Please continue reading
on the next page.





■ Popular Woodworking

BACK ISSUE LIBRARY

This page is blank because it contained a full-page advertisement—the content for which was not retained.


To maintain page numbering with the original table of contents, this page has been inserted.

Please continue reading
on the next page.



A Popular Woodworking Project

photo by Deborah Porter



Colonial Footstool

by John A. Nelson

In early America, footstools came in just about all shapes and sizes. I doubt if you would ever find two alike, even if made by the same person. In those days the footstool was commonly called a "cricket" because it was usually found at the foot of a chair in front of a warm fire.

This footstool is a reproduction of one made sometime in the eighteenth century in New England. It is easy to make and very sturdy. It can be made of pine or practically any wood, since it will be painted.

Cut out the basic parts to the dimensions in the cutting list. You will find a full-size pattern in the PullOut™ Plans section in the middle of this magazine for the ends (A) and the braces (B). Tack the two rough-cut end pieces together, transfer the end pattern onto one of these, and cut out both at the same time using a band saw, jigsaw, or sabre saw. Do the same with the braces (B), and sand all rough edges.

To assemble, attach the braces to the ends using finish nails and glue. See the exploded view for the correct fit. Next, line up the top (C), and glue and nail it in place.

Sand the assembled stool all over, and ease the sharp edges along the top by sanding. Paint your stool however you like. When it's dry, find a cozy chair and a warm fire to try out your new "antique" cricket. **PW**

John A. Nelson is the author of many books on woodworking and a frequent contributor to Popular Woodworking.





illustration by the author

Footstool					
Cutting List					
Qty	Part	Finished Size			Piece
		T	W	L	
2	A	5/8"	6"	5 3/8"	ends
2	B	5/8"	2 1/4"	12"	braces
1	C	5/8"	6"	12"	top

Project for the Shop



Lathe Tool Rack

photo by the author

by Jerry Ernce

I hadn't had my wood lathe for too long before I decided that I had to come up with a place to keep the tools. I looked around at what the professionals do, and didn't see anything I liked. They had them blade-end-up in a box hung on the side of the lathe, or just laying on a table or in a drawer. Nothing I saw looked safe, neat or organized. I felt that the tools should hang near the lathe at eye level so I could get to them easily and not have to pick up two or three to find the one I needed. I worked out new handles that had to be lifted to be removed from a rack. This would keep them from falling out accidentally. While I was making new handles, I made them longer for leverage. I turned each handle from a different hardwood for quick identification and beauty. It all fell together to make a safe, neat and handy lathe accessory.

Start by making the handles. Use a different hardwood for each tool—each piece 1-1/2" square X 13" long. If you can, salvage the metal ferrules from your old

Jerry Ernce is a woodworker in Broken Arrow, Oklahoma.

tools, or you can get new ones. I had a machinist friend make me new ones out of brass. [Editor's Note: See "Tricks of the Trade" on page 5 for another ferrule idea.]

Mark and drill the hole in each piece to fit the gouge or chisel you have chosen for it, and drill the hole so that it fits snug. If the shank of your cutter is tapered, you may have to drill stepped holes to get a good fit. Mount the hardwood blank on the lathe, and turn the handle round. Finish turning the handles using the pattern in Figure 1. I worked out this shape because of its function; the business end is thick to carry the stress put on the cutter, the length is for leverage, and the knob acts as a hanger and also lets your fingers know when you've reached the end of the handle. While I was at it, I made an extra handle for any tool I might want to add later on.

You may want to alter the dimensions of the rack if you have more or fewer tools than I do. The dimensions given here are for a rack that will hold 11 tools. With the upper rail (A) cut to size, lay out the holes and slots as shown in Figure 2. Drill the




Figure 1

Lathe Tool Rack					
Cutting List					
Qty	Part	Finished Size			Piece
		T	W	L	
1	A	3/4"	2"	30 1/2"	upper rail
1	B	3/4"	2"	30 1/2"	lower rail
2	C	3/4"	2 3/4"	34"	frame sides
2	D	3/4"	2 3/4"	24"	frame ends
1	E	1/8"	23 1/4"	33 1/4"	back

Figure 2





Figure 3




Jig Journal

Corner Notching Jig

This simple jig will let you cut exposed spline joints in a mitered frame using a 1/4" dado blade on a table saw. Make the jig from stock that's thick enough to properly support the frame (I used two-by material for this 2" frame) and wide enough to accommodate the cut. Attach a high auxiliary fence against which you can reference the jig and the frame.

Glue up the frame and place it in the jig to set the blade height. Set the fence 3/4" away from the blade and cut through the jig. With the frame in the jig, cut a slot in each corner referencing the same edge against the fence. Make a second cut in each corner by referencing the opposite edge against the fence.



illustrations by Tom Larson

holes first, using a 1" bit. Then rout the edge of the rail, using a 1/2" round-over bit. Next, cut the slots through from the front to the holes, and then rout the edges of the holes and the slot, and the front edge of the rail. Make the lower rail (B) next, drilling holes first and then cutting out the slots with a band saw or coping saw, and then sanding smooth. Don't rout this rail.

Make the box by first cutting out the four pieces for the sides (C) and ends (D). Miter the ends of these pieces as you cut them to length. Cut the 1/8" wide X 3/8" deep groove in the back (E) in each piece.

Assemble the box with its back in place and glue and clamp the mitered corners together. Square up all four sides. When these are dry, cut the slots for the splines. The "Jig Journal" at left contains instructions for a jig which will make these cuts easily. You can make your splines out of any thin stock, such as 1/4" hardwood or plywood. Choosing a wood that contrasts with your frame will make a nice looking joint.

Make the splines oversize, and glue them in place. After they're dry, sand the splines flush. Attach the rails in place using glue and drywall screws countersunk from the back. If your tools are of different length be sure that you place your rails so as to leave room for the cutters at the bottom and room at the top to lift the tools for removal. Finish the rack with the finish of your choice (I used a polyurethane) and mount it on the wall near your lathe.

Now, pick a tool...any tool. You should never have to fumble in the shavings again. **PW**

Swedish Savers

by Shirley Stebbins

Peter Tryg's work as a lumberjack in the North woods of Minnesota led him quite naturally to a love of wood carving, and many of his carvings are of lumberjacks. It was his Swedish heritage, however, that led him into making these authentic birch bark canisters. He learned how while on a visit to his ancestral homeland.


Before he begins making these Swedish "savers," Peter cuts a complete pattern out of paper or lightweight cardboard. He has

Shirley Stebbins is a writer from Sturgeon Lake, Minnesota.

come up with several different versions of the interlocking splice that joins the ends of the bark, the most common being arrow-shaped fingers that lock into triangular cutouts. The PullOut™ Plans section in the middle of this issue has a sample pattern; this is folk art, though, so variations are encouraged.

Removing the birch bark from the tree is a simple matter of making a vertical slit with a knife and peeling the bark off. This must be done in June, while the sap is still running.

Peter traces his pattern onto a long sheet of birch bark and cuts it out with a straight knife and a chisel. If he wants to make



Peter cuts arrow-shaped fingers, or some other inter-locking joint on one end.



On the other end of the piece, he cuts the shape that will receive the fingers.

Peter carefully locks the two ends together and spreads a coating of wood glue inside the overlapping ends.



He puts the glued bark onto a tree core that has been split in half, then he drives wedges tightly into each end and lets it dry.



the edges more decorative, he cuts them with pinking shears, as on the smaller cannisters and the oval snuff box in the photo at bottom.


Next he splits a length of tree core that will fit into the canister and ties the two halves back together. He then wraps the bark around the core and glues it at the notches with carpenters wood glue. To make sure that the canister dries tight and circular, he drives a wooden wedge into the slit of the tree core at each end. He allows this part of the canister to dry for at least six hours.

When the canister has dried, Peter glues another layer of

birch bark into the inside of the canister, drives the wedges back into the core, and allows it to dry once again.

Peter then cuts a top and bottom for the canister out of pine and attaches a leather handle to the top. He glues the bottom in with wood glue. Sometimes he finishes the outsides with paint or varnish, but usually leaves them unfinished.

These Swedish savers are not only decorative, but can also be used as the Swedes used them—for flour, sugar lumps, and even snuff! **PW**



Peter spreads the inside of the outer bark with wood glue and pushes in a birch bark lining for the canister. He then repeats the procedure with the tree core, driving in the wedges and allowing it to dry.




A pine bottom and a lid with a leather handle complete the canister.

This method can be used to make a large variety of sizes and styles. The smaller Swedish savers were trimmed with pinking shears.



COMPUTER-ASSISTED FURNITURE DESIGN



PART 1: DRAWING IN 3-D

This computer desk was designed by Scanco using Dimensions Presenter software.

by Alan Marks

Deep in the recesses of my mind, I have always nursed the hope that one day I will put away my mechanical pencils, eraser, drafting board, rolls of paper and all the other countless paraphernalia I assemble periodically in order to draw a simple piece of furniture. Someday, I have told myself, it will be possible to sit down at a computer and do it all on the screen.

Furthermore, I fantasize about never having to build another prototype. Imagine being able to draw a three-dimensional scale model of a chair (the most complex piece of furniture, to my mind) on the computer screen, and turn it around and view it from every conceivable angle.

Could this really be too much to ask for? I think not. The Macintosh combined with my favorite word processing pro-

gram has already helped me achieve one dream, which was to never have to re-type a manuscript.

With this in mind, and after amassing a collection of the latest drawing and design software available for evaluation, it gives me great pleasure to share my findings on computer-assisted drawing, which I hope will encourage the reader as much as it has me to give computer drawing with the Macintosh a try.

Why the Macintosh? The Mac, as users lovingly refer to it, is easy to use, fun to learn about, and graphically oriented—much more so than its competitor IBM and its clones. The way in which the Mac and its user communicate relies on a visual interaction, as opposed to the verbal/numerical system used by other computers. The Mac operates largely through the use of a “mouse,” a small device which you slide across your desk top, which in

turn moves a pointer on the computer screen. Files and documents on the Mac appear as tiny picture representations called “icons.” To open a file, you position the pointer on it and click a button on the mouse. All operations on the Mac are carried out using this same basic method. Variations, such as clicking twice on the mouse, or “dragging” by holding the button down while you move the mouse, allow you to perform different functions.

Although this ease of operation is a good reason to recommend the Macintosh, more important is its graphics capability. While the IBM and IBM-based systems concentrated on business and financial-oriented programming, the Macintosh developed as the leader in graphics, and is used widely by designers and graphic artists. This is due, in part, to the Mac’s visual orientation, and partly to the fact that because of this, there are more

Alan Marks is a cabinetmaker in Carmel Valley, CA, and a contributing editor to PW.

and better programs available for the Mac. If you're already an IBM or IBM-type owner and find yourself drawn to computer drawing, don't despair—there are programs available in IBM versions as well.

The two parts of this article correspond to the two major work areas addressed by programs: two-dimensional space and three-dimensional space. In this issue, I will discuss software as it pertains to three-dimensional drawing; two-dimensional drawing will be discussed in the next issue (August/September 1989). To qualify as three-dimensional, a program had to be capable of creating facsimiles of objects which can be rotated and viewed from any angle in three-dimensional space. As far as my experience goes, no program can claim to be equally proficient in both areas. An illustration of Macintosh graphics may be found on page 78 of this magazine. William McMaster regularly uses the Macintosh together with a graphics program called Adobe *Illustrator 88* to produce drawings for his carving articles. Illustrator Tom Larson, whose drawings regularly appear in *PW*, uses a popular program called *AutoCad*, which has recently become available for the Macintosh.


The Macintosh

Besides needing one of the programs discussed in this article, what kind of equipment do you need to produce drawings? The Macintosh Plus, currently Apple Computer's entry level model, will run any of the programs mentioned in this article. The Macintosh Plus sells for around \$1,350 but if you get a package deal, it can be purchased cheaper. My particular Plus has two-and-a-half times the memory Apple originally supplied it with. Drawing programs can require a lot of memory in proportion to the complexity of your drawings. A few 3-D design

programs exist which only the more advanced Macintosh II can operate, but these were not considered for this review. Besides the computer, which comes equipped with keyboard, monitor, and mouse, you will need a storage device called a hard disk. Depending upon how

However, many copy shops and print shops now have a laser printer service, where for a price (usually under a dollar a page) they will print out your drawing from a **diskette**, a small portable storage device which costs about two dollars. Services in major cities also, for a reason-

Figure 1



The MiniCad™ version of the knob, shown in dot-matrix and laser printer versions.


much information you wish to store in your hard disk, you can expect to pay upwards of five hundred dollars for one.

About Printers

To print out a copy of your drawings, you need a printer. These come in a number of types, two of which are applicable here: **dot-matrix** and **laser** printers. The dot-matrix type is the basic computer printer, using a "grid" (matrix) of dots to assemble words or drawings. These printers are very affordable, ranging from one to a few hundred dollars depending on the features included. Laser printers are a more recent invention. Figure 1 shows a dot-matrix printout next to that of a laser printer. As you can see, the clarity, smoothness and definition of laser printers is vastly superior to dot-matrix types. For most of us, the cost of a laser printer will be prohibitive, and the dot-matrix printer will be the most logical choice.

able fee, will laser print by mail drawings of any standard size or larger. (You can do drawings of practically any size on the Macintosh and are not at all restricted by the relatively small size of the monitor.)

These are humble beginnings. Things can get much more expensive if you pull the stops out. For example, if you decide you want to create drawings larger than an 8-1/2" X 11" format, you may want to consider getting another instrument used by printing services, the plotter. Plotters can produce copies up to 44" wide in some models and 100 feet long. If you get a more advanced computer than the Macintosh Plus, you might consider using color and a color plotter. Major manufacturers of plotters are Hewlett Packard, CalComp, and Houston Instruments. Two types of plotters exist: pen plotters and electrostatic ones. The latter is extremely fast and accurate, though pen plotters



have amazing accuracy as well. Expect to pay around \$3,000 for a smaller, less elaborate plotter.

CAD

CAD is an acronym for Computer Aided Design; CADD refers to Computer Aided Design and Drafting; CAM means Computer Aided Manufacturing. If you decide that CAD is something you'd like to keep tabs on, consider subscribing to The CAD/CAM Journal, a bimonthly magazine published exclusively for Macintosh owners (16 Beaver Street, New York, N.Y. 10275-0241). MicroCAD News, a monthly publication, covers developments in the field regardless of computer affiliation (Ariel Communications, Inc., 12710 Research, Suite 250, Austin, TX 78759). The other publications I know about are published by individual software manufacturers with their own private axes to grind. They could be useful, however, once you have decided which program to use.

All drawing programs perform operations using "tools." Tools are symbolic buttons on the screen, each of which creates or alters a selected object in some way. The button is accessed by maneuvering the cursor onto it with the mouse and then clicking the mouse. Certain operations are more easily or quickly implemented with some programs than others. Some programs do not perform some operations.

Essential for learning how to use a program is the documentation or instructional material accompanying it. Much depends upon easily understood explanations and on whether answers to questions that pop up can be easily found in the

manual.

Extremely helpful are tutorial aids, such as video or cassette tapes or walk-through lessons on a diskette. Unfortunately, not all programs have these.

Most manuals do not provide exhaustive information about a program, and in such cases one must rely upon the quality of technical support available from the software publisher. I find it both frustrating and expensive to wait on long distance hold for the next available technician to tell me why I can't get my program to do what it's supposed to. Some users subscribe to electronic bulletin boards accessed over telephone lines via modems. Most major software publishers intercept questions posted on them and provide answers to users, who also benefit from the gracious help of other users on the board. A distinct minority of publishers provide registered users with a toll-free number for assistance.

Drawing in 3-D

Before looking at the various programs, let me discuss 3-D programs in generic terms. Ideally, to my mind, it should be possible to feed in the basic two-dimensional information required to describe an object adequately. This

would require the three standard mechanical drawing views, front, side and top, from which a three-dimensional object would be generated automatically. Accomplishing this is easy if you are creating a two-dimensional representation of a 3-D object. Draftsmen do it routinely using one or more projection techniques. The program of my wildest dreams would create objects with irregular convex and concave surfaces or with irregular voids or holes in them, and require minimal effort to accomplish the task.

The following programs are capable of rotating objects (with some individual limitations to be discussed): Swivel 3-D, Mac3-D, Super 3-D, MiniCad, Pegasys, Mac Architron and Dimensions. The last

Objects in Swivel 3-D, as in most programs, can be rotated in all dimensions. The illustrations shown here were transported from Swivel to Adobe Illustrator 88, and then reproduced on a Linotronic 300 typesetting machine.






Figure 2



four listed also create two-dimensional construction drawings, and their relative strengths and weaknesses in two dimensions will be discussed in the second part of my article.

Some of the above programs create three-dimensional extrusions of two-dimensional shapes. Some rotate a two-dimensional shape about a central axis, creating something similar to a lathe-turned object. Several are capable of modeling solids but cannot easily handle voids.

Bearing my fantasy program in mind, let's see how closely each of these programs approaches this ideal.

SWIVEL 3-D Paracomp, Inc., 123 Townsend Street, Suite 310, San Francisco, CA 94107, (415) 543-3848

Swivel 3-D is a truly unique program among its fellows. I can see Swivel as the ideal tool for a designer of children's toys. With Swivel, a number of solid parts, arms, levers, or whatever, may be linked to one another at joint intersections and moved through predetermined arcs or rotated in relation to one another. As a test of these programs I chose to draw one of the knobs from my band saw. I chose it for practical reasons; I needed to send a drawing of it to the manufacturer to assist him in replacing a knob that was lost. The closest I could come to producing the object with Swivel is shown in Figure 2. I couldn't figure out a way of producing a seven-sided polygon as a starting point. Six or eight was the all the program would allow, so I chose six. After choosing a hexagonal cross section, I "crossed" that shape using something called a free poly tool with a symmetrical through-section at 90° to its axis. The free poly tool produces most dramatic results. The best thing about Swivel is that when you change something in the cross section, top or side views, you see immediate results in the three-dimensional one, and vice-versa.

To use Swivel you have to conceive of a complicated object in terms of simple shapes and forms. Once created, these can be assembled to make almost anything. And whatever you make can be viewed in perspective from any conceivable angle. After creating my hexagonal solid, I created a cylinder with a hole in it and linked the two objects on the same axis with the linking tool.

I enjoyed working with Swivel, even though it was impossible to scale my lines. Since there is no provision for sizing them in the program, I had to guesstimate proportions. Also I could find no way to reproduce the knob's complicated curvatures.

Documentation included a tutorial and sample files on disk. I found the program fun to learn and extremely versatile. Dimensioning is impossible and text is not an option, although the results can be copied into other drawing programs with text provisions, mentioned above, and text can be added.

MAC3-D Challenger Corporation, 18350 Kedzie Avenue, Homewood, Illinois 60430, (312) 957-3475

Mac3-D is one of the original, if not *the* original, three-dimensional programs for the Macintosh. It operates in the conventional mode pioneered by Apple Computer in its first drawing program for the Mac—MacDraw. In Mac3-D, when objects are selected, they are highlighted with re-sizing handles. Clicked on and dragged with the mouse, selected objects are changed in size or shape, or both. In Mac3-D, entire three-dimensional surfaces can be moved. Prismatic shapes can be altered by changing the position of a vertex, or single edges may be moved parallel to their original position.

As with Swivel 3-D, closed objects may be shaded, but they may also be filled with patterns and textures. Two-dimensional drawing can be done, but the makeup of this program doesn't encourage it. The shading process in Mac3-D is woefully primitive and slow. I found Mac3-D cumbersome to use and cannot recommend it.

SUPER 3-D™ Silicon Beach Software, Inc., P.O. Box 261430, San Diego, CA 92126, (619) 695-6956

This is a very well-thought-out program, and its excellent features really impressed me. For example, rotation bars are built into the sides of the drawing surface and operate when you drag on them. When they turn they spin like thumbwheels. Really ingenious! Like Swivel 3-D, it shows solid objects in perspective.

Four views are supported simultaneously, and as you change the top, side, or front view, changes in the three-dimen-

sional view occur at the same time. At your option you may fill the screen with any one of the views. It does both extrusions and revolved profiles about a chosen axis to create solid, lathe-turned objects. There are no provisions for creating regular polygons in the tool palette, so I could not create a top view of the knob with its seven scalloped sides. In this program, it is possible to scale objects in generic units, a real plus when getting things drawn in correct proportion is critical. A window, when called upon, will temporarily display the dimensions in generic units of any object you select. Unfortunately, you cannot assign permanent dimensions to the drawing itself. You can enter text, choosing from a number of styles and sizes.

There is an excellent tutorial in the Super 3-D manual. The manual is good, except that there were so many errors in it when originally published that they sent an extensive errata sheet along with it. It took me about twenty minutes to copy these corrections into the manual. The index isn't worth much so I had to hunt around a lot to find answers.

Overall, this is a great program, with a few rough edges.

MINICAD+™ Graphsoft, Inc., 8370 Court Ave., Suite 202, Ellicott City, MD 21043 (301) 461-9488

MiniCad+ is the first of four ensuing dedicated drafting programs which incorporate three-dimensional capabilities on the side. The MiniCad+ 3-D manual is well done and extremely clear. There is no tutorial; you make experiences entirely on your own, but chances of success run high because the various tool and menu options are so well explained. Explanations are easy to locate in the manual.

I liked the way 3-D was implemented in MiniCad+. It relies heavily upon tools and commands in the 2-D module and integrates smoothly with them. But, unfortunately, it does not attain a high level of sophistication.

You cannot create concurrent axonometric views. I was able to create a knob-like object by rotating a profile, but could not link up discrete components to build my knob. Since chairs are built up of discrete parts, there is no way to my knowledge that MiniCad+ could create one in 3-D. And there seems to be no reason to prefer MiniCad+ for designing

cabinets in 3-D either. In fact, if one were to choose a program for 3-D capabilities alone, there would be no reason to pick MiniCad+.

PEGASYS EXPERT™ IGC Technology Corporation, 305 Lennon Lane, Walnut Creek, CA 94598, (415) 945-7300

Pegasys does have tutorials, and one of them is called *Working in 3-D*. Pegasys supports one type of three-dimensional representation, called a "wire frame." Wire frames are lines drawn on invisible planes or surfaces and they outline an object. Because the planes are merely delineated with lines, and not solid, you can see through the lines to other planes behind them. The other 3-D programs mentioned above all support solid, shaded surfaces as well as wire frame ones and do not have this restriction. This does not necessarily condemn Pegasys to a low rank on the totem pole, however. Pegasys is a sophisticated drafting program that offers a 3-D option on the side.

Pegasys does not allow you to combine objects in 3-D, nor can they be edited extensively once they are drawn. I was able to create a seven-sided polygon, properly scaled and dimensioned in millimeters, my unit of choice in the drafting mode. Working with this basic shape I created one scalloped side, which the program allowed me to rotate and duplicate (a great feature) seven times about the center of the polygon. I then deleted the polygon and filleted the arcs internally. I could extrude this two-dimensional shape so that it had an exact thickness of sixteen millimeters. I could rotate it and view it from all angles.

I could also create a cylinder with a hole in it, representing the shaft of the knob. But that was the most I could do with it. I couldn't link the two objects on the same exact axis, and I couldn't reproduce the complex curves of the knob.

Pegasys did not allow me to view changes in three planes simultaneously, nor could I easily or quickly switch from one view to the next. I could not see how the program could be used for creating and linking complex three-dimensional objects, though you might want to use it for drawing cabinets in wire frame, or architectural drawings in which you'd like to peek into

a room with extruded wire frame walls and furniture from all angles.

PLANIT™ Microspot, 21060 Homestead Rd., Suite 207, Cupertino, CA 95014, (408) 739-0326

And speaking of cabinets, we come to Planit. Planit is marketed as a computer-aided kitchen design program. With it, you can lay out predrawn cabinets, appliances, floors, ceilings, and do entire kitchens in perspective viewed from any angle. The hitch here is the word "predrawn." The software manufacturer licenses the system to various cabinet manufacturers and equips your version with catalogs of whatever lines of cabinets exist as options. The demo I evaluated, however, was impressive.

Now why can't you create your own cabinets, you ask? Though not available for me to evaluate, part of the Planit package includes a Catalog Editor, which will enable you to do just that.

MAC ARCHITRION™ Gimeor, Inc., 1815 H Street, N.W. Washington, D.C. 20006, (202) 223-4373

Also in the architectural vein, Mac Architrion, developed in France for the Mac, is a top of the line program whose two-dimensional capabilities will be discussed at length in Part 2 of this article. Of the programs containing both 2-D and 3-D modules, Mac Architrion is the only one which places greater emphasis on 3-D. Purely an architectural application, it makes no claims to be a universal tool. It seemed logical to its developers that two-dimensional plans should be developed from 3-D ones since architects tend to visualize in three dimensions.

Furniture has an architectural form, but unfortunately, furniture with curves cannot be rendered adequately with this program. It is incapable of building complex forms, using only primitive solids as it does. There are no automatic shading features, though surfaces may be individually textured to simulate shading. Creating cabinetry is a distinct possibility, however, as long as the elements can be composed out of blocks. The procedures for rotating objects, defining horizon lines, types of projection, and viewpoints were impressive but they could not be quickly or easily implemented. Making a shape anything like my knob was impossible.

DIMENSIONS PRESENTER™ Visual Information, Inc., 16309 Doublegrove, La Puente, CA 91744, (818) 918-8834

Of all the programs I tried, Dimensions Presenter had the most potential, it seemed to me. Still in preparation by the publisher at the time this was written, the manual in pre-release form promised nirvana. At first glance, Dimensions Presenter looked as though it would allow me to import into it, for three-dimensional viewing, drawings originally created in two dimensions using any one of a number of common 2-D drawing programs for the Mac, including MacDraw, Dreams, and MacDraft. Great, I thought. Anything I've drawn in them, I can recreate in 3-D with Presenter. Not so, Joe.

Presenter will, when its bugs are exterminated, permit us to import a specially created drawing in plan view, one utilizing grouping and layers labeled with special text markers. The object created in 3-D will either consist of extruded shapes or be a lathe-turned profile. Neither of these can be edited further. That's the bad part.

The good part is that you will be able to compose rectangular cabinets using it with your favorite drawing program, or a piece or pieces of furniture with rectangular or circular components and then shade them and view them in perspective from any angle and with any lighting you choose. In this respect, it does Mac Architrion one better.

Now, though I still haven't unearthed the 3-D program that fulfills all of my dreams, I don't intend to end this article on a defeatist note. There is hope for us. First of all, in the next installment of this two-part article, I plan to tell you about some exciting two-dimensional programs I've looked through which I guarantee will draw anything in two dimensions that your heart desires.

Secondly, as concerns the 3-D dilemma, one of the above-mentioned software publishers promises to show me a 3-D program that runs on the Mac Plus and creates and manipulates complex objects of any shape. Another speaks of a soon-to-be-announced 3-D interior design program for the Mac which lets you create and manipulate your own furniture. If this rosy future materializes (or should I say, takes shape?), I promise you'll be the first to know. **PW**

A Popular Woodworking Project



Wall Cabinet

by Devore O. Burch

My friend Bill McGee is an antique dealer. One day in his shop, he showed me an old furniture catalog published around the turn of the century. Bill mentioned how scarce some of these items were becoming and how much they were in demand by his customers. He thought that replicas of some of the pieces in the old catalog would sell very well in his shop, and asked if I would care to make them.

This "wall cabinet" is one of the items we selected from the old catalog. Though I'd be more inclined to call it a shelf, according to the catalog, it's a cabinet.

Devore O. Burch is a woodworker in Fort Worth, Texas.

This is from the "Age of Golden Oak," a period that started before 1890 and began to fade away after 1920, during which time most furniture manufactured in America was made of oak. General dimensions were given in the catalog description of the item, so I scaled the drawing up to these dimensions and made a batch of 12. This wall cabinet was offered in either golden oak or walnut finish, and it sold for \$2.70 retail in 1900 with a bevel-edged mirror; I got \$175.00 apiece wholesale for my reproductions, but Bill never told me his retail asking price.

The Back Panel and Shelves

A full-size pattern for the back panel (A) is in the PullOut™ Plans section in the





photo by David Camp

center of the magazine. Tape the two pages of the plans together at their edges where shown by the shaded area, and trace the pattern onto some butcher paper or drafting velum. Make the back panel by gluing up 3/4" stock to the rough width and length given in the cutting list. Scrape the surfaces, and choose which will be the front, then draw the pattern on the back. Since the panel is symmetrical about the vertical center line, the PullOut™ Plan is for one half of the panel. Mark the vertical center line on the panel, line up the pattern with the center line, and mark the outline on the panel. Flip the pattern to the other side of the center line to mark the rest of the panel outline. In addition to the mirror



cutout indicated on the panel pattern, trace the mirror pattern onto the back of the panel to show the edge of its recess (see Figure 1).

Drill holes for #10 $\times$ 1-1/2" flat head wood screws at the shelf locations, then put a 3/8" bit in the drill press and bore holes in the round areas at the top of the pattern. Bore starter holes for the two cutouts at the top and the mirror cutout while you're at the drill press. Locate the mirror starting hole close to the edge so you can use the cutout for the two half shelves (B). Bore 1/2" holes for the two

buttons at the top.

Saw out the perimeter with a band saw or a sabre saw and smooth the edges with files, sandpaper and, if possible, a sanding drum. Rout a quarter-round edge inside the mirror cutout, then rout the rabbet on the back for the mirror to nest into.

Trace the patterns from the PullOut™ Plans section for the half shelves (B) and the full shelves (C) onto the stock and cut them out. Drill 1/2" holes halfway into the bottom surface of the top shelf and the top surface of the bottom shelf for the support spindles (D). Rout a nice shape on the

Wall Cabinet					
Cutting List					
Qty	Part	Rough Size			Piece
		T	W	L	
1	A	3/4"	23"	25"	back panel
2	B	3/4"	3 1/2"	6 1/8"	half shelves*
2	C	3/4"	4"	13 5/8"	full shelves
2	D	1 1/4"	1 1/4"	15"	support spindles
2	E	3/4"	1 1/2"	18"	outer split turning pieces **
2	F	1 1/4"	2 1/2"	10"	center split turning pieces **
1	G	1/8"	8 1/4"	10 1/4"	mirror retainers
Supplies					
2	1/2" buttons				
#10 × 1 1/2" flat head wood screws					
#4 × 1/2" flat head wood screws					

* make from mirror cutout

** join face-to-face to make one turning blank

front edges of the shelves.

Spindles and Split Turnings

Turn the support spindles on the lathe by first marking the transition points as indicated on the pattern. Since this is full size, you can set your calipers right to the different diameters to check your work.

The other turned pieces in this project (E and F) are split turnings. Cut the pieces for each to the rough size given in the cutting list, then put them together to do the turning. The traditional method for making split turnings is to glue a piece of paper between the wood halves, split the halves apart after the turning is complete, then sand off the remaining paper. I prefer to join the two halves together with a wood screw through each end in the scrap area. (Be careful to mark the shoulders well away from the screws.) After turning, simply remove the screws to separate the halves.

I like to finish turned pieces right on the lathe, and I chose to stain these with a 50/50 mix of golden oak and mahogany brown NGR stain. Irregular shapes and turnings lend themselves well to the modern penetrating oil finishes such as Minwax or Watco.

Assembly

To drill pilot holes for the shelf screws, I found it easiest to clamp the shelves to a two-by-four batten and clamp the batten to the back panel, as shown in Figure 2. That way the two half shelves (B) could be perfectly lined up and held square to the panel. Screw all the shelves to the back panel without glue and apply your finish. Mask off the areas where the split turnings will be glued on so the finish won't interfere with the adhesion.

When the finish is thoroughly dry, glue and screw the shelves to the back panel. Glue the outer split turnings (E) where they contact the back panel at each end, and attach one half of the center split turning (F) to the top of the panel (discard the other half, or use it on another wall cabinet). Apply the buttons and give another coat of finish to the whole project.

After all the parts are finished and assembled, the final operation is to install the mirror. A plain mirror may be used, but if you can have your mirror bevelled, it will add to the authenticity. The mirror retainer (G) is made from 1/8" hardboard and is attached with four #4 $\times$ 1/2" flat head wood screws. **PW**




Figure 1




Figure 2

The Audio/Video Cabinet

by **Hugh Foster**

My latest customer was making his first big foray into the wonderful world of high fidelity. He was going to transform his living room and his life of silence with an audiophile system composed of a 26" TV monitor, a video cassette recorder, a compact disc player, a turntable, and a powerful receiver. All these components had to fit into one walnut box.

We came up with this design that features adjustable shelves in the component storage area (including a sliding shelf for the turntable) and a cupboard with another adjustable shelf beneath the TV. The cupboard doors stick up past the TV shelf so that fingers can pull them open from the top, thus eliminating the need for knobs. The European hinges for the cupboard and the glass door are readily available from mail order sources; the glass itself can be cut to size by your local glass merchant and it doesn't have to be drilled for the hinges.

My client didn't want dovetails, so the carcase is assembled with dado joints and reinforced with triangular glue blocks.

Start by making up the panels. You might choose to use a hardwood plywood, in which case you will need to allow for facing all exposed edges when you cut the panels to size. I glued up panels of solid walnut—except for the component shelves (A) which I made out of birch plywood with walnut facing attached to the front edge. Make your facing as wide as you want (3" would suffice) so long as the overall dimensions equal those given in the cutting list.

When the panels are ready, cut the sides (B), partition (C), bottom (D), top (E) and the TV shelf (F) to size according to the cutting list. Orient the parts as to their position in the cabinet and lay out the dadoes as indicated in Figure 1.


I like to cut my dadoes with a router and a T-square. Made like a draftsman's


Hugh Foster is a part-time furniture designer/builder in Manitowoc, Wisconsin.



photo by the author

Figure 1





T-square, this serves as a straightedge to guide the router. The first cut you make will cut into the stock of the square creating a reference point with which to locate the T-square (see Figure 2). I keep a separate T-square for each size bit I use for cutting dadoes.

In this case, it's a $\frac{3}{4}$ " bit, set to cut $\frac{1}{2}$ " deep dadoes. The two dadoes that accept the TV shelf (F) should stop $\frac{3}{4}$ " from the front of the cabinet to allow for the overlapping doors (G). Stop the dadoes for the bottom (D) and the partition (C) at $\frac{1}{2}$ " from the front edge. Square the ends of the dadoes with a chisel later.

While you've got the router out, cut $\frac{5}{8}$ " wide $\times$ $\frac{3}{16}$ " deep grooves for shelf standards that run the length of the left side of the cabinet and inside the cupboard area on the right side of the cabinet. (I located these grooves at 3" from either edge.)

In order for the bottom and the partition to fit in their dadoes, you'll need to

Audio/Video Cabinet Cutting List

Qty	Part	Finished Size			Piece	Qty	Part	Finished Size			Piece
		T	W	L				T	W	L	
5	A	3/4"	16"	187/8"	component shelves	1	P	1/4"	253/4"	121/4"	short back
2	B	3/4"	18"	43"	sides	1	Q	1/4"	151/4"	17"	turntable shelf
1	C	3/4"	18"	40"	partition	2	R	1/2"	1"	151/4"	side trim
1	D	3/4"	18"	473/4"	bottom	1	S	1/2"	1"	18"	front trim
1	E	3/4"	19"	50"	top	1	T	3/4"	16"	267/8"	wide shelf
1	F	3/4"	171/4"	28"	TV shelf	Supplies					
2	G	3/4"	131/2"	15"	doors	2pr	European style hinges*				
2	H	3/4"	11/4"	463/4"	top rails	1pr	glass door hinges*				
2	I	3/4"	1"	19"	tall back rails	1pr	turntable slides*				
2	J	3/4"	1"	27"	short back rails	4pr	15/8" casters				
2	K	3/4"	1"	38"	tall back stiles	1	U	1/4"	183/4"	373/4"	glass door
2	L	3/4"	1"	131/4"	short back stiles	28	shelf clips				
12	M	3/4"	3"	3"	corner blocks	20	panel-retaining buttons**				
2	N	3/4"	31/4"	463/4"	toeboards	8	#10 X 11/4" rnd. hd. screws w. washers				
1	O	1/4"	173/4"	363/4"	tall back		shelf standards (18')				
*Allen Specialty Hardware, 332 W. Bruceton Rd., Pittsburg, PA 15236											
**The Woodworkers' Store, 21801 Industrial Blvd., Rogers, MN 55374											

*Allen Specialty Hardware, 332 W. Bruceton Rd., Pittsburgh, PA 15236

**The Woodworkers' Store, 21801 Industrial Blvd., Rogers, MN 55374

illustrations by Tom Larson




Figure 2

cut $1/2" \times 1/2"$ notches in the appropriate corners. Mark and cut these notches carefully because a sloppy fit here will look pretty bad. The partition will also need a $3/4" \times 1"$ notch cut out of both edges at the top to accept the top rails (H).

The cabinet has no back over the TV area because the picture tube sticks out. I installed rabbeted frames that accept

removable backs behind the cupboard and the component shelves. To make these frames, first dry-assemble the cabinet and measure the two openings they will fill. Cut the rails (I and J) and stiles (K and L) with mitered ends to fit these openings. Spline the joints and glue up these frames; when they're dry, glue the carcass together using these frames to


help square it up. Install the corner blocks (M) with glue and screws in all eight corners at the top, then lay the cabinet upside down and install the two toeboards (N) with four more corner blocks. While I had my cabinet upside down, I applied the finish to the underside and installed the casters.

Rout a $1/4"$ deep $\times 3/8"$ wide rabbet into the two back frames to accept the backs (O and P). Cut the backs to size and install them with panel-retaining buttons (see supply list) so they can be removed as necessary for hooking up the stereo components.

The turntable shelf (Q) slides out on special hardware that mounts to the underside and is secured to one of the component shelves (A). I made walnut trim pieces (R and S) to cover the sides and front of the shelf so the hardware would be hidden. When you've decided on the location of this shelf, drive a couple of screws at an angle through the component shelf and into the carcass to keep it from sliding out with the turntable shelf.

Mount the top (E) by driving screws up through the corner blocks. Drill over-size holes in the corner blocks and use round head screws with washers to allow for wood movement. Apply the finish of your choice and hang the doors according to the instructions provided with the hinges. Your completed audio/video cabinet may very well outlast the components that are in it.

Figure 3



Illustrations by Tom Larson

A Popular Woodworking Project

Pushcarts

photo by the author

by Kingsley Hammett

Pushcarts as a form of free enterprise are probably as old as time. Literature is filled with rags-to-riches tales of immigrants who rose from the streets of New York to become retailing giants. Your goals may be more modest: to sell your wooden Christmas tree ornaments once a year at the local mall, or to give a teenager a business experience selling sodas at the softball park, or to serve as a display in front of your florist shop. Whatever the use, the basic pushcart is little more than a box on wheels. This cart was designed to be used to sell drinks and snacks at a Fourth of July parade. It rolls on bicycle wheels, has a door in the back and four panels on top that allow access to the inside.

Kingsley Hammett is a licensed general contractor in New Mexico. He is also the Editor and Publisher of New Mexico Business Opportunity News.

illustrations by Tom Larson

Figure 1




Figure 2






photo by the author



This drop-leg assembly helps level the cart on uneven terrain. A full-size pattern for the handles (V) can be found in the PullOut™ Plans section.



Begin by cutting the sides (A), bottom (B) and ends (C) to size according to the cutting list. Cut the pieces from a single sheet of plywood as shown in Figure 1. Cut the door opening in one of the end pieces with a sabre saw to the dimensions shown in Figure 2, and save the cutout to use for the door.

To assemble the body of the cart, first attach the bottom braces (D and E) to the bottom like a frame, using glue and 1-3/4" drywall screws. Attach the vertical braces (F) flush along the vertical edges of the end pieces (C) with their bottom ends positioned

2" away from the bottom edges of the ends (see Figure 2). Attach the ends to the bottom by gluing and screwing them to the bottom end braces, then apply the sides (A).

The lids (G) have 3/4" finger holes and fit down between the sides of the pushcart and rest on ledgers (H and I). Cut the ledgers to size, and install them so their top edge is 3/4" below the top edge of the cart.

If you want to use an umbrella with your pushcart, bore an appropriately sized hole in the upper cross piece (J) and in a lower cross piece (K) that can be attached to the bottom (this piece is not necessary if you don't want to use an umbrella). Lay all the lids and the upper cross piece on the ledgers and screw the cross piece in place.

To support the bicycle wheels used in this cart, I made a sort of bicycle fork out of 2" wide flat steel. I had two pieces bent to shape at a welding shop, and had them notch the bottoms of each to accept the wheels and drill holes to accept the 1/2" bolts that attached the forks to the cart. Install these forks about 2" to 3" past the center of the cart and fasten the two backup boards (L) to the sides on the inside of the cart. Attach the wheels with 1/2" wing nuts—this enables you to remove the wheels easily so you can carry the cart in a station wagon or truck without it rolling around.

Make the drop-leg assembly by gluing the small blocks (M) to the cover block (N) and then screwing this assembly to the front end (C) on center. Drill the hole for the bolt and wing nut and cut the slot in the leg (O). Slide the leg into the opening and fasten it with a 1/2" bolt and wing nut.

Miter the ends of the top trim pieces (P and Q) and attach them to the top edges of the cart. Attach the end trim pieces (R) flush to the corner of the cart and then apply the side trim pieces (S) so that they overlap the end trim. Miter the door frame pieces (T and U) and attach them to the cutout piece you saved with a 1" lip all around.

Cut out the handles (V) on the band saw using the full-size patterns in the PullOut™ Plans section at the center of the magazine. Rout the edges with a 1/4"

Pushcart					
Cutting List					
Qty	Part	Finished Size			Piece
		T	W	L	
2	A	1/2"	24"	47 3/4"	sides
1	B	1/2"	23"	48 3/4"	bottom
2	C	1/2"	23"	24"	ends
2	D	1 1/2"	1 1/2"	23"	bottom end braces
2	E	1 1/2"	1 1/2"	43 3/4"	bottom side braces
4	F	1 1/2"	1 1/2"	22"	vertical braces
4	G	3/4"	10 3/4"	23"	lids
2	H	3/4"	2"	43 3/4"	side ledgers
2	I	3/4"	2"	20"	end ledgers
1	J	3/4"	3 1/2"	23"	upper cross piece
1	K	1/2"	3 1/2"	20"	lower cross piece *
2	L	3/4"	3 1/2"	19 1/4"	backup boards
2	M	3/4"	7/8"	4"	small blocks
1	N	3/4"	4"	5 1/2"	cover block
1	O	3/4"	3 7/8"	24"	leg
2	P	3/4"	1 1/4"	49"	long top trim pieces
2	Q	3/4"	1 1/4"	25 1/4"	short top trim pieces
4	R	3/4"	2 1/2"	24"	end trim pieces
4	S	3/4"	3 1/4"	24"	side trim pieces
2	T	3/4"	2"	18"	horizontal door frame pieces
2	U	3/4"	2"	19"	vertical door frame pieces
2	V	3/4"	4"	20"	handles
2	W	3/4"	3 1/2"	8 3/4"	spacer blocks

* optional

round-over bit and bolt them and their spacer blocks (W) to the sides of the cart.

Paint the cart with bright colors and add some flags or streamers as attention-getters if you like. Now you're in business—no lease, no overhead, and you make your own hours. What could be better? **PW**

Supplies

2	bicycle wheels (w. wing nuts)
2	custom wheel brackets
4	1/2" X 1 3/4" bolts (w. washers & nuts)
4	1/2" X 2 1/4" bolts (w. washers & nuts)
1	1/2" X 1 1/2" bolt (w. washer & wing nut)
2	butt hinges
1	door latch
	1 3/4" drywall screws

illustrations by Tom Larson

Wine Rack/End Table

by Ray Day

For those who enjoy a variety of wine, some kind of storage is a necessity. A wine rack is useful for storing the bottles on their sides, but store-bought racks often present another problem—where do you put the rack?

I designed a wine rack that serves a function in addition to the storage of wine; I added a top so it could also serve as a table. This piece of furniture has storage for twelve wine bottles and looks great in a den, family room, bar area, or any other convenient spot.

I used mortise and tenon joinery throughout the project. The cross pieces for the bottles (A) are joined to the rails (B) with round tenons, while all the rails are fastened to the legs (C) with $\frac{1}{4}$ " $\times$ 1" $\times$ $\frac{1}{2}$ " long tenons (see Figure 1a).

Although I constructed this wine rack/end table from red oak, it can be made from any lumber you select. All pieces are from 4/4 stock, and 10–12 board feet will suffice to complete the project.

Begin construction by edge-gluing enough boards to make up the top (D). Make the piece wider and longer than necessary so it can be cut to size later.

While the top is drying, cut all the other pieces to the finished sizes indicated in the cutting list. Note that all the rails (B and E) and legs (C) are 1- $\frac{1}{2}$ " wide, so they

can be ripped at the same time. It is best to rip them slightly wider than necessary and then bring them to their finished width on a jointer after cutting them to length. The length specified in the cutting list includes $\frac{1}{2}$ " tenons on each end.

For the cross pieces (A) you have three choices for joinery. I used a round tenon cutter on a drill press to cut $\frac{1}{2}$ " diameter $\times$ $\frac{1}{2}$ " long tenons on the ends of the braces. An alternative is to cut the pieces 1" shorter than indicated on the cutting list, and use $\frac{3}{8}$ " $\times$ 1" glue dowels to join them to the rails. A third possibility is to just use $\frac{3}{4}$ " dowel rods that are 10- $\frac{1}{2}$ " long for the cross pieces. If this last option is selected, be sure to drill the $\frac{3}{4}$ " holes in the front and rear rails exactly $\frac{1}{2}$ " deep so the shelf assemblies measure 11" from front to back. The dowels will need to be bevelled on the ends for glue relief. For the other two methods, the holes can be drilled $\frac{9}{16}$ " deep for glue relief.

Once all pieces are cut and jointed to finished size, cut all the mortises in the legs for the rails as shown in Figure 2. Cut

the mortises on one face of the legs, then orient them right to left and front to back to choose the edges that will receive the mortises for the end rails (E). I used a router mounted on a router table with a $\frac{1}{4}$ " straight bit to cut the mortises. Since all the mortises are centered on the legs, the ones on the faces can all be cut with the same set-up. You'll have to adjust the fence for the mortises on the edges.

Cut the tenons on all the rails. To do this you can set a $\frac{1}{2}$ " wide dado head to cut $\frac{1}{4}$ " deep, position a wooden auxiliary fence to act as a stop, and make a pass on all four surfaces at each end. I used a tenoning jig and miter gauge to cut the tenon cheeks and shoulders with a regular blade instead of a dado head set. If you cut your mortises with a router, you will have to round the corners of the tenons with a file to make them fit the mortises.

Next, drill five holes each in six of the eight rails to accept the cross pieces. The hole diameter ($\frac{1}{2}$ ", $\frac{3}{8}$ ", or $\frac{3}{4}$ ") will depend on the method you selected for joining the braces to the rails. Regardless





photo by the author

Ray Day is the Editor of Wood Matters, a newsletter about woodworking and the owner of A Day's Work, a small furniture-making and plans shop in Iowa City, IA.

Trim the top (A) to finished size and rout an edge detail that appeals to you on all but the back edge. Stain and finish the

Technical drawing of a rectangular plate. The overall dimensions are 19 3/4" in height and 1 1/4" in width. The plate features four rectangular cutouts, each 1" high. The top cutout is positioned 5/8" from the left edge and 1/4" from the top edge. The other three cutouts are spaced evenly along the height. The bottom cutout is 1" from the bottom edge. The drawing includes dimension lines and arrows indicating the measurements.

Technical drawing of a vertical plate with four circular holes. The plate has a total width of $3\frac{3}{4}$ " and a total height of $15\frac{5}{8}$ ". The four holes are spaced vertically at intervals of $3\frac{3}{8}$ ". The holes are located at the top and bottom of the plate, with the top hole centered at a distance of $15\frac{5}{8}$ " from the top edge and the bottom hole centered at a distance of $3\frac{3}{8}$ " from the bottom edge. The holes are also spaced horizontally at intervals of $3\frac{3}{8}$ ". The plate has a rounded right edge and a small rectangular notch at the top center.



Illustrations by Tom Larson

Build each shelf as a separate subassembly.




photo by the author

Wine Rack/End Table					
Cutting List					
Qty	Part	Finished Size			Piece
		T	W	L	
15	A	3/4"	3/4"	10 1/2"	cross pieces
8	B	3/4"	1 1/2"	16 3/4"	rails
4	C	3/4"	1 1/2"	19 3/4"	legs
1	D	3/4"	12 1/2"	18 3/4"	top
2	E	3/4"	1 1/2"	9 3/4"	end rails
Supplies					
8	table irons				

top and the base separately. Then lay the top upside down on your workbench, and position the base so the back of the top is flush with the back of the rear legs and the base is centered side to side. Secure the top with table irons, then celebrate with a crisp Chardonnay. **PW**

Calendar

Events of Interest to Woodworkers

*If your group is having an event you would like other woodworkers to hear about, please send us all pertinent information at least three months before the opening date. We will publish it for you in **Calendar** free of charge.*

June 1—July 2, Seattle, WA

A one-man show of work by furnituremaker Grady Mathews will be presented at the Northwest Gallery of Fine Woodworking, at 202 First Avenue South, Seattle, WA 98104, Tel. (206) 625-0542. Gallery hours are Mon-Sat 10:30 to 5:30, and Sun 12:00 to 5:00.

June 2—4, Oklahoma City, OK

A show will be held by the Oklahoma Woodcarvers Club at the Penn Square Mall, N.W. Highway and Pennsylvania, Oklahoma City. For more information, contact: Jim Crist, 2000 N. Purdue, Oklahoma City, OK 73127, Tel. (405) 943-8107.

June 5—June 16, Fort Bragg, CA

A course entitled *Basic Carving* will be presented by The College of the Redwoods Fine Woodworking program. The

course is designed for beginning and intermediate woodworkers, and will run from 8:30 to 5:30 pm. in the college's Fine Woodworking shop. The fee is \$10 for California residents, and \$147.00 for out-of-state tuition. For more information, contact: College of the Redwoods, 440 Alger Street, Fort Bragg, CA 95437.

June 20—25, W. Springfield, MA

The Original Rhinebeck Craft Fair will be held at the Eastern States Exposition, 1305 Memorial Avenue, West Springfield, MA. For more information, contact the ACC Crafts Fairs at P.O. Box 10, 256 Main Street, New Paltz, NY 12561, Tel. (914) 255-0039.

June 26—July 14, Fort Bragg, CA

A course entitled *Introduction to Fine Woodworking Tools & Techniques* will be presented by The College of the Redwoods Fine Woodworking program. The course is designed for beginning and intermediate woodworkers, and will run from 8:30 to 5:30 pm. at the college's Fine Woodworking shop. The fee is \$15 for California residents, and \$249.00 for out-of-state tuition. For more informa-

tion, contact: College of the Redwoods, 440 Alger Street, Fort Bragg, CA 95437.

July 3—7, Marshall, NC

A course on Japanese woodworking will be given by Carl Swensen, including instruction on how to fine-tune and sharpen Japanese hand tools, followed by making a joined woodworker's tool box with a sliding lid. Course presented by the Country Workshops, 90 Mill Creek Road, Marshall, NC 28753, Tel. (704) 656-2280. Tuition is \$250 for the 5-day class, and includes Louise Langsner's famous home cooking. Camping and dormitory facilities available. For more information, contact Drew Langsner at the above address.

July 9—August 12, St. Louis, MO

The Turner's Challenge, the third annual exhibition of lathe-turned objects, will present the newest work of 65 renowned international artists. For more information, contact: Wood Turning Center, P.O. Box 25706, Philadelphia, PA 19144, Tel. (215) 844-2188.

July 7—9, Tulsa, OK

The Eastern Oklahoma Woodcarvers



EXOTIC & DOMESTIC HARDWOODS

LUMBER • PLYWOOD • VENEERS

BALSAWOOD ■ BUBINGA ■ COCOBOLO ■ EBONY ■
GONCALO ALVES ■ GRANADILLO ■ JATоба ■
KINGWOOD ■ LACEWOOD ■
MACACAUBA ■
MAHOGANY ■ MAPLE
(BIRD'S EYE AND CURLY)
PADAUK ■
PURPLEHEART ■
ROSEWOOD ■
SATINWOOD ■ TEAK ■
TULIPWOOD ■ WENGE ■
ZEBRAWOOD

(516) 378-2612

West System
Brand
Epoxies



Wood-Ply
Lumber Corp.

100 BENNINGTON AVE., DEPT. PW
FREEPORT, NY 11520



Association will hold its thirteenth annual National Show on July 7, 8 and 9, at the Kensington Galleria Shopping Mall, 71st and South Lewis, Tulsa, OK 74011. For more information, contact Dale Hill, Rt. 1 Box 75, Broken Arrow, Oklahoma 74011, Tel. (918) 455-8683.

July 17—August 11, Ft. Bragg, CA

A course entitled *Fine Woodworking Projects* will be presented by The College of the Redwoods Fine Woodworking program. The course is designed for beginning and intermediate woodworkers, and will run from 8:30 to 5:30 pm. at the college's Fine Woodworking shop. The fee is \$22.50 for California residents and \$441.00 for out-of-state tuition. For more information, contact: College of the Redwoods, 440 Alger Street, Fort Bragg, CA 95437.

July 17—21, Marshall, NC

A course on *Green Woodworking* will be given by Drew Langsner, including instruction on riving, shaving, hewing and bending. Projects include making a firewood tote and a large dough trough. Course presented by the Country Work-

shops, 90 Mill Creek Road, Marshall, NC 28753, Tel. (704) 656-2280. Tuition is \$250 for the 5-day class, and includes Louise Langsner's famous home cooking. Camping and dormitory facilities available. For more information, contact Drew Langsner at the above address.

June 22—25, Nazereth, PA

Symposium 89, a national exposition of stringed musical instrument making and repair, will be held on the campus of Lafayette College, 14 South Broad Street, Nazereth, PA. The Symposium will feature lectures, workshops, and demonstrations from many of the key people in the instrument making field. Application deadline is June 10, 1989. Early registration is recommended. For more information, contact: Symposium 89, 14 South Broad Street, Nazereth, PA, Tel. (215) 759-7100

July 23—28, Blue Earth, MN

The Seventh Annual Upper Midwest Woodcarving Exhibition, a juried show,

will be held by the Royal Chisellers Wood Carvers Club. For more information, contact: Harley Schmitgen, 311 East 14th St., Blue Earth, MN 56013, Tel. (507) 526-2777.

August 7—11, Richmond, CA

The Lumber Drying Short Course features such topics as drying fundamentals, controlling defect development, use and maintenance of equipment, reducing costs and increasing quality. The course includes lectures, demonstrations and lab exercises. Enrollment is limited to 25 and the fee is \$300. For more information, contact Tom Breiner, UC Forest Products Laboratory, 1301 South 46th St., Richmond, CA 94804, Tel. (415) 231-9487.


The First ECONOMICAL Scrollsaw That Works Like THE REAL THING

Save with Our Package Deal

A \$204.85 Value, now just

\$149.95
plus \$6.00 shipping
(within 48 states)

You Receive
Free Books & Blades
Worth \$31.85



DELTA

SCROLLSAW TECHNOLOGY took a giant leap forward in the late 1970's when a German manufacturer first introduced the rocking parallelogram mechanism along with a floating blade clamp system, features which dramatically increased blade life and cutting precision.

DELTA NOW MAKES THESE FEATURES highly affordable in its new 15" model 40-150 scrollsaw. It weighs 37 lbs., has a 2-year limited warranty, and performs superbly!

WHILE SUPPLIES LAST, save big by ordering our Delta Scrollsaw Package Deal, which includes the 40-150 scrollsaw (list price \$173), 62 assorted spare blades (worth \$22), 2 bestselling toy pattern books (\$5.90 value), plus our own Scrollsaw User's Guide (a \$3.95 value).

YOU SAVE \$54.90!


To order, send check, M.O. or MC/Visa info.
Send \$1.00 for our complete tool catalog
(free with order).

MC/Visa Users outside GA
ORDER TOLL FREE
(800) 241-6748
(Orders Only)

highland hardware

1045 N. Highland Avenue, Dept. P
Atlanta, GA 30306 (404) 872-4466

38" High
Solid Wood



Rocking Horse Kit

Build this beautiful 38" rocking horse yourself, and have a family heirloom. Our rocking horse kit includes solid wood parts cut and shaped, with all trim included, for only \$69.00 ppd. Check or M.O. accepted.

Tampa Wood Products, Inc.
P.O. Box 14426, Tampa, Florida 33690
Phone: (813) 251-6583

SCROLL SAW LETTERS EASILY...



...with **Lettering Layout Guides!**

- Name Plates
- Signs
- Gifts and more


Our unique Lettering Guides are available in many styles and sizes to suit your needs. Upper and Lower Case Script and Block Styles...and numbers too. Send \$1.00 for brochure and prices to:

SEYCO SALES

1414 Cranford Drive
P. O. Box 472749
Garland, TX 75047

WOOD PARTS

TOY, FURNITURE, CRAFT & GAME



Wheels • Spindles

• Balls • Knobs

• Shaker pegs • And more!

Since 1927! Send \$1.00 for Catalog.

BROWN WOOD PRODUCTS CO.

P.O. Box 8246PW
Northfield, IL 60093 • (312) 446-5200



PACIFIC BRASS HARDWARE



Dept. P.W.

1414 Monterey Avenue,
Victoria, B.C. Canada V8S 4W1

Catalogue \$2.00

Trade Enquiries always
welcomed

Focus on Carving

Carving Carousel Animals - Part 2




photo by the author

by William H. McMaster

In the last issue of *PW* (April/May 1989), I told some of the history of the carousel, gave a pattern for "Rosebud" and described three recognized styles of carving carousel animals. In this article I shall present patterns of horses representing each of the three styles. These patterns are one-tenth scale, which is one of the most common sizes for woodcarvers and can be carved in 1-1/4" thick wood. You can enlarge or reduce them further to obtain another scale; however, if you plan to carve all the animals in this collection,

William H. McMaster is Chief of the Education Division of the California Carvers' Guild. His "Focus on Carving" is a regular feature in PW.

you should carve them all at the same scale. "Bubbles" and "Lillie Belle" are smaller horses because they are from the smaller traveling carousels which typically had animals that were three feet long, instead of four feet long.

The horses were always the most popular animals on the carousel, therefore any collection should consist mostly of horses. The patterns presented here will help you get started, but if you truly desire to make an authentic copy, I would suggest that you refer to photographs of the original carvings. A reference for each horse will be given with its description, and you can get the books from your library or bookseller. From these photographs you can also see the original colors

of the painted horses.

As mentioned in the last issue, you will need a holding tab for clamping the work while carving these horses. Figure 1 shows where I placed mine. For a small "Military Mueller" the size of this pattern, I would place it above the saddle so that there is space to work on the legs. The other two horses can have theirs below the belly—"Bubbles" definitely so, because of the intricately carved leopard skin over the saddle, and "Lillie Belle" since her legs are placed in the flying gallop pose giving you plenty of room to work on them.

Again, if you have any problems envisioning the piece, I would definitely recommend that you make a clay model

before starting to carve. The armature arrangement shown for "Rosebud" in the previous issue is also appropriate for these horses.

"Bubbles" and "Lillie Belle" are both jumpers so you will have to plan ahead for the support pole. The patterns show where the pole should be placed. Since we are using a holding tab in this same area, the tab should be placed behind the location of the hole. It is easiest to drill this hole before you start carving. I do not favor a pole going all the way through the horse as you see in many ceramic renditions. I prefer to follow the lead of many museums and private collectors and use the pole only to support the animal. After all, the purpose of our art is to emphasize the carousel animal.

After bandsawing out the pattern, the next step is to separate the legs. Do this by removing wood to the center of the block for each leg. This assures that they end up on the correct side of the horse. Do not go much further than halfway, since the legs should be carved from the outside first to assure that you leave enough wood to carve the legs correctly.

When carving these horses, make sure that each horse's hoofs are all the same size. Draw a template and make frequent measurements. It's very easy to mismatch them and this really detracts from the finished carving.

The patterns for these horses are for the "romance" side only. The off-side is just a simplified version, so you do not need detailed plans. However, you should sketch the position of the off-side legs on the plastic pattern you make to guide your carving of the details.

Philadelphia Style

In the Philadelphia style the emphasis was on realism and classic elegance. These designs were dominated by the Gustav Dentzel Company and the Philadelphia Toboggan Company.

In 1860, at the age of twenty, Dentzel arrived alone from Kreuznach, Germany and opened a cabinet shop in Philadelphia. In Germany, his family had had experience in carousel carving, so after he became established, he built a small carousel to test the American public's reaction. The response was so enthusiastic, he redirected his business to carousels in 1867. This was the beginning of the American carousel. He was the first to use steam engines to power his carousels, and

his factory remained in business until 1928. They produced one to two carousels a year, each custom built. His horses are beautifully proportioned, graceful, and have lifelike expressions. The Dentzel company employed many of the most famous carousel carvers.

The lead horse in this series is known as "Military Mueller" and was carved by Daniel C. Mueller, who sometimes worked for the Gustav Dentzel Company. Like most of the prominent carousel car-

ers of the time, Mueller was also an immigrant. However, his art education was more extensive than the others as he attended the Pennsylvania Academy of Fine Arts and was a sculptor in stone as well as wood. Mueller's horses were the most realistic of all the American carvers. They were based on the Arabian stallion, and he favored Civil War and circus trappings for his horses. A good picture of the original horse for this pattern is shown on page 61 of *The Carousel Animal* by Tobin




Figure 1. Location of Holding Tabs

Fraley and Gary Sinick.

The characteristics to note in the carving of this horse are the typical pompador that Mueller used for the forelock and the Civil War McClelland saddle with traditional cavalry tack. The horse is anatomically correct, so be sure to put in all the muscles properly.

One thing to note in the carving is that this horse has a very slight tilt to the head which cannot be shown adequately in the


pattern. Be sure to put this in, since no matter how subtle, it greatly enhances the appeal of the carving. Nothing is worse than a figure that is completely symmetric. The head should tilt toward the romance side, and carve the eye as though the horse is looking at the rider. A more detailed and enlarged drawing of his head is given in Figure 2. This drawing identifies and emphasizes some of the anatomical features that should be carved to en-

hance your horse. These details can be used as a reference for the other two horses.

"Military Mueller" is held to its base by small dowels in each of the three standing legs. Drill holes for these before carving the legs. Then glue a dowel into the hoofs after the carving has been completed. Don't glue the dowels into the base because wood movement might break your horse. The dowels should

Full-Size Pattern

illustrations by the author



"Military Mueller" – Daniel Mueller, 1924






Figure 2. Facial Features



Legend

1. Cylindrical muscle region above eye
2. Triangular frontal bone
3. Groove
4. Triangular depression
5. Zygomaticus muscle
6. Facial vein
7. Masseteric ridge
8. Facial dish
9. Levator muscle
10. Nasal peak
11. Zygomatic arch
12. Depressor muscle

Full-Size Pattern



"Bubbles" – Stein & Goldstein, 1908

extend at least 1/2" below the hoof.

Coney Island Style

These animals displayed the flamboyance and glitter of Coney Island, which was the entertainment center of the East at that time. The animals on these carousels had exaggerated features and were trimmed with gold leaf and jewels. On your scaled miniatures, you can use costume jewelry to decorate your animals.

Our example of this style is the horse known as "Bubbles," which was produced by the company of Stein and Goldstein. Solomon Stein and Harry Goldstein were immigrants from Russia who started out in this country carving ladies' wooden combs. When they shifted to carousels they both carved their own animals. Their company lasted only until 1918. Many of their horses are reminiscent of the heavy-boned chargers that bore knights during the Middle Ages and were adorned with armor. Other horses like "Bubbles" portrayed aggressive animals carved in a running-free style. One version of this horse can be found on page 148 of *Painted Ponies* by William Manns and Peggy Shank.

This horse is characterized by a long neck and a growling leopard skin laid

over the saddle. Both the horse's head and that of the leopard are turned outward (towards the romance side). Note the orientation of the very definite tilt to the head. Be sure to block it out carefully before carving and don't cut the mouth open while bandsawing. It should not be carved until the head has been formed so that the proper tilt can be attained.

Country Fair Style

The animals carved in the Country Fair style have a definitive folk art look; they were generally smaller, and were designed to be used on the traveling carousels. This style originated in upstate New York near North Tonawanda with Allan Herschell whose company made "Rosebud," the horse that was the subject of last issue's column. "Lillie Belle", who also represents this style, was made by the C.W. Parker Company and was one of their most admired carvings. A photo reference for this horse can be found on page 105 of *Art of the Carousel* by Charlotte Dinger.

The Parker Company, established in 1892, was located in Abilene, Kansas and offered the first real competition to the Eastern companies. They made only horses and these were highly stylized


and adorned with Americana of the Midwest. Their horses used extended running positions with nostrils flaring and open flowing manes. One of the stories associated with the Parker factory was that President Dwight Eisenhower worked as a sander for the company when he was a teenager.

Our horse, "Lillie Belle," is characterized by her long body and very stylized flying mane. This is a pierced design with the individual bunches of hair carved to look like flames on a burning log. The pose, known as the flying gallop, has both the front and back legs extended. In this particular case both sets of legs are carved in the same pose.

The saddle bag hanging behind the saddle is adorned with grape leaves and grapes. There is also a leaf decoration under the cantle. Use colored rhinestones for the jewels adorning her trappings. This carving has many openings to drill out before carving; be sure to drill undersized, to leave room for the carving.

With these four horses, you have a good start on a nice carousel carving collection. In the next issue we will present the patterns for some of the menagerie animals. [PW]

Full-Size Pattern




"Lillie Belle" – C. W. Parker, 1914

Woodworker's Supply

OF NEW MEXICO


"Where the experts buy their tools"

PW9



FREUD THIN KERF BLADES
24T \$44.95
60T \$54.95

803-373	10" x 24T	\$44.95
803-394	10" x 60T	\$54.95



MARKING AND MORTISE GAUGE
MG-009 Rosewood marking gauge \$19.75



QUALITY CHISEL SETS
Boxwood handles and chrome vanadium blades for durability.

WC-106	Six-piece set (1/4"-1")	\$39.95
WC-110	Ten-piece set (1/4"-1 1/4")	\$69.95



BOSCH'S 3 HP PLUNGE ROUTER NOW WITH VARIABLE SPEED

806-105	110V variable	\$289.95
806-112	220V variable	\$309.95
802-021	110V	\$239.95
802-022	220V	\$264.50



BOSCH JIG SAWS

801-167	1581VS	\$142.50
801-169	1582VS	\$142.50



OUR #1 SELLING TOOLS

108-100	PC 330	\$ 64.50
108-102	PC 505	\$124.50

Packages include sander, dispenser, 120 grit and 80 grit Stikit paper

800-125	PC 330 package	\$108.00
800-126	PC 505 package	\$165.00



PORTER-CABLE'S NEW CORDLESS
802-425 #9850 \$159.95




POWERFUL VSR DRILL REACHES CORNERS

800-450	#8005, 3/8", 2,500 RPM	\$129.95
802-089	#8000, 3/8", 1,300 RPM	\$129.95
802-090	#8050, 1/2", 750 RPM	\$165.00



RYOBI 2-1/4 HP PLUNGE ROUTER

777-802	R-501 (trigger)	\$169.95
802-088	R-500 (lock on)	\$189.00



RYOBI 10" MITER BOX

801-862	With LU85	\$249.00*
801-228	With steel blade	\$199.00*

*FREE delivery in 48 states

DELTA MACHINERY PRICE GUARANTEE

LOWEST MACHINERY PRICES FOR ONE FULL YEAR:


Price shopping for machinery makes sense, but it can mean delaying your purchase of a needed machine while you spend days or weeks checking the prices.

WITH OUR LOWEST MACHINERY PRICE FOR ONE YEAR guarantee, you can order now with the confidence you are getting the best price. You have a full year to shop for a better price. Should you find the machine advertised for less... we'll match it. We know you can't beat these sale prices anywhere.

If you purchase a stationary machine during this sale and find an advertised price for the same machine that is better (including freight, merchandise certificates, free goods and applicable taxes) within one year of the date of your purchase, simply send us the advertisement and a copy of our invoice to you and we'll reimburse you for the difference. As a customer of Woodworker's Supply, your complete satisfaction is important to us. We want you to remain a loyal customer.



DELTA 10" CONTRACTOR'S SAW
GET 2 FREE FREUD THIN KERF BLADES
34-410 10" con- tractor's saw \$699.00*



CALCULATOR HANDLES FRACTIONS TO 1/64" AND MORE
Construction Master II has roofing, metric, circle, volume functions. Pocket Handyman handles 90% of "in-shop" calculations.

805-615	Construction Master II	\$79.95
805-476	Pocket Handyman	\$39.95



TWENTY-FOUR-PIECE CARVING SET
Every tool you'll need. Wooden case included. Oak handles, burnished chrome vanadium blades.


801-017	24-piece carving set	\$299.95
---------	----------------------	----------



DELTA 14" BANDSAW
1 HP NOW AVAILABLE
ALL DELTA BANDSAWS COME WITH MOTOR, STAND, LIGHT AND 3 FREE BLADES

801-118	1/2 HP	\$499.00*
801-596	3/4 HP Baldor	\$559.00*
805-979	1 HP Baldor	\$599.00*
805-944	Mobile base	\$109.95
806-538	1 HP Baldor motor only	\$189.95

MOBILE BASE AVAILABLE



DELTA 16" DRILL PRESS
Get a seven-piece Forstner bit set FREE — \$59.95 value.

17-900	16" drill press	\$359.00*
--------	-----------------	-----------



DELTA 14" DRILL PRESS
Get a seven-piece Forstner bit set FREE — \$59.95 value.

11-950	14" drill press	\$269.00*
--------	-----------------	-----------

*FREE delivery in 48 states



DELTA'S SANDER/GRINDER

31-050	1" x 30" sander/grinder	\$79.95
801-542	1" x 30" belts Starter Set 2 ea. 80, 100, 120, 220	\$7.90
	1 ea. 400 grit	



DELTA 6" PRECISION JOINTER
A new advanced design that offers more precision and easier operation.

801-592	Delta DJ-15 6" jointer	\$1099.00*
801-363	Mobile base	\$ 109.95

*FREE delivery in 48 states

1-800-645-9292

8:30-5:30 MT
Mon.-Fri.

Yo-Yo

by John A. Nelson

Here is a classic toy to make for your son or daughter—and one that's not made of plastic as most are today. Commercial yo-yos are made of three pieces; this one is turned from only one piece.

Not being a yo-yo expert, I would suspect you could modify this design slightly and experiment with the many variables. After I built this one, I found myself wondering if it would function better if the center shaft was increased somewhat from the $\frac{5}{16}$ " diameter to perhaps $\frac{1}{2}$ " diameter or larger. Perhaps the outside $2\frac{1}{2}$ " diameter could be reduced to $1\frac{3}{4}$ " or so.

Either way, this makes an interesting woodturning project. You can paint it with colors and designs of your choice.

The yo-yo requires a blank $2\frac{3}{4}$ " thick $\times$ 3" square, and it is simply turned between centers. Using a parting tool, cut the groove for the string. Taper the gap between inside surfaces of the groove from $\frac{1}{4}$ " down to $\frac{1}{8}$ " as shown.

To add the detail on the edge of the yo-yo, use the corner of a tool to make a thin groove. Take a two-foot length of wire and hold it into the groove until it gets hot and burns the groove. This technique adds a nice effect and can be used in many other woodturning projects you do.

Paint the yo-yo any design you wish or use a clear finish. The illustrated design is only a suggestion. Lay it out with a compass. Add a coat of high-gloss varnish over the entire yo-yo before you add the string.

Drill a $\frac{1}{16}$ " diameter hole through the center $\frac{5}{16}$ " diameter shaft. You might want to experiment with different kinds and thicknesses of string—I found that some strings worked better than others did.


Now you can be the "yo-yo man" in your town! **PW**

John A. Nelson is a woodworker and drafting instructor from Peterborough, New Hampshire, and the author of *How to Build a Grandfather Clock* (TAB Books, Monterey Lane, Blue Ridge Summit, PA 17214).

illustration by the author



Deborah Porter




CLASSIFIED MARKET

TOOLS

WHITTLING & CARVING HAND/POWER TOOLS BOOKS
STONES, WOOD, AND SUPPLIES

WARREN TOOL Co., Inc.



RT. 1 BOX 14A DEPT. PW
RHINEBECK, NY 12572
(914) 876-7817

SEND \$1.00
FOR CATALOG

DUST COLLECTORS. All equipment American made. 550CFM totally enclosed motor \$295. 4-inch blast gates \$12.75. Adjustable roller stand \$29.95. Collector fittings of all types. Dealers inquire, call for brochure. MCPI, P.O. Box 8025, Kansas City, MO 64129 (816) 861-4126

CARBIDE ROUTER BITS • UNIQUE OPPORTUNITY Inventory Clearance. Supply Very Limited. Send Self-Addressed Stamped Envelope For Details. Skycraft Tools, Attn: John Felds, P.O. Box 418 P, Myersville, MD 21773

Repair band saw blades in less than two minutes with the

**ELECTRO
BAND SAW BRAZER
#101B**

Do inside contour sawing easier and faster. Make your own band saws from coil stock. Brazers complete with kit \$75.50

Mfrd. by

NELSON & JACOBSON, INC.

3546 NO. CLARK ST., CHICAGO, IL 60657



HOBBYISTS Improve your **METAL LATHE** with the ultimate tool-post system! KRF, Box 783C, St. Joseph, MI 49085. (616) 429-7050

CUSTOM BRANDING IRONS. 250-800 watts drill press or hand-held. In-house branding and parts marking. Brochure \$1.00. **ENGRAVING ARTS, P.O. Box 787A, Laytonville, CA 95454.** (707) 984-8203 Fax (707) 984-8045.

BOOKS & CATALOGS

FREE ILLUSTRATED CATALOG of books for woodworkers: instructions, scaled drawings, patterns for furniture, toys, house carpentry, duck decoy, bird and figure carving, chip carving, wood sculpture, lathe work, more. Most \$4.00 to \$6.00. Write: **DOVER PUBLICATIONS, Dept. A226, 31 E. 2nd Street, Mineola, NY 11501**

The HAMMER DULCIMER BOOK



\$19.95 How I Build The Things by Charlie Alm

Book describes step-by-step how to build a hammer dulcimer. Many tips and illustrations. Helpful to novice and professional.

**Woodworks
P.O. Box 218
Brookston, IN 47923
(317) 563-3504**

Check or Money Order
VISA and MasterCard

1-5pm, M-F

WOODS

SPALTED, QUILTED, AND CURLY MAPLE, boards and blocks, clock and table burls, Alaskan yellow cedar for carving and boats, **RANDLE WOODS, P.O. Box 96, Randle, WA 98377.** (206) 497-2071

HARDWOOD LUMBER, kiln-dried, large variety of species in several thicknesses and grades. Flooring, paneling, finishing supplies. No minimum order, size selection available. Call or send stamp for listing. Garreson Lumber, RD#3, Dept. G, Bath, NY 14810. (607) 566-8558

DOWELS - PLUGS - PEGS

Manufacturer Direct
Largest and finest selection of Oak, Walnut, Hickory, Maple, Cherry, Mahogany, Teak, even Treated Dowels
Quantity Discounts

MIDWEST DOWEL WORKS, INC.

4631 Hutchinson Road
Cincinnati, OH 45248
(513) 574-8488



Catalog on request

PLANS AND KITS

105 LAWN ORNAMENTS! Full size patterns! Enjoy creating animals, birds, flowers and other lawn and garden decorations. Only \$5.95. Craftmasters, Box 8133 (PW67), West Chester, OH 45069.

WOODEN CARS, SIMPLE, SAFE FOR CHILDREN. Five patterns for five dollars. Send money order to Friedli Enterprises, 1941 San Diego Ave., Ramona, CA 92065.

CHILDREN'S FURNITURE plans and instructions. Introductory offer 5 plans for \$4.95: desk, table and chair, toy chest, rocker and cradle. All others 1/2 price, many to choose from. Backyard play center \$3.95. Money back guarantee. Catalog \$1.00 refundable. **JOSEPHS, P.O. Box 8308, Turnersville, NJ 08012.**

THE ONIT

Plan No. 210 - Only \$11.50
Make this Classic American Chair.
Ironing Board, & Step Ladder with
full size, easy to follow plans.

Money Back Guarantee!
Gold Country Woodworks Dept. PW
1615 Wimbledon Dr., Auburn, CA 95603



VICTORIAN GINGERBREAD! 20 Authentic patterns \$7.95, brochure \$1.00. Smart Designs, P.O. Box 112 Dept. PW, Hanford, CA 93232

SILHOUETTES—Over 400. 30 plus topics. Horses, Country, Old Time, Dogs, Holidays, Western, Mother Goose, etc. For decor, signs, scenes, whatever. With directions. Moneyback guarantee. \$10.00 postpaid. Geecraft, Box 391-P, Blue Earth, MN 56013

PLANS, LAWN/PATIO FURNITURE, Workbench, Kids'Toys, Etc. Catalog \$1.00, Box 908, Cornville, AZ 86325

DUTCH WINDMILL! Over five feet tall including blades. Accent any yard/garden! Patterns PLUS woodcraft catalog \$7.00. **ACCENTS (DR-69), Box 7387, Gonic, NH 03867**

ROUGHED OUT BLANKS, 35 different 80% roughed out basswood blanks of birds, animals, and characters. Also supplies. Free brochure with SASE to West Falls Woodcarving P, 7458 Ellicott Road, West Falls, NY 14170, (716) 662-3648

SUPER WOODCRAFT PATTERNS windmills, wells, vanes, whirligigs, bird houses, jigsawing for fun or profit. Catalog \$1. **CRAFTER'S, 11840 North U.S. 27, Dewitt, MI 48820.**

BOAT KITS—PLANS—PATTERNS—250 designs 6'70" Powerboats, Sailboats, Houseboats, Hydroplanes, Dinghies, Duckboats, Canoes, Kayaks, **CATALOG \$3.00** (Book "Amateur Boatbuilding" \$6.00) Clarkcraft, 16-833 Aqualane, Tonawanda, NY 14150

WOOD SUPPLIES WHOLESALE: Shaker pegs, candle cups, hearts, dowels, toy parts, free catalog. Rainbow Woods, 20 Andrews St., Newnan, GA 30263

CUSTOM TIMBER FRAME BUILDING PLANS. Drawn including all framing details. Experienced with all type houses. Call Paul (510) 623-8258 or write: **AP&B, 210 Fontana Rd., Hot Springs, AR 71901**

PLANS FOR 300+ TOOLS Catalog \$1.00 (refundable) Wood-Met Services, Dept. PW, 3314 Shoff Circle, Peoria, IL 61604

COMPLETE SET OF PLANS AND BLUEPRINTS for a classic rolltop desk. Build one just like Grandpa had. A woodworker's delight. \$9.95 R&D Publishing, Box 271, Lawndale, NC 28090

ADIRONDACK CHAIR & MATCHING BENCH Attractive, durable, perfect for yard/patio. Full size patterns PLUS woodcraft catalog \$7.00. **ACCENTS (AR-69), Box 7387, Gonic, NH 03867**

WEEKEND WOODWORKER 8 easy, full scale patterns. Convenient removable pages. Order now. Only \$4.95. R&D Publishing, Box 271, Lawndale, NC 28090



100 LAWN & GARDEN ORNAMENTS

Create decorative and profitable wooden yard animals, birds, butterflies, whirligigs, signs and more! Our most popular yard designs PLUS decorative alphabet.

Over 100 full size patterns only \$7.00

Catalog of 1000 patterns \$2.00 (Free with order)

ACCENTS Dept. GR69, Box 7387, Gonic, NH 03867

PLANS FOR BEAUTIFUL WOOD DISPLAY STEAM LOCOMOTIVES Send \$1 for descriptions and prices. Steamer Plans, Dept. W, 4341 Avon, Independence, MO 64055

CLASSIFIED MARKET

SIMPLIFIED PLANS for wooden-gear, weight-driven, pendulum regulated clock. \$10.00.
BOB MEYER, Rt.1, Box 275, Elgin, MN 55932

MISCELLANEOUS

SPRAY-ON SUEDE LINING: Finish any project with a soft touch. Free Brochure with sample. DonJer Products, Ilene Court-Bldg. 8G, Bellemead, NJ 08502, (800) 336-6537

FINE WOODWORKING PROGRAM. One-year comprehensive course in fine furniture and cabinet-making. **GUITAR BUILDING PROGRAM.** Four-month course in instrument construction. Nationally accredited. Financial aid available. Free brochure. **ROBERTO-VENN SCHOOL OF LUTHIERY, 4011 S. 16th St., Phoenix, AZ 85040. (602) 243-1179.**

PROFESSIONAL STAINED GLASS just \$3/copy
If you work with stained glass, this monthly magazine will be your bible. Techniques, projects, lush color photos, tool evaluation and analysis by experienced professionals. \$25/year (12 issues). Satisf. guaranteed \$50,000 in awards for new work. Order from:
Professional Stained Glass
245 West 29th St., Dept. Q-4, New York, NY 10001

Door Harp Parts Same Day Service

Tuning Pins: 100 for \$18.00, 500 for \$75.00
Wire: 25 ft. for \$2.50, 350 ft. for \$15.00
Wood Balls 3/4" 100 for \$8.00, 500/\$30.00
Visa & MC (516) 462-6228 Catalog \$1.00
Shipping charge \$2.50 NY Res. add tax
ARMOR Box 445, East Northport, NY 11731

INFORMATIVE 192 PAGE CATALOG for woodworkers, woodcarvers, upholsterers, antique restorers, including many unusual, hard-to-find items. Send \$1.00 to Van Dyke's, Dept. 50, Woonsocket, SD 57385.

World's Largest Selling Glue Gun!
Supertack Hot Melt Glue & Guns
Buy the best at below wholesale. Free glue samples - Free Freight.
Translucent Sticks 1/2" Diameter 4" or 10" Length.
PRICES - delivered (West Coast add 20¢/lb.)

SUPERTACK 3000 STICKS		PRO-90 TRIGGER GUN	
5 lb.	\$25.00	1-	\$18.00 each
10 lb.	\$43.50	2-3	\$17.00 each
25 lb.	\$98.75	4-6	\$16.00 each
50 lb.	\$182.50	7-12	\$15.00 each
		13-24	\$14.00 each

Supertack SANDPAPER
HIGH QUALITY • DISCOUNT PRICES • FREE FREIGHT most areas
BELTS: BEST RESIN OVER RESIN, "X" WEIGHT 10/Box

1 x 42	\$0.70 ea.	4 x 36	\$1.15 ea.
3 x 21	.75	6 x 48	2.65
3 x 24	0.80	6 x 89	4.75
4 x 24	0.90		

Prices quoted 80 grit, other grits available
ADHESIVE CLOTH DISCS: BEST RESIN, OVER RESIN BOND, "X" WEIGHT

5" Diameter	\$0.70 ea.	9"	\$1.45 ea.
6"	.80	10"	1.60
8"	1.15	12"	2.00

Prices quoted 80 grit, other grits available.
CABINET PAPER - BROWN
40 Grit 50 PK \$16.00
60 Grit 50 PK 14.00
80 Grit 50 PK 12.00
100, 120, 150, 100 PK 21.00
180, 220 100 PK 18.00
WET/DRY PAPER - BLACK
180 thru 1200 100 PK \$22.00
NOLOAD PAPER - WHITE
180 thru 400 100 PK \$19.00
Also Shop Rolls • Garnet & Cloth Sheets
CLEANING STICKS \$3.50 Small \$6.50 Large
RED HILL CORP. P.O. BOX 500, BIGLERVILLE, PA 17307
CALL TOLL FREE - 1-(800) 822-4003 or (717) 337-1419
Minimum Order \$25.00 • PA Res. Add 6% • FREE CATALOGUES

MARINE CARVING, Boatbuilding, Seamanship and More. Summer workshops July 31-Aug 11. Call or write for brochure: The Rockport Apprenticeship, Box 539P, Rockport, ME 04856 (207) 236-6071

18 NOTE REUGE MUSICAL MOVEMENTS and accessories. Send SASE for information to: WOODSMITHS, 128 Henry Road, Enola, PA 17025.

BUILDING? RESTORING? REPAIRING? Use Chem-Tech, the epoxy glue professionals use. Strength and reliability proven in boats and aircraft over 15 years. Introductory Offer: 1/2 pt. T-88 Epoxy Glue only \$9.95 ppd. USA. Orders shipped within 48 hrs. Technical staff on call to answer your questions. Chem-Tech, Dept. PW, 4669 Lander Rd., Chagrin Falls, OH 44022. (216) 248-0770.

BASKET WEAVING AND CANING SUPPLIES. Large selection weaving materials books, hoops, handles, tools, and misc. Retail and wholesale. Catalog \$1. Refundable. **ROYALWOOD LTD. 517-PW, Woodville Road, Mansfield, OH 44907**

BUSINESS OPPORTUNITIES

IDEAL WOODWORKING BUSINESS. Unusual Money Maker. Work Home. Free Brochure. Pine-Co, 897-3 Mammoth, Manchester, NH 03104.

MAKE MONEY WITH YOUR WOODWORKING. Book shows you how. Covers different kinds of selling, pricing, credit, getting started. \$5.00 Satisfaction Guaranteed. In Print, Box 687PW Farmingdale, NJ 07727

LET THE GOVERNMENT FINANCE your wood-working business. Grants/Loans to \$500,000 yearly. Free recorded message: (707) 448-0270 (KC1)

WOODWORKING INSTRUCTOR to teach and reside at summer camp for teenagers in New Milford, Connecticut, July-August 1989. **BUCK'S ROCK, 140 Riverside Drive, New York, NY 10024. (212) 362-2702.**

WOOD TOY
toys and joys
Box 628-P
Lynden, WA 98264


- * Patterns - Parts - Wheels
- * Executive Toys
- * Send \$1 for new catalog and receive coupon for wheels & axle pegs.

POST OFFICE BOX BRONZE DOORS; No. 1 \$5.00; No. 2 \$6.00; No. 3 \$8.00, plus \$1.00 each shipping. SASE: Hubbert Woodcrafts, P.O. Box 1415, Fletcher, NC 28732. (704) 687-0350.

CLASSIFIED MARKET INFORMATION:
Classified Display: \$60.00 per inch for 1 issue, \$50.00 per inch for 6 time rate (6 consecutive issues); **Classified Rate:** 95 cents per word; 15 word minimum. Payment must accompany all Classified ads (not commissionable). Deadline for Issue 50 (Aug. '89) is June 1, 1989. **Popular Woodworking, 1300 Galaxy Way #8, Concord, CA 94520, (415) 671-9852.**

Index to Advertisers

Brown Wood Products	76
Clayton Enterprises	7
Daniel's Discount Tools	15
Dollar Trading Corp.	14, 18
Dietrich's Dyna-Vent	12
Econ-Abrasives	7
Forrest Manufacturing Co.	17
Freud USA	88
Grizzly Imports	2, 87
Highland Hardware	76
Leichtung Workshops	12
Lignomat USA	14
MLCS Ltd.	10, 13
Oldham-United States Saw	7, 8
Pacific Brass Hardware	76
Rodman	13
Skycroft Tools	7
Seyco Sales	76
Specialty Furniture Designs	7
Tampa Wood	76
Total Shop	19
Transpower (TCM)	17
Truly Persnippity	13
Watco-Dennis	12
West Coast Veneer	7
Wilke Machinery	11
Wood-Ply	75
Woodworkers Supply of NM	82



Out of the Woodwork

by Bob Laney

Packratting

I recently ran across an article in a magazine on the phenomenon of packratting—the tendency of some people to acquire and stockpile items which may or not have value, in quantities beyond reasonable amounts. When I showed this to my wife, she suggested, not subtly, that woodworkers may be prone to the temptation to packrat much the same way that those who work in bars are subject to the temptation to drink (and all too often succumb). Upon further discussion, it became clear that she actually felt that *I* could be described as one afflicted with this tendency, and furthermore, that the state of my shop attested to this fact.

Upon hearing this, I was stunned. I immediately took my wife on a tour of my shop, with the intention of dispelling the

Bob Laney is a woodworker in Hendersonville, North Carolina.

notion that I could possibly be described as one with the packrat virus. I now take you on this same tour, knowing that an audience of woodworkers is bound to be more knowledgeable and understanding than she was.

The first thing we come across as we enter is the pile of 1 × 8's in the middle of the floor. These are not only carefully stickered and supported off the floor, but are also of obvious value and not really in the way once you get used to stepping over them. I must admit that the lumber rack, where these pieces might have gone, is full of what some might view as an odd collection of bits and pieces, but these too have obvious value to the trained eye.

Looking up, we see the maple branches left from pruning the season before last; these will go with the pieces of carbon steel in the box behind the metalworking vise to make some neat

carving tools when I get the chance.

Now, here is some good spare door hardware. Over the years I've replaced numerous locks for friends, relatives, and myself. These strike plates are good brass-plated steel; try buying just a strike plate sometime!


That box under the bench is a quarter-gross of English Whitworth bolts complete with nuts which once secured motorcycles in their shipping crates. These, believe it or not, were going to be simply thrown out by a motorcycle dealer when I came across them! That was twenty years ago, and I've already used three of them in a jig I built a few years back.

That's the chassis of a riding lawnmower back there at the rear of the shop. All it needs are some wheels to make it a sturdy shop cart. Or perhaps the rear axle with its sprockets and bearings could be the basis for some clever home-engineered machine I could well get around to designing. I've had a number of ideas in the seven years since I got it.

Some people actually toss out plywood cutoffs. I'm not talking about quarter sheets and the like; even the dullest imagination could see possible uses for large, regularly shaped pieces. It takes real creativity, however, to see to what use a piece of 1/2" CDX, shaped like Brazil or some internal organ, could be put someday.

Here are some containers that hardware and tools came in. That's pipe and angle stock overhead. I don't like to brag, but I spent a day-and-a-half designing the brackets that hold those short pieces of pipe and L-metal between the joists. It was tricky, especially trapping the ones less than a foot long.

So, as you can see, everything in my shop has a clearly designated use, and I could hardly be described as a packrat. When dealing with non-woodworkers, though, I've decided it's wiser not to call attention to cleverly salvaged items until they're put to use; otherwise, they are too often seen as mere junk by those lacking imagination and foresight. It is this lack, I believe, that has given rise to the packrat myth. **PW**





MIRROR, MIRROR ON THE WALL, WHY IS GRIZZLY THE BEST MAIL ORDER HOUSE OF THEM ALL

GLANCE BELOW & SEE WHY!

MINI DUST COLLECTORS




The Lowest Price
IN U.S.A.!

This portable dust collector is the answer to the small shop mess. Motor draws 8 amps and unit weighs 77 lbs.

MODEL G1031

ONLY \$169⁹⁵ Prepaid To You

15" SCROLL SAWS



Cuts up to 2" thick material. Table tilts 45° and table size is 7⁷/₈"x17".

MODEL G1572

ONLY \$99⁹⁵ Prepaid To You

BRAD POINT DRILL SETS



7 Pc. set in pouch or 25 Pc. set in metal case.

7 Pc. set contains 1/8" to 1/2" by 1/16 increments.

MODEL G1834

ONLY \$6⁹⁵

25 Pc. set contains 1/8" to 1/2" by 1/64 increments.

MODEL G1835

ONLY \$27⁵⁰

Both Sets Prepaid To You!

MULTI-STOP



Precisely position repeat cuts on Radial Arm saws and other machines. MADE IN U.S.A.!

MODEL G1821

ONLY \$27⁵⁰ Prepaid To You

CLAMPING MITRE-GAUGE



A very handy device that holds the work-piece in place when cutting.

MODEL G1822

ONLY \$29⁹⁵ Prepaid To You

RGT HANDLER



Safely & accurately cut, shape, route and joint pieces as small as 1" with this jig.

**Introductory Price
MODEL G1771**

\$29⁹⁵ Prepaid To You

LATHE CHISELS




This professional 8 Pc. set is made of carbon steel and heat-treated to 60° Rockwell.

Overall length is 15 1/4" each.

MODEL G1089

ONLY \$29⁹⁵ Prepaid To You

INCRA JIG



Make intricate dovetails, finger-joints, etc... with this amazing jig.

**Introductory Price!
MODEL G1768**

\$29⁹⁵ Prepaid To You

TEMPLATES FOR INCRA-JIGS

Designed to fit in the auxiliary slot of the Incra-Jig, all calculations on your part are eliminated! Set of 6 templates for making dovetails and finger-joints.

MODEL G1832

ONLY \$14⁹⁵ Prepaid To You

WOOD VISES



Heavy duty cast-iron construction with quick setting feature. G1091 opens 8", G1092 opens 10".

G1091 — \$42⁵⁰

G1092 — \$59⁹⁵

Both prepaid to you

PANTOGRAPH




Enlarge or reduce images right on the wood accurately. Comes with a scribe point & lead. Made in Japan.

MODEL G1731

\$18⁵⁰ Prepaid To You

THE INCREDIBLE "SHOPHELPER" ANTI-KICK DEVICE



Sold elsewhere for \$89.95

MODEL G1630

\$49⁹⁵ Prepaid to you

ALSO AVAILABLE: Model G1578
Green shophelpers for shapers! Used as hold downs, these green shop helpers are very popular with shaper owners.

Only \$49.95 Prepaid to you

Price Breakthrough!

DOWELLING JIG



You've read about it, you've heard about it—THIS IS ONE DYNAMITE JIG!


REGULARLY \$49.00

MODEL G1662

ONLY \$34⁹⁵

Both prepaid to you

7-PC. TAPERED COUNTERSINK SET



Predrill holes for woodscrews easily and correctly the first time! This very high quality set is made in Japan.

MODEL G1728

\$39⁹⁵ Prepaid To You

We have the most courteous operators and the fastest shipping crew in the world! You place the order and before you hang up the phone, UPS is knocking on your door — well almost!

CALL TOLL FREE (FOR ORDERS AND CATALOG REQUESTS ONLY)

EAST OF THE 1-800-523-GRRR
MISSISSIPPI: (717) 326-3806

← (For Orders & Catalogs Only) →
← (For Inquiries & Customer Service) →

WEST OF THE 1-800-541-5537
MISSISSIPPI (206) 647-0801

New Safety Dado

Improved Design. Effective Control.

The Freud Difference

Advanced CAD System. The Computer-Aided Design System simulates actual cutting conditions in three dimensions and records the blade performance. This allows Freud engineers to electronically vary the material being cut and the blade's physical characteristics, developing saw blades that provide optimum cutting performance.

Laser Technology. A computer-controlled, 500-watt laser is used in the production of Freud cutting tools. The concentrated beam of light creates a perfectly round blade, produces shoulders identical in shape and size, and precisely centers the arbor hole. In addition, expansion slots are strategically placed to allow for heat dissipation during brazing and blade body expansion during actual use.

Superior Carbide. The chemicals used to produce and bond materials like composition boards, melamine, MDF and plastic laminates will attack carbide and cause it to corrode. Freud's engineers developed a special mixture of titanium, cobalt and tungsten carbide to significantly reduce this corrosive problem.

Titanium is used to protect the cobalt and tungsten carbide from chemical corrosion, ensuring a longer lasting carbide edge.




The right degree of hardness is another important property of carbide life. This difficult problem is solved by using carbon and tungsten powders with a grain size of 0.8 microns. Freud carbide is 33% more dense than the standard 1.2 micron size found in the carbide of other manufacturers.



Freud Micrograin Carbide



Standard Carbide



Old shoulder style (behind) compared to new safety shoulder style (front)

Freud Dado Head Puts You in Control.

The secret is the shoulder. It is in front of every tooth and it limits the tooth's bite. Since each tooth removes a very small chip (.2mm), you are in control. There is almost no climbing. Almost no chance of kickback. This is the key to a safer dadoing experience.

Freud's improved dado head does not compromise results either! It cuts a smooth square bottom. The tear-out is virtually non-existent, even when dadoing problem materials. Get control of your work, put Freud's new dado head on your saw!

Stock Number	Diameter	Teeth	Max. Groove	Inside Chippers
SD 306	6 inches	24	13/16"	(4) 1/8" & (1) 1/16"
SD 308	8 inches	24	13/16"	(4) 1/8" & (1) 1/16"
SD 310	10 inches	36	13/16"	(4) 1/8" & (1) 1/16"
SD 312	12 inches	36	13/16"	(4) 1/8" & (1) 1/16"

Call for the name of your local distributor.



Makes radial arm saw dadoing safer



Storage case comes standard

freud®

218 Feld Ave. High Point, NC 27264

(919) 434-3171